

The University of Iowa

Iowa City, Iowa 52242

RECEIVED NOV 22 1982

11/18/82
N.

University Hygienic Laboratory

(319) 353-5990



1847



18 November 1982

E.A. Hickok and Associates
545 Indian Mound
Wayzata, MN 55391

Attn: Mr. George Boyer

Dear George;

The attached results are the ones reported to you on 12 November 1982 by telephone.

Sincerely,

Armand F. Lange, Ph.D.

Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

lm

cc: Dr. Splinter
Dr. Hahne
Ms. Cain
Mr. Brewer
File

9626717

RECEIVED OCT 18 1982

• University Hygienic Laboratory

(319) 353-5990



1847

13 October 1982

E. A. Hickok and Associates
545 Indian Mound
Wayzata, MN 55391

ATTN: Mr. George Boyer

Dear George:

Attached are the results of the PNA analyses of the samples received from Frank Matthews on 15 September 1982.

Sincerely,

Armand F. Lange, Ph.D.

Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

CMW

cc: Dr. Splinter
Dr. Hahne
Ms. Cain
Mr. Brewer
File

DEPTH TO INLET 801'


9626718

EUGENE A. HICKOK IDENTIFICATION		5122 (W23) 11/4/82 Time 0 FIG OHL# 2-4158 µg/L	5123 (W23) 11/5/82 Time 22 IG OHL# 2-4159 µg/L	Reagent Blank µg/sample
Sample	Compound			
117	2,3-Dihydroindene	15	33	<1
115	Indene	8	75	<1
128	Naphthalene	<1*	480	<1
134	Benzo[b]thiophene	2	32	<1
129	Quinoline	<5	<5	<1
142	2-Methylnaphthalene	3	100	<1
117	Indole	<1	<1	<1
142	1-Methylnaphthalene	66	80	<1
154	1,1'-Biphenyl	29	30	<1
152	Acenaphthylene	18	33	<1
154	Acenaphthene	54	68	<1
166	Fluorene	100	65	<1
178	Phenanthrene	180	100	<1
178	Anthracene	65	14	<1
179	Acridine	4	5	<1
179	Phenanthridine	1	<1*	<1
167	Carbazole	9	27	<1
202	Fluoranthene	150	23	<1
202	Pyrene	120	19	<1
228	Benzo[a]anthracene	14	2	<1
228	Chrysene	15	1	<1
252	Benzo[b]fluoranthene	9	<1*	<1
252	Benzo[k]fluoranthene	10	<1*	<1
252	Benzo[e]pyrene	10	<1*	<1
252	Benzo[a]pyrene	18	<1*	<1
252	Perylene	2	<1*	<1
276	Indeno[1,2,3-CD]pyrene	4	<1*	<1
278	Dibenz[a,h]anthracene	4	<1*	<1
276	Benzo[ghi]perylene	5	<1*	<1

*Compound present, but below quantitation limit

9626-19

545 Indian Mound
Wayzata, Minnesota 55391
(612) 473-4224



October 21, 1982

Mr. Mike Hansel
Regulatory Compliance Section
Solid and Hazardous Waste Division
Minnesota Pollution Control Agency
1935 West County Road B2
Roseville, Minnesota 55113

Re: St. Louis Park Well Abandonment Program


Dear Mr. Hansel:

Enclosed herewith are the results of the samples taken during the September 13, 1982 pumping test. The pump inlet was at a depth of 801 feet.

The pumping test was abandoned after four (4) hours because the packer was leaking. The pump was removed and reset and a pumping test run on September 17, 1982. The samples taken during this pumping test will be forwarded to you shortly.

Sincerely,

EUGENE A. HICKOK AND ASSOCIATES


George W. Boyer, P.E.
Vice President

bt

Enclosure

9626720

		OW 23;	Formation MS;		9-13-82		Time 4:00 (Duplicate GC/MS run)		9/17/82
F. A. Hickok & Associates Identification		Time 0:00	Time 0:30	Time 1:00	Time 2:00			5:15 MS	
UHL #		2-3289	2-3290	2-3291	2-3292	2-3293	2-3293	2-3293	
Q m/e	Compound								
117	2,3-dihydroindene	15	12	5.0	3.2	3.9	4.1		34
115	Indene	42	37	6.9	3.5	4.1	5.0		190
128	Naphthalene	400	420	<1**	<1**	<1**	<1**		3000
134	Benzo[b]thiophene	15	12	4.3	3.1	2.6	2.7		58
129	Quinoline	<1	<1	<1	<1	<1	<1		<10*
142	2-methylnaphthalene	560	440	<1**	1.8	<1**	<1**		2300
117	Indole	<1	<1	<1	<1	<1	<1		<10*
142	1-methylnaphthalene	310	260	25	14	9.2	9.4		1500
154	1,1'-biphenyl	120	86	7.6	4.7	3.4	3.7		350
152	Acenaphthylene	390	230	18	8.4	5.7	6.1		780
154	Acenaphthene	320	170	22	13	8.6	9.5		850
166	Fluorene	530	490	28	17	9.0	10.1		1900
178	Phenanthrene	2,500	2,100	38	21	7.6	8.2		3500
178	Anthracene	590	460	17	10	2.8	3.2		1400
	Acridine	29	18	3.3	1.8	<1**	1.0		110
179	Phenanthridine	34	25	1.6	<1**	<1**	<1**		40
167	Carbazole	28	18	<1**	<1**	<1**	<1**		160
202	Fluoranthene	1,700	1,400	46	21	7.6	8.1		2300
202	Pyrene	1,500	1,200	38	18	6.5	6.8		1900
228	Benz[a]anthracene	680	460	15	8.0	2.3	2.4		1500
228	Chrysene	580	420	12	6.4	3.0	3.0		1200
252	Benzo[b]fluoranthene	530	330	9.7	5.6	2.6	2.8		1000
252	Benzo[k]fluoranthene	330	300	7.1	4.1	2.4	2.4		800
252	Benzo[e]pyrene	310	280	6.4	3.4	1.7	1.8		660
252	Benzo[a]pyrene	570	450	11	6.2	2.5	2.5		980
252	Perylene	85	80	2.2	1.8	<1**	<1**		250
276	Indeno[1,2,3 CD]anthracene	290	200	6.4	2.9	1.7	1.6		300
278	Dibenz[a,h]anthracene	81	43	2.0	1.6	<1**	<1**		240
276	Benzo[g,h,i]perylene	310	190	5.9	3.1	1.5	1.5		300

All values in µg/L (PPB)

*Excessive amounts of other compounds present required higher detection limit.

Detection Limit 1 µg/L

Compound detected but below quantitation limits

(Samples at Time 0:00 and 0:30 contained large amounts of sediment.)

9626721

DATE	2/5	8/1	8/1	8/6	8/1	2/6	8/8	8/7			
HOUR						0	8	16	24		
FORMATION	OAK										
PACAGE	LAKE										
DEPTH, INLET		100'	665'	750'	845'	6045'	6045'	8045'			
Q m/e Compound	μg/L	μg/L	μg/L	μg/L	μg/L	μg/L	μg/L	μg/L	μg/L		
117 2,3-dihydroindene	<1	16	14	15	102	12	5	12			
115 Indene	<1	17	21	16	204	32	14	31			
128 Naphthalene	<1	11	72	6	1287	71	52	78			
134 Benzo[b]thiophene	<1	10	13	7	154	9	5	10			
129 Quinoline	<5	<5	<5	<5	<5	<5	<5	<5			
142 2-methylnaphthalene	<1	18	40	17	2241	47	12	25			
117 Indole	<1	2	<1*	2	156	<1*	<1*	1			
142 1-methylnaphthalene	<1	233	42	53	1497	49	16	27			
154 1,1'-biphenyl	<1	23	19	16	788	9	3	8			
152 Acenaphthylene	<1	34	22	22	808	12	8	12			
154 Acenaphthene	<1	326	31	41	1628	26	9	24			
166 Fluorene	<1	263	36	62	1757	26	17	20			
178 Phenanthrene	<1	659	85	114	5249	29	16	22			
178 Anthracene	<1	169	16	37	2004	7	3	4			
179 Acridine	<1	22	5	5	295	<1*	<1*	5			
179 Phenanthridine	<1	11	<1*	1	399	<1*	<1*	<1*			
167 Carbazole	<1	3	12	3	3013	7	4	7			
202 Fluoranthene	<1	428	40	68	4334	14	7	8			
202 Pyrene	<1	291	26	52	3662	12	5	7			
228 Benz[a]anthracene	<1	152	16	21	1748	6	<1*	1			
228 Chrysene	<1	122	12	19	1628	4	<1*	<1*			
252 Benzo[b]fluoranthene	<1	122	11	15	1301	2	<1*	<1*			
252 Benzo[k]fluoranthene	<1	121	7	11	1028	1	<1*	<1*			
252 Benzo[e]pyrene	<1	111	7	11	928	1	<1*	<1*			
252 Benzo[a]pyrene	<1	122	12	16	1498	2	<1*	1			
252 Perylene	<1	37	3	5	506	<1*	<1*	<1*			
276 Indeno[1,2,3 CD]pyrene	<1	72	3	15	1612	1	<1*	<1*			
278 Dibenz[a,h]anthracene	<1	26	1	5	588	<1*	<1*	<1*			
276 Benzo[g,h,i]perylene	<1	68	3	17	944	1	<1*	<1*			

9626722

EUGENE A. HICKOK
IDENTIFICATION

OW23 4977-78 OW23 4979 80
form. lig formation lig
Time 0 10/18/82 Time 24 10/19/82
III # 2-3972 III # 2-3971

11/4/82 11/5/82
0 22
IG IG
GOOD GOOD
688.5 688.5

Q m/e Compound

691 691

117	2,3-Dihydroindene	9	8	15	32
115	Indene	25	20	8	75
128	Naphthalene	150	100	41	480
134	Benzo[h]thiophene	8	7	2	32
129	Quinoline	<5	<5	<5	<5
142	2-Methylnaphthalene	43	15	3	100
117	Indole	<1	<1	<1	<1
142	1-Methylnaphthalene	43	23	66	80
154	1,1'Biphenyl	13	5	29	30
152	Acenaphthylene	14	6	18	33
154	Acenaphthene	36	13	54	68
166	Fluorene	45	13	100	65
178	Phenanthrene	87	23	180	100
178	Anthracene	16	4	65	14
179	Acridine	5	1	4	5
179	Phenanthridine	<1*	<1*	1	<1
167	Carbazole	9	5	9	27
202	Fluoranthene	51	9	150	23
202	Pyrene	44	7	120	19
228	Benz[a]anthracene	12	2	14	2
228	Chrysene	9	2	15	1
252	Benzo[h]fluoranthene	8	2	9	<1
252	Benzo[k]fluoranthene	7	1	10	<1
252	Benzo[e]pyrene	7	1	10	<1
f52	Benzo[a]pyrene	13	2	18	<1
252	Perylene	2	<1*	2	<1
276	Indeno[1,2,3 CD]pyrene	5	<1*	4	<1
278	Dibenz[a,h]anthracene	2	<1*	4	<1
276	Benzo[g,h,i]perylene	4	1	5	<1

*Compound present below quantitation limit

9626723

EUGENE A HICKOK ID: Water OW23 Formation MS Time - 4:30 9-17-82

Q m/e	Compound	2-3893 µg/L	Reagent Blank µg/sample
117	2,3-dihydroindene	34	<1
115	Indene	190	<1
128	Naphthalene	3000	<1
134	Benzo[b]thiophene	58	<1
129	Quinoline	<10*	<1
142	2-methylnaphthalene	2300	<1
117	Indole	<10*	<1
142	1-methylnaphthalene	1500	<1
154	1,1'-biphenyl	350	<1
152	Acenaphthylene	780	<1
154	Acenaphthene	850	<1
166	Fluorene	1900	<1
178	Phenanthrene	3500	<1
178	Anthracene	1400	<1
179	Acridine	110	<1
179	Phenanthridine	40	<1
167	Carbazole	160	<1
202	Fluoranthene	2300	<1
202	Pyrene	1900	<1
228	Benzo[a]anthracene	1500	<1
228	Chrysene	1200	<1
252	Benzo[b]fluoranthene	1000	<1
252	Benzo[k]fluoranthene	800	<1
252	Benzo[e]pyrene	660	<1
252	Benzo[a]pyrene	980	<1
252	Perylene	250	<1
276	Indeno[1,2,3-CD]anthracene	300	<1
278	Dibenz[a,h]anthracene	240	<1
276	Benzo[g,h,i]perylene	300	<1

*Excessive amounts of other compounds present required higher detection limit.

9626724

		OW 23;		Formation MS;		9-13-82		
A. Hickok & Associates Identification		Time 0:00	Time 0:30	Time 1:00	Time 2:00	Time 4:00 (Duplicate GC/MS run)		Reagent Blank
UHL #		2-3289	2-3290	2-3291	2-3292	2-3293	2-3293	
Q m/e	Compound							
117	2,3-dihydroindene	15	12	5.0	3.2	3.9	4.1	N.D.*
115	Indene	42	37	6.9	3.5	4.1	5.0	N.D.
128	Naphthalene	400	420	<1**	<1**	<1**	<1**	N.D.
134	Benzo[b]thiophene	15	12	4.3	3.1	2.6	2.7	N.D.
129	Quinoline	<1	<1	<1	<1	<1	<1	N.D.
142	2-methylnaphthalene	560	440	<1**	1.8	<1**	<1**	N.D.
117	Indole	<1	<1	<1	<1	<1	<1	N.D.
142	1-methylnaphthalene	310	260	25	14	9.2	9.4	N.D.
154	1,1'biphenyl	120	86	7.6	4.7	3.4	3.7	N.D.
152	Acenaphthylene	390	230	18	8.4	5.7	6.1	N.D.
154	Acenaphthene	320	170	22	13	8.6	9.5	N.D.
166	Fluorene	530	490	28	17	9.0	10.1	N.D.
178	Phenanthrene	2,500	2,100	38	21	7.6	8.2	N.D.
178	Anthracene	590	460	17	10	2.8	3.2	N.D.
9	Acridine	29	18	3.3	1.8	<1**	1.0	N.D.
179	Phenanthridine	34	25	1.6	<1**	<1**	<1**	N.D.
167	Carbazole	28	18	<1**	<1**	<1**	<1**	N.D.
202	Fluoranthene	1,700	1,400	46	21	7.6	8.1	N.D.
202	Pyrene	1,500	1,200	38	18	6.5	6.8	N.D.
228	Benz[a]anthracene	680	460	15	8.0	2.3	2.4	N.D.
228	Chrysene	580	420	12	6.4	3.0	3.0	N.D.
252	Benzo[b]fluoranthene	530	330	9.7	5.6	2.6	2.8	N.D.
252	Benzo[k]fluoranthene	330	300	7.1	4.1	2.4	2.4	N.D.
252	Benzo[e]pyrene	310	280	6.4	3.4	1.7	1.8	N.D.
252	Benzo[a]pyrene	570	450	11	6.2	2.5	2.5	N.D.
252	Perylene	85	80	2.2	1.8	<1**	<1**	N.D.
276	Indeno[1,2,3 CD]anthracene	290	200	6.4	2.9	1.7	1.6	N.D.
278	Dibenz[a,h]anthracene	81	43	2.0	1.6	<1**	<1**	N.D.
276	Benzo[g,h,i]perylene	310	190	5.9	3.1	1.5	1.5	N.D.

All values in µg/L (PPB)

* N.D. - None Detected


Detection Limit 1 µg/L

Compound detected but below quantitation limits

(Samples at Time 0:00 and 0:30 contained large amounts of sediment.)

9626725

545 Indian Mound
Wayzata, Minnesota 55391
(612) 473-4224



November 24, 1982

Mr. Mike Hansel
Regulatory and Compliance Section
Solid Land Hazardous Waste Division
Minnesota Pollution Control Agency
1935 West County Road B-2
Roseville, MN 55113

Re: St. Louis Park Well Abandonment Program

Dear Mr. Hansel:

Enclosed herewith please find one (1) copy of the qualitative and quantitative results of the sample taken from Well 23 on October 28, 1982.

If you have any questions please feel free to contact me at 473-4224.

Sincerely,

EUGENE A. HICKOK AND ASSOCIATES

George W. Boyer
George W. Boyer, P.E.
Vice President

bt

Enclsoure

9626713

RECEIVED NOV 21 1982



University Hygienic Laboratory

(319) 353-5990

19 November 1982

E. A. Hickok and Associates
545 Indian Mound
Wayzata, MN. 55391

Attn: Mr. Paul Josephson

Dear Paul:

Attached are the qualitative and quantitative results from the samples submitted on 1 November 1982.

Sincerely,

(Armand F. Lange, Ph.D.)

Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

mrw

Enclosure

cc: Dr. Splinter
Dr. Hahne
Ms. Cain
Mr. Brewer
File

9626714

UNIVERSITY HYGIENIC LABORATORY

EUGENE A HICKOK IDENTIFICATION		OW23 10" casing 10/28/82 Time 0 UHL# 2-4079 ug/L	Blank ug/sample
Q m/s	Compound		
117	2,3-Dihydroindene	220	<1
115	Indene	280	<1
128	Naphthalene	2600	<1
134	Benzo[b]thiophene	160	<1
129	Quinoline	<20 *	<1
142	2-Methylnaphthalene	2500	<1
117	Indole	<20 *	<1
142	1-Methylnaphthalene	1600	<1
154	1,1'-Biphenyl	450	<1
152	Acenaphthylene	200	<1
154	Acenaphthene	1600	<1
166	Fluorene	1700	<1
178	Phenanthrene	4000	<1
178	Anthracene	900	<1
179	Acridine	100	<1
179	Phenanthridine	30	<1
167	Carbazole	230	<1
202	Fluoranthene	1500	<1
202	Pyrene	1300	<1
228	Benz[a]anthracene	400	<1
228	Chrysene	530	<1
252	Benzo[b]fluoranthene	400	<1
252	Benzo[k]fluoranthene	330	<1
252	Benzo[e]pyrene	280	<1
252	Benzo[a]pyrene	470	<1
252	Perylene	70	<1
276	Indeno[1,2,3 cd]pyrene	190	<1
278	Dibenz[a,h]anthracene	210	<1
276	Benzo[g,h,i]perylene	260	<1

*High detection limits due to presence of large amounts of other compounds

9626715

UNIVERSITY HYGIENIC LABORATORY

E.A. Hickok Identification

OW23 10" casing 10/28/82 Time 0

UHL # 2-4080

Compounds Identified

2,3-Dihydroindene	Methylcyclodecane	Biphenylene
Indene	Trimethylbenzene	Methylphthalazinone
Naphthalene	Methyldecane	Naphthalenol
Benzo[h]thiophene	Ethyl-dimethylbenzenes	Methylnaphthalenols
2-Methylnaphthalene	Methyl-2,3-dihydroindenes	[1,1'-biphenyl]-ols
1-Methylnaphthalene	Undecane	Dimethylnaphthol
1,1'-Biphenyl	Ethenyl-dimethylbenzenes	Dibenzofuranol
Acenaphthylene	Phenylpropenal	Methoxy-1,1'-biphenyl
Acenaphthene	Tetramethylbenzenes	Methyl-phenoxybenzene
Fluorene	Tetramethylpentane	Dibenzodioxins
Phenanthrene	Trimethyloctane	Methyldibenzothiophenes
Anthracene	Dimethyldecanes	Methylphenanthrenes
Acridine	Hydroxybenzaldehyde	Methylpyridindolols
Phenanthridine	Methylphenols	Dimethylnaphthothiophene
Carbazole	Ethylphenols	Dimethylethyl-[1,1'-biphenyl]-ol
Fluoranthene	Dimethylphenols	Methylphenylcinnolines
Pyrene	Methylindene	Methylbenzo[c]cinnoline
Benz[a]anthracene	Methoxybenzaldehyde	Phenanthrenol
Chrysene	Trimethylphenols	Benzofluorenes
Benzo[b]fluoranthene	Ethyl-methylphenols	Dimethylbenzo[c]cinnolines
Benzo[k]fluoranthene	Hydroxybenzoic Acid	Dimethyl-1,1'-biphenyl
Benzo[j]fluoranthene	Isofurandione	Methylfluorenes
Benzo[e]pyrene	Diethylphenol	Dihydromethylbenzofuran
Benzo[a]pyrene	Ethyl-naphthalenes	Phenylnaphthalenes
Perylene	Dimethylnaphthalenes	Methylphenanthrenes
Indeno[1,2,3-cd]pyrene	Dimethylbenzofuran	Dimethylphenanthrenes
Dibenz[a,h]anthracene	Cyclopentylbenzene	Ethylphenanthrene
Benzo[q,h,i]perylene	Dihydromethylnaphthalenes	Phenanthroimidazole
Ethylbenzene	Dimethyl-2,3-dihydroindene	Methylpyrenes
Dimethylbenzenes (xylenes)	Tridecane	Terphenyls
Ethenylbenzene	Methylethylnaphthalene	Benzo[b]naphthothiophenes
Nonane	Trimethylnaphthalenes	Cyclopentaphenanthrene
Methylethylbenzene	Methyl-1,1'-biphenyl	Methyltriphenylenes
Propylbenzene	Methyldibenzofuran	Binaphthalenes
Dimethylnonane	Dibenzofuran	Dimethylbenzo[c]phenanthrene
Methyl-ethylbenzenes	2,3-Dihydroindenediol	Methylbenzo[j]aceanthrylenes

9626716

1 ach mer L

11/82
N

SUMMARY OF BORINGS AND PIEZOMETER INSTALLATION BY GCA CORPORATION/TECHNOLOGY DIVISION - REILLY TAR SITE, ST. LOUIS PARK, MINNESOTA

Designation														
No.	Elevation of L.S. (MSL)	Location	Type	Date completed	Piezometer	Perforated interval depth below L.S.	Total depth below L.S.	Depth to bedrock below L.S.	Drilling method	Sample type	No. of samples	Distance into bedrock	Depth over 60 ft	Comments
1	908.88	(ST1 (old)) PB130	36th St & Minnehaha Creek Clean Background Location	10/25/82	Yes	89.3' to 92.3'	93.5'	87.5'	Drive and wash	SS ^a ST ^b	21 0	6'	33.5'	Screen in bedrock
2	909.14	PB137	36th St & Minnehaha Creek; 40' E of PB130 Clean Background Location	10/28/82	Yes	82.3' to 85.3'	84.5'	85.0'	Drive and wash 1	SS ST	2 6	1.5'	26.5'	Cleared utilities
3	907.46	PB138	34th St & Xylon/Wyoming (next to water tower) Clean Background Location	11/2/82	Yes	63.5' to 66.5'	78.5'	77.8'	Drive and wash	SS ST	17 2	7' 1.5'	18.5'	Cleared utilities
4	893.67	PB139	Dead end of Quebec at 31 St Reilly Tar Site Solid Ground	11/4/82	Yes	59.0' to 62.0'	67.5'	63.5'	Drive and wash	SS ST	16 1	4'	7.5'	Cleared utilities
5	893.80	PB140	Louisiana Av. next to W23 Reilly Tar Site Solid Ground	11/10/82	Yes	65.7' to 68.7'	71.0'	70.0'	Drive and wash	SS ST	17 1	1'	10'	Cleared utilities
6	890.11	PB142	Walker Av. & Louisiana Av. Ext. Reilly Tar Site Solid Ground	11/12/82	No	-	64'	63.7'	Augered	SS ST	14 1	-	4'	Cleared utilities
7	914.00	PB141	On Highway 7 overpass west of Louisiana Av. exit Reilly Tar Site Solid Ground	11/15/82	No	-	65'	-	Augered	SS ST	13 0	-	5'	Roadway signs special materials
8	895.11	PB144	Filled Swamp S of Highway 7 164' W of W13 Reilly Tar Site Solid Ground	11/19/82	Yes	44.3' to 47.3'	59'	51' (?)	Drive and wash	SS ST	13 1	8'	-	Cleared utilities

^aSplit Spoon Sampler.

^bThin wall Shelby Tube Sampler.

SUMMARY OF PAH ANALYSIS AT REILLY TAR SITE FOR SAMPLES TAKEN DURING OCTOBER-NOVEMBER 1982
BY GCA/TECHNOLOGY DIVISION

Compound	Sample No./Type										RB-138 03	RB-138 07	RB-138 010	RB-138 012	RB-138 016	RB-138 018	RB-139 04	RB-139 09	RB-139 010	RB-139 016
	RB-136(ST-1) 03	RB-136(ST-1) 04	RB-136(ST-1) 05	RB-136(ST-1) 06	RB-136(ST-1) 010	RB-136(ST-1) 018	RB-136(ST-1) 019	RB-136(ST-1) 020	RB-136(ST-1) 021											
	fibrous peat 0 to 5' b/s	nonfibrous peat 0 to 7' b/s	nonfibrous peat 0 to 8' b/s	gray till 0 to 13' b/s	outwash 0 to 13' b/s	gray till 0 to 73' b/s	sand 0 to 78' b/s	sand 0 to 83' b/s	weathered bedrock 0 to 87' b/s											
Naphthalene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Acenaphthylene	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.49	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Acenaphthene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Fluorene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Fluoranthene	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3*	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Anthracene	ND	ND	ND	ND	ND	ND	ND	ND	ND	-	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Acridine	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Carbazole	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Fluoranthene	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Pyrene	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Benzo(a) anthracene	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.87	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Benzo(h) fluoranthene	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.1*	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Benzo(a) pyrene	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.42	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Dibenzo(a,h) anthracene	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	ND*	

ND = 0.5 mg/kg 0.2 mg/kg

ND* = 2.0 mg/kg 0.8 mg/kg

Concentrations in µg/kg

*Reported value is total concentration of the two coeluting compounds.

Compound	Sample No./Type			
	FB-144 #2	FB-144 #3	FB-144 #5	FB-144 #7
	top soil @ 8' bls	fibrous peat @ 14' bls	nonfibrous peat @ 19' bls	outwash @ 29' bls
Naphthalene	1.2	3.4	ND	6.6
Acenaphthylene	ND	0.73	ND	ND
Acenaphthene	0.24	0.46	ND	0.65
Fluorene	0.24	0.50	ND	0.45
Phenanthrene	1.1 ^a	4.8 ^a	ND	0.93
Anthracene	-	-	ND	-
Acridine	ND	0.28	ND	ND
Carbazole	ND	0.53	ND	0.24
Fluoranthene	0.53	4.3	ND	ND
Pyrene	0.40	3.8	ND	ND
Benzo(a) anthracene	0.34 ^a	6.2	ND	ND
Benzo(k) fluoranthene	ND	11.7 ^a	ND	ND
Benzo(a) pyrene	ND	14.5	ND	ND
Dibenzo(a,h) anthracene	ND*	1.5	ND*	ND*

ND = 0.2 mg/kg ----- 0.5 mg/kg 0.2 mg/kg

ND* = 0.8 mg/kg ----- 2.0 mg/kg 0.8 mg/kg

Concentrations in mg/kg

^aReported value is total of the two coeluting compounds.

PRELIMINARY SUMMARY OF PHYSICAL TESTING RESULTS AT REILLY TAR SITE FOR SAMPLES TAKEN DURING
OCTOBER-NOVEMBER 1982 BY GCA/TECHNOLOGY DIVISION

Test	PB 137			PB 138		PB 139	PB 140	PB 142	PB 144
	#1/4'-5' non-fibrous peat	#5/8'-10.5' till	#6/10.5'-13' till	#5/8'-10.5' lac. clay	#13/48'-50' DM outwash	#8/20'-22.5' lac. clay	#5/8'-10.5' lac. clay	#3/4'-6.5' DM outwash	#4/15'-17.5' fibrous peat
K_v (ave.)	7.4×10^{-7}	3.5×10^{-7}	2.1×10^{-7}	7.2×10^{-8}	-	7.6×10^{-8}	-	-	1.2×10^{-7}
K_h	*	-	-	-	-	-	-	-	*
Porosity (%)	*	28	28	39	-	45	-	-	*
Particle Size	0% gravel 41% sand 55% silt 4% clay	4.7% gravel 49.7% sand 28.1% silt 17.5% clay	2.2% gravel 53% sand 27.1% silt 17.5% clay	1.3% gravel 35.1% sand 44.1% silt 19.5% clay	0% gravel 14.6% sand 75.4% silt 10% clay	0% gravel 15% sand 60% silt 25% clay	-	-	*
TOC	190,000 mg/kg	2,500 mg/kg	2,100 mg/kg 2,800 mg/kg	3,400 mg/kg	900 mg/kg	6,600 mg/kg	7,600 mg/kg	-	110,000 mg/kg

*Test in progress.

BORA GCA		BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 1 OF 2	HOLE NO. PB136							
SITE Background: 36th & Minnehaha				COORDINATES -		ANGLE FROM HORIZ. 90°		BEARING -							
BEGUN 10/18	COMPLETED 10/25	DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		HOLE SIZE 4"	OVERBURDEN (ft.) 87.5	ROCK (ft.) 6	TOTAL DEPTH 93.5'						
CORE RECOVERY (14.%)		CORE BOXES -	SAMPLES 21	EL. TOP OF CASING 910.53		GROUND EL. 908.88	DEPTH/EL. GROUND WATER 8.6'/900.28		DEPTH/EL. TOP OF ROCK 87.5/821.38						
SAMPLE HAMMER WEIGHT/FALL 140#/30"				CASING LEFT IN HOLE: DIA./LENGTH 2"/295'		LOGGED BY: P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	SAMPLE RECOVERY	SAMPLE BLOWS "	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
						1st 6"	2nd 6"	3rd 6"	4th 6"						
RB/ 2.5"	2'	6"	11			2	3	3	5	908.88		1	0-4'. <u>Topsoil</u> , organic, roots, and grass.	Mud & cuttings discharged to creek as OK by Mike Hansel;	-
SB	2'	12"	13			3	3	4	6	904.88		2		standpipe with 2,65' stickup.	
RB	2'	14"	10			2	2	4	4	902.88	5	3	4'-6'. <u>Brown fibrous peat</u> .	Water table ≈ 8.6'.	3
SB	2'	20"	10			2	1	4	5	902.38		4	6'-6.5'. <u>Black nonfibrous peat</u> .	Operation start @ 11:00.	4
SB	2'	24"	11			4	4	4	3	900.88		5	6.5'-8'. <u>Med. to coarse sand</u> with organic rich S/C zones.	SS sampler is 2.5" ID and the tip is flush inside.	5
										899.88			8'-9.5'. <u>Nonfibrous peat</u> .		
										898.88	10		9.5'-10'. <u>Outwash sand</u> .		
SB	2'	23.6"	35			9	11	11	13			6	10'-26'. <u>Gray till</u> . Very fine silty clay with scattered pebbles of limestone, sandstone (red) and mafic rocks.		6
											15				
SB	2'	23.2"	38			4	10	12	16			7			-
											20				
SB	2'	18"	33			6	9	12	12			8			-
											25				
										882.88					
SB	2'	0	50			12	16	17	17			9	26'-38'. <u>Coarse outwash</u> . Coarse sand (reddish/brown) fine fine to medium gravel of red sandstone, limestone, and basaltic rocks, and rock fragments.		-
											30				
SB	2'	0.7'	47			10	14	23	10			10			10
											35				
SB	2'	2'	57			15	21	16	20	870.88		11	38'-51.5'. <u>Gray till</u> . Similar in texture to above till layer. A few oxidized S/C rich layer (thin) are observed.		-
											40				
SB	2'	4"	94			21	19	32	43			12			-
											45				
SB = SPLIT SPOON; ST = SHELBY TUBE D = DENNISON; P = PITCHER; O = OTHER				SITE Background: 36th & Minnehaha						HOLE NO. PB136					

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078	SHEET NO 2 OF 2	HOLE NO. PB136	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH	SAMPLER RECOVERY CORE RECOVERY	SAMPLER BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB S P E C I F I C A T I O N N O.	
					1st 6"	2nd 6"	3rd 6"	4th 6"							
SS	2'	3"	77		20	26	21	30	857.38	50	13		Reduced sampler tip to specs.	-	
SS	2'	9.5"	120		35	38	38	44	852.88	55	14	51.5'-56'. Outwash sand. Medium sand; quartz, feldspars and rock fragments, fine gravel of mafic rocks.	-		
SS	2'	9"	55		16	18	16	21		60	15	56'-66'. Gray till similar in texture and composition to above till layers.	-		
SS	2'	0	171		21	41	55	75	842.88	65	16		-		
SS	2'	0	301		44	80	126	95	837.88	70	17	66'-71'. Medium sand, poorly sorted, with fine gravel.	-		
SS	2'	0.85'	153		36	44	46	63	832.38	75	18	71'-76.5'. Gray till similar in texture and composition as above till layers.	18		
SS	2'	1.85'	173		35	45	64	64	830.38	80	19	76.5'-78.5'. Sand matrix with fine gravel.	19		
									827.38			78.5'-81.5'. Gray till similar in texture and composition as above till layers.			
SS	2'	0.8'	225		19	60	86	79		85	20	81.5'-87.5'. Reddish/brown medium sand matrix with pebbly gravel.	20		
SS	1'	1'	180		21	180	-	-	821.38	90	21	87.5'-93.5'. Weathered limestone bedrock.	21		
									815.38			Bottom of hole.			
SS = SPLIT SPOON; ST = SHELBY TUBE O = DENNISON; P = PITCHER; Q = OTHER										SITE Background: 36th & Minnehaha		HOLE NO. PB136			

PROJECT <u>Reilly TAR 1-619-078</u>		WELL NO. <u>PB136</u>	
SITE <u>Background clean location 36th & Minnehaha</u>		AQUIFER <u>Platteville</u>	
COORDINATES _____		Limestone	
DATE COMPLETED <u>10/25/82</u>			
SUPERVISED BY <u>P.Huidobro</u>			

GENERALIZED STRATIGRAPHY		ELEVATION / DEPTH
GROUND ELEVATION 908.88 	Elevation of reference point	<u>910.53</u>
	Height of reference point above ground surface	<u>1.65</u>
	Depth of surface seal	<u>1'</u>
	Type of surface seal: <u>concrete</u>	
	I.D. of surface casing <u>steel with</u>	<u>4"</u>
	Type of surface casing: <u>vented locking cap</u>	
	Depth of surface casing	<u>5.35'</u>
	I.D. of riser pipe <u>galvanized</u>	<u>2"</u>
	Type of riser pipe: <u>10.5 section</u>	
	Topsoil Peat Medium sand Peat Alternating layers of gray till and outwash Medium sand and gravel outwash Limestone bedrock	Diameter of borehole
Type of filler: <u>cement/bentonite 1:1</u>		<u>822.88/86'</u>
Elevation / depth of top of seal		
Type of seal: <u>6/1 cement/bentonite</u>		
Type of gravel pack <u>No. 20 silica sand</u>		<u>821.38/87.5'</u>
Elev./depth of top of gravel pack		
Elevation / depth of top of screen		<u>819.58/89.3'</u>
Description of screen <u>3"x2" welded slot No. 10 galvanized steel</u>		
I.D. of screen section		
Elevation / depth of bottom of screen		<u>816.58/92.3'</u>
	bentonite	<u>816.58/92.3'</u>
	Elev./depth of bottom of gravel pack	
	Elev./depth of bottom of plugged blank section	<u>815.38/93.5'</u>
	Type of filler below plugged section <u>bentonite</u>	
	Elevation of bottom of borehole	<u>815.38/93.5'</u>

GCA		BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB137							
SITE Background: 36th & Minnehaha				COORDINATES 30' N of PB136		ANGLE FROM HORIZ. 90°		BEARING -									
BBSUN 10/26		COMPLETED 10/28		DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		HOLE SIZE 4"		OVERBURDEN (ft.) 85.0							
ROCK (ft.) 1.5		TOTAL DEPTH 86.5'		CORE RECOVERY (1% %) -		CORE BOXES 8		SAMPLES 8		EL. TOP OF CASING 910.9							
GROUND EL. 909.14		DEPTH/EL. GROUND WATER 8.7'/900.44'		DEPTH/EL. TOP OF ROCK 85/824.14													
SAMPLE HAMMER WEIGHT/FALL 140#/30"				CASING LEFT IN HOLE: DIA./LENGTH 2"/≈90'				LOGGED BY P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
										909.14							
SS/2.5"	2'	0.7'	14			2	4	5	5				1	0-3'. Topsoil with grass and roots and pebbles.		-	
SS	2'	0.8'	14			4	5	4	5	906.14			2			-	
ST	1'	1'											3	3'-7.5'. Fibrous peat.	ST = 3" x 30"	3*	
ST	2.5'	0											4			4*	
ST	2.5'	2.5'											5	7.5'-11.5'. Top and bottom of sampler show gray clays.	Water table @ ≈8'	5*	
ST	2.5'	2.5'								897.64			6	11.5'-25'. Gray till. Assumed from log of borehole PB136.		6*	
													15		Washings are uniform throughout the rest of the hole. Showing fine gravels and some gray S/C. Very little sand.		
													20				
										884.14			25	25'-37.5'. Coarse outwash. Assumed same stratigraphy as borehole PB136.			
ST	0	0											7			-	
													30				
													35				
										871.64			40	37.5'-51.5'. Gray till. Assumed same stratigraphy as borehole PB136.			
													45				
																*Sample for physical measurement only	
SS = SPLIT SPOON; ST = SHELBY TUBE D = DENNISON; P = PITCHER; O = OTHER										SITE Background: 36th & Minnehaha		HOLE NO. PB137					

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 2 OF 2	MOLE NO. PB137
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"						
									857.64	50				
									853.14	55		51.5'-56'. Outwash sand. Assumed same stratigraphy as borehole PB136.		
									843.14	60		56'-66'. Gray till. Assumed same stratigraphy as borehole PB136.		
									838.14	70		66'-71'. Medium sand. Assumed same stratigraphy as borehole PB136.		
									832.64	75		71'-76.5'. Gray till. Assumed same stratigraphy as borehole PB136.		
									830.64	80		76.5'-78.5. Sand and gravel. Assumed from borelog PB136.		
												78.5'-85'. Gray till. Assumed same stratigraphy as PB136.		
ST	1'	1'							824.14	85	8	85'-86.5'. Bedrock. Weathered limestone.	Loss of H ₂ O & mud. Roller bit to 86.5' is difficult and jumpy. No washings are recovered.	8*
									822.64	90		Bottom of hole		

SS = SPLIT SPOON; ST = SHELBY TUBE
O = DENNISON; P = PITCHER; Q = OTHER


SITE Background: 36th & Minnehaha

MOLE NO.
PB137

FORM 1003B

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly TAR</u> SITE <u>36 & Minnehaha</u> COORDINATES <u>-</u> DATE COMPLETED <u>10/27/82</u> SUPERVISED BY <u>P. Huidobro</u>		WELL NO. <u>PB137</u> AQUIFER <u>Glacial Drift</u>	
---	--	---	--

GENERALIZED STRATIGRAPHY (Assumed to be similar to PB136)	GROUND ELEVATION <u>909.14</u> 	Elevation of reference point <u>910.9</u> Height of reference point above ground surface <u>1.76</u> Depth of surface seal <u>1'</u> Type of surface seal: <u>concrete</u> I.D. of surface casing <u>4"</u> Type of surface casing: <u>steel with vented locking cap</u> Depth of surface casing <u>5.24'</u> I.D. of riser pipe <u>2"</u> Type of riser pipe: <u>galvanized steel</u> Diameter of borehole <u>4"</u> Type of filler: <u>1/1 cement/bentonite</u> Elevation / depth of top of seal <u>834.54/74.6'</u> Type of seal: <u>1/1 cement/bentonite</u> Type of gravel pack <u>silica sand No. 20</u> Elev./depth of top of gravel pack <u>833.54'/75.6'</u> Elevation / depth of top of screen <u>826.84'/82.3'</u> Description of screen <u>No. 10 slot welded galvanized steel</u> I.D. of screen section <u>822.64'/86.5'</u> Elevation / depth of bottom of screen <u>822.64'/86.5'</u> Elev./depth of bottom of gravel pack <u>822.64'/86.5'</u> Elev./depth of bottom of plugged blank section <u>822.64'/86.5'</u> Type of filler below plugged section <u>822.64'/86.5'</u> Elevation of bottom of borehole <u>822.64'/86.5'</u>	
--	--	--	--

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PBI38	
SITE 34th & Xylon-Wyoming				COORDINATES -				ANGLE FROM HORIZ. 90°				BEARING -					
BEGUN 10/29		COMPLETED 11/2/82		DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		HOLE SIZE 4"		OVERBURDEN (ft.) 77.8		ROCK (ft.) 0.7		TOTAL DEPTH 78.5'			
CORE RECOVERY (%) 1408/30"		CORE BOXES -		SAMPLES 19		EL. TOP OF CASING 909.77'		GROUND EL. 907.46'		DEPTH/EL. GROUND WATER -		DEPTH/EL. TOP OF ROCK 77.8'/829.66'					
SAMPLE HAMMER WEIGHT/FALL 1408/30"				CASING LEFT IN HOLE: DIA./LENGTH 2"/≈80'				LOGGED BY: P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	SAMPLE BLOWS	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.			
				1st 6"	2nd 6"	3rd 6"	4th 6"										
SS/ 2.5"	2'	1.2'	26	4	7	8	11	907.46			1	0-4'. <u>Topsoil</u> . Sand and pebbles, roots, grass, and gray clay.	Drilling, un-interrupted using method of sampling ahead of the casing; RB 3' and driving casing 5' supply of mud is continuous now, due to use of a Longyear mud mixer. Operation goes faster and without problem	-			
SS	2'	0.8'	30	12	9	9	12	903.46		2		-					
SS	2'	0.6'	21	6	7	8	6	900.96		3	4'-6.5'. Brown sand, mostly quartz, chunks of tar; oxidized S/C zones.	3					
SS	2'	1.5'	20	4	5	8	7	900.46		4	6.5'-7.0'. Fibrous <u>peat</u> .	-					
ST/ 3.0"	2.5'	1.8'	-	-	-	-	-	896.96		5	7.0'-10.5'. Black/brown <u>nonfibrous</u> <u>peat</u> .	5*					
SS	2'	1'	44	16	12	14	18	892.96		6	10.5'-14.5'. Poorly sorted <u>sand</u> with fine gravel. Mostly quartz and feldspar.	-					
SS	2'	1.8'	23	4	6	7	10		20	7	14.5'-30'. Gray till. Dense, fine silt and clay. Pebbles of limestone, angular, and rounded mafic rocks; red sandstone and agate (red). Yellow/brown oxidation zones at the top.	7					
SS	2'	1.7'	35	7	8	11	16		25	8		-					
SS	2'	1.8'	49	23	11	17	21	877.46	30	9		-					
SS	2'	1'	290	80	66	90	134	873.46	35	10	30'-34'. Coarse <u>gravel</u> of weathered limestone, olivine basalt, red sandstone and granitic rocks.	10					
SS	2'	2'	147	50	49	45	53		40	11	34'-64'. Outwash <u>sand</u> . Brown, moderate to well sorted. Mostly quartz, agate, and mafic minerals, some orthoclase. Grain size increases with depth. Thin, very dense silt and clay layers observed at 53' and 59.5'.	-					
SS	2'	1.5'	178	55	59	56	63		45	12		*Sample for physical measurements only.	12				

SS = SPLIT SPOON; ST = SHELBY TUBE
O = DENNISON; P = PITCHER; O = OTHER

SITE 34th & Xylon/Wyoming

HOLE NO.
PBI38

FORM 1003A

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 2 OF 2		HOLE NO. PBI 38	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.			
					1st 6"	2nd 6"	3rd 6"	4th 6"									
SS	30"	24"	-	-	-	-	-	-		50	13						
SS	2'	16"	315		84	127	100	88		55	14						
SS	2'	1.5'	417		83	104	100	213		60	15						
SS	2'	1.5'	167		55	47	54	66	843.46	65	16				16		
									839.96			64'-67.5'. Medium to coarse outwash sand and fine gravel with thin layers of silt and clay.					
SS	2'	1.5'	86		28	29	30	27		70	17						
												67.5'-75'. Gray clay, dense, with very fine lenses of fine sand. Large rafted pebbles of basaltic composition.					
SS	2'	14"	64		23	23	19	22	832.46	75	18				18		
									829.66			75'-77.8'. Coarse sand with chips of weathered limestone.					
SS	3"	0	-		300	-	-	-	828.96	80	19						
												77.8'-78.5'. Bedrock, weathered limestone. Bottom of hole. 78.5'.	No loss of H ₂ O at bedrock contact. Washings from 8.0' come out with fine sand and large LS chips.				

SS = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE 34th & Xylon/Wyoming

HOLE NO.
PBI 38

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly TAR</u>		WELL NO. <u>PB138</u>	
SITE <u>34th & Xylon/Wyoming</u>		AQUIFER <u>Glacial Drift</u>	
COORDINATES <u>-</u>		DATE COMPLETED <u>11/2/82</u>	
SUPERVISED BY <u>P. Huidobro</u>			

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>909.77</u>
		Height of reference point above ground surface	<u>1.81</u>
	GROUND ELEVATION 907.46	Depth of surface seal	<u>1'</u>
	Topsoil	Type of surface seal: <u>concrete</u>	
	Sand	I.D. of surface casing <u>steel</u>	<u>4"</u>
	Peat	Type of surface casing: <u>steel</u>	
	Alternating layers of gray till and outwash	Depth of surface casing	<u>5.19'</u>
		I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>galvanized steel, coupled</u>	
		Diameter of borehole	<u>4"</u>
	Outwash sand and fine gravel	Type of filler: <u>cement/bentonite 1:1</u>	
		Elevation / depth of top of seal	<u>849.96/57.5'</u>
		Type of seal: <u>6:1 cement/bentonite</u>	
		Type of gravel pack <u>silica sand #20</u>	<u>848.16/59.3'</u>
		Elev./depth of top of gravel pack	
	Elevation / depth of top of screen	<u>843.96/63.5'</u>	
	Description of screen <u>No. 10 slot welded galvanized steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>840.96/66.5'</u>	
Clay	Elev./depth of bottom of gravel pack	<u>835.46/72'</u>	
Sand	Elev./depth of bottom of plugged blank section	<u>828.96/78.5'</u>	
Limestone bedrock	Type of filler below plugged section <u>bentonite</u>		
	Elevation of bottom of borehole	<u>828.96/78.5'</u>	

GCA		BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PBI39							
SITE 31st & Quebec				COORDINATES -		ANGLE FROM HORIZ. 90°		BEARING -									
BBSUM 11/3		COMPLETED 11/4/82		DRILLER Braun Engr.		DRILL MAKE AND MODEL CME75		HOLE SIZE 4"		OVERBURDEN (ft.) 63.5							
ROCK (ft.) 4.0		TOTAL DEPTH 67.5'		CORE RECOVERY (%) -		CORE BONES -		SAMPLES 17		EL. TOP OF CASING 896.45							
GROUND EL. 893.67		DEPTH/EL. GROUND WATER -		DEPTH/EL. TOP OF ROCK 64'/829.67		SAMPLE HAMMER WEIGHT/FALL 140#/30"		CASING LEFT IN HOLE DIA./LENGTH 2"/≈70'		LOGGED BY P. Huidobro							
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH	CORE RUN LENGTH	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS " "	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
										893.67							
SS	2.5"	2'	14"	29		3	7	11	11				1	0-6'. Topsoil. Organic rich, roots and oxidized zones. Coarse sand and gravel. Bioturbated.	Continuous sampling for top 10', after which samples are taken ahead of the H casing, after RB and introduction of casing. Safety considerations are applied as per contract requirements because site is suspected to be contaminated. No contamination by oil or creosote is observed in the RB washings and cuttings.	-	
SS	2'	1.2'	49		8	15	15	19				2		-			
SS	2'	2'	60		12	16	20	24	887.65			3		-			
SS	2'	1.5'	11		3	3	3	5				4	6'-18'. Thin layer (3") of fibrous peat followed by black, nonfibrous peat, strong decomposition odor.	4			
SS	2'	1.5'	7		0	2	2	3				5		-			
SS	2'	0	13		5	4	4	5				6		-			
SS	2'	14"	7		1	2	2	3				7	18'-21.5'. Lacustrine clayey silt with thin lenses of fine sand.	Character of washings at the interval where no samples are recovered are consistent with those above and below those	-		
ST/30"	30"	30"							872.17			8	21.5'-22'. Medium sand.		8		
									871.67								
									869.97				22'-23.7'. Silty clays.				
SS	2'	14"	47		13	15	20	12	868.67			9			9		
SS	2'	1.5'	52		13	11	17	24				10	23.7'-25'. Outwash sand with <1% gravel.				
SS	2'	1'	66		22	21	20	25	859.17			11	25'-34.5'. Gray till. Fine sand in a S/C matrix with gravel of granitic and mafic rocks, and limestone. Red/brown oxidized zones interlayered.				
SS	2'	0	48		23	18	15	15				12	34.5'-64'. Outwash sand and gravel. Sand fraction is brown, fine to coarse consisting mostly of quartz and rock fragments. Fine to coarse gravel of both gravimetric and mafic rocks mixed with limestone and red sandstone. A one-inch layer of red till is observed at the bottom of the outwash layer in contact with the limestone bedrock.				
SS	2'	0	72		28	27	20	25				13					
SS = SPLIT SPOON; ST = SHELBY TUBE D = DENNISON; P = PITCHER; O = OTHER										SITE 31st & Quebec		HOLE NO. PBI39					

BORA BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 2 OF 2	MOLE NO. PBI39
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORRECTION	SAMPLE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"						
88	2'	1'	73		19	26	22	25			14		intervals. Core catcher replaced after sample # 13. Samples 15 & 16 are impossible to extrude from liners, possi- bly due to highly cohesive fine sands. @ 64', RB's jumpy and hydraulic pres- sure 800 lb. Washing con- tains checks of weathered lime- stone.	-
										50				
88	2'	4"	117		33	38	38	41			15			-
										55				
88	2'	1'	153		40	46	52	55			16			16
										60				
88	0.5'	0			200	-	-	-	829.67		17			-
									826.17		65	64'-67.5'. <u>Bedrock</u> . Limestone.		
											70	Bottom of hole.		

SS = SPLIT SPOON; ST = SHELBY TUBE
 O = DENNISON; P = PITCHER; Q = OTHER

SITE 3lat & Quebec

MOLE NO.
PBI39

FORM 1008B

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u>		WELL NO. <u>PB139</u>
SITE <u>31st & Quebec</u>		
COORDINATES <u>-</u>		AQUIFER <u>Glacial Drift</u>
DATE COMPLETED <u>11/5/82</u>		
SUPERVISED BY <u>P. Huidobro</u>		

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>896.45</u>
		Height of reference point above ground surface	<u>2.78'</u>
	GROUND ELEVATION <u>893.67</u>	Depth of surface seal	<u>1'</u>
	Topsail	Type of surface seal: <u>concrete</u>	
	Peat	I.D. of surface casing	<u>4"</u>
		Type of surface casing: <u>steel 7"x4"</u>	
	Lacustrine clay	Depth of surface casing	<u>4.22'</u>
	Alternating layers of gray till and outwash	I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>coupled</u>	
		<u>galvanized steel</u>	
	Outwash sand and gravel	Diameter of borehole	<u>4"</u>
		Type of filler: <u>1:1 cement/bentonite</u>	
		Elevation / depth of top of seal	<u>838.67/55'</u>
		Type of seal: <u>6:1 cement/bentonite</u>	
		Type of gravel pack <u>silica sand</u>	
	Elev./depth of top of gravel pack	<u>837.17/56.5'</u>	
	Elevation / depth of top of screen	<u>834.67/59.0'</u>	
	Description of screen <u>No. 10 slot welded steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>831.67/62.0'</u>	
	Elev./depth of bottom of gravel pack	<u>827.67/66.0'</u>	
	Elev./depth of bottom of plugged blank section	<u>826.17/67.5'</u>	
	Type of filler below plugged section <u>bentonite</u>		
	Elevation of bottom of borehole	<u>826.17/67.5'</u>	

904 BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
SITE Louisiana Ave. Near W23										COORDINATES		ANGLE FROM HORIZ.		BEARING			
BEGIN 1/8/82		COMPLETED 11/10/82		DRILLER BRAUN ENGR		DRILL MAKE AND MODEL CME 75		HOLE SIZE 4"		OVERBURDEN (ft.) 70		ROCK (ft.) 1		TOTAL DEPTH 71 ft.			
CORE RECOVERY (IL %)		CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK					
				18		895.99'		893.35'				70/823.60					
SAMPLE HAMMER WEIGHT/FALL 140 #130				CASING LEFT IN HOLE DIA./LENGTH 2"/873'				LOGGED BY P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.		
					1st 6"	2nd 6"	3rd 6"	4th 6"									
SS/2.5"	1.6'	1.5'	272		2	10	31	231	891.60'			1	0-1.75'. Top Soil, brown sandy clay with roots and grass.	Using existing pit to dispose of cuttings and mud. Samples recovered from tarry layer are impossible to extrude from liners; they have to be scraped off.	-		
SS	2'	1.5'	126		105	53	38	35				2	1.75'-5'. Well compacted black bituminous material. Gravelly sand all coated with black material. Tar smell. Material is very brittle.	Washing from smelly zones come out with an iridescent oily film on top. HNU reading is 75 ppm.	2		
SS	2'	1'	31		12	14	9	8	888.35'			3	5'-8'. Coarse moderately sorted brown sand. Mostly qtz and rock frags red in color 1" layer of black sand (coated)		3		
SS	2'	1.8'	21		6	5	7	9	885.35'			4			4		
ST	30"	18"										5	8'-11.5'. Very uniform layer of fibrous peat. Gray-black silty clay with gravel (4 cm). Strong tarry smell.		5		
									881.85				11.5'-13'. Gray medium-fine sand, most qtz with some gravel, weathered LS and x-line rocks.				
									880.35								
SS	2'	16"	34		14	11	11	12				6	13'-16'. Very small silty clay gray on top and brown at bottom interlayered with coarse gravel. Till.	Casing does not advance beyond 27; goes through. When pulled out drill pipe is chewed up, bit brings up a large chunk of jasper.	6		
									877.35								
SS	2'	1'	59		20	21	17	21				7	16'-65'. Outwash. Mod. sorted sand and fine gravel. It is not possible to determine its color because the grains appear to be saturated with very smelly "oily" fluid that covers all particles with an iridescent sheen. Mineralogy and petrology are tentative at best, mostly qtz and rock fragments. Gravel components are LS, red SS and xtaline rocks of basaltic nature as well as perthitic igneous rocks. Subporphyritic mafic rocks are also present. Phaneritic rocks of granitic composition with subhedral fabric. Gravel component decreases with depth and the sediment becomes better sorted in the medium to coarse sand range, which is about 90% qtz with little feldspars and rock fragments. Silt and clay content of this outwash is less than 10%.	Cuttings from RB from 30'-55' consist of sand and broken gravel. Sand is fine and gravel is about 1 cm. It is possible that this material is not held properly by the core catcher, or interfering with the ball valve on top, thus the samples are flushed out.	-		
SS	2'	0	71		20	19	22	29				8					
SS	2'	6"	45		16	15	16	14				9	48'-50' into the outwash consists of poorly sorted very fine to coarse sand; with <5% gravel and traces of silt and clay. Sand is reddish brown in color, and consists mostly of qtz with a larger component of red and black rock fragments and some red SS chips. Rock fragments are very angular and in general with a high sphericity value.	Left the site @ 16:30 after hitting bedrock heavy snow and hail/sleet.	-		
SS	2'	0	55		19	20	18	17				10					
SS	2'	0	100		18	22	32	46				11					
SS	2'	0	111		49	32	34	45				12					
SS	2'	4"	50		9	14	20	16				13					

SS = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE
Louisiana Ave. Near W23

HOLE NO.
PB140

FORM 1003A

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
										Reilly Tar		1-619-078		2 of 2		PB140	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE	SAMPLER CORRECTION	SAMPLER CORRECTION	SAMPLER CORRECTION	SAMPLER CORRECTION	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
SS	2'	0.5		65		18	29	18	18				14	58'-60'. Outwash zone with mineralogy and petrology similar to overlying zone. Well sorted medium sand 90% qtz 10% feldspars and fragments of mafic rx and red SS. Traces of S/C. No gravel.		14	
SS	2'	0		122		34	43	41	38				15	63'-65'. Outwash is poorly sorted very fine to coarse brown sand with about 5% gravel.		-	
SS	2'	10"		54		21	22	17	15				16			16	
SS	2'	10"		122		24	31	59	32				17			-	
SS	1.5'	0.5'		192		50	40	152		823.35			18	65'-70'. Red/brown till in contact with bedrock. This unit is composed of 70% very fine sand, 25% silt and clay and 5% medium gravel. Fine portion is mostly qtz while pebbles are of mafic rock, and LS, angular to rounded. Unstratified.		-	
										822.35				Bedrock - Bottom of hole.			

*Sample for physical measurements only

SS = SPLIT SPOON; ST = SHELBY TUBE
 D = DENNISON; P = PITCHER; O = OTHER

SITE Louisiana Ave. Near W23

HOLE NO. PB 140

FORM 10058

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u>		WELL NO. <u>PB140</u>
SITE <u>Louisiana Ave. next to W23</u>		AQUIFER <u>Glacial Drift</u>
COORDINATES <u>-</u>		
DATE COMPLETED <u>11/10/82</u>		
SUPERVISED BY <u>P. Huidobro</u>		

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>895.99'</u>
		Height of reference point above ground surface	<u>2.64</u>
	GROUND ELEVATION <u>893.35'</u>	Depth of surface seal	<u>1.0'</u>
	Top soil	Type of surface seal: <u>concrete</u>	
	Gravelly sand	I.D. of surface casing	<u>4"</u>
	Sand	Type of surface casing: <u>steel 7' long</u>	
	Fibrous peat	Depth of surface casing	<u>4.46'</u>
	Fine-medium sand	I.D. of riser pipe	<u>2"</u>
	Gray till	Type of riser pipe: <u>galvanized steel</u>	
	Outwash sand and gravel	Diameter of borehole	<u>4"</u>
		Type of filler: <u>1:1 cement bentonite</u>	
		Elevation / depth of top of seal	<u>831.35' / 62.0'</u>
		Type of seal: <u>6/1 cement bentonite</u>	
		Type of gravel pack <u>No. 20 silica sand</u>	
		Elev./depth of top of gravel pack	<u>830.35' / 63.0'</u>
	Elevation / depth of top of screen	<u>827.65' / 65.7'</u>	
	Description of screen <u>No. 10 slot welded galvanized steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>824.65' / 68.7'</u>	
	Elev./depth of bottom of gravel pack	<u>823.35' / 70.0'</u>	
	Elev./depth of bottom of plugged blank section	<u>822.35' / 71.0'</u>	
	Type of filler below plugged section <u>bentonite pellets</u>		
	Elevation of bottom of borehole	<u>822.35' / 71.0'</u>	

GCA		BORING LOG		PROJECT		JOB NO.		SHEET NO.		HOLE NO.						
		Reilly Tar		1-619-078		1 OF 2		B141								
SITE Hwy. 7, West of Louisiana Ave. EXT.				COORDINATES				ANGLE FROM HORIZ.		BEARING						
90°																
BEGUN		COMPLETED		DRILLER		DRILL MAKE AND MODEL		HOLE SIZE		OVERBURDEN (ft.)						
11/15/82		11/15/82		BRAUN ENGR		CME 75		4"		-						
CORE RECOVERY (11.%)		CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER						
-		-		13		-		914.00		-						
SAMPLE HAMMER WEIGHT/FALL				CASING LEFT IN HOLE DIA./LENGTH				LOGGED BY								
140 #130								P. Huidobro								
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft.	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.
						1st 6"	2nd 6"	3rd 6"	4th 6"							
										914				0'-1'. Black sand and gravel.	Drilling on a 2-lane hwy. One lane closed time limitation for drilling.	
SS	2.5'	2'	1.1'	37		12	9	8	8		5		1	1'-30' is fill material that comprises the embankment for the Hwy 7 overpass. No particular odor or visible contaminants are detected in this interval. Fill is poorly sorted material ranging from fine sand to fine gravel. Sand fraction consists mostly of qtz and mafic rx. Gravel is composed mostly of well rounded pebbles of gabbro and red SS. Between 18' and 30' there are small blotches of yellow-brown oxidized zones.	No casing is used. Hollow stem auger is used instead, with RB as appropriate. Sampler ahead of auger.	-
SS	2'	2'	1.3'	41		13	11	8	9		10		2			2
SS	2'	2'	1.5'	57		14	12	11	20		15		3			3
SS	2'	2'	1.5'	102		26	23	18	35		20		4			-
SS	2'	2'	1.8'	82		37	14	10	21		25		5			-
SS	2'	2'	0.4'	60		12	12	19	17	884'	30		6			-
SS	2'	2'								881'				30'-33'. Black silty clay with LgX fine sand.		
SS	2'	2'								879'	35		7	33'-35'. Uniform layer of brownish peat, rich in light-brown fibers. Odorless		7
SS	2'	2'									40		8	35'-43.5'. Organic rich, well compacted dark grey decomposed peat with abundance of fresh H ₂ O shell fragments. Layer is odorless acid structureless.. Mostly silt with some clay.		8
SS	2'	2'								870.5'						
SS	2'	2'	1.8'	41		3	8	14	16		45		9	43.5'-48'. Grey till made up of about 90% very fine sand and silt with clay and fine gravel. Strong creosote smell.		9
										866'						

SS = SPLIT SPOON; ST = SHELBY TUBE
 O = DENNISON; P = PITCHER; Q = OTHER

SITE Hwy. 7 West of Louisiana Ave. Ext.

HOLE NO. B141

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
										Reilly Tar		1-619-078		2 OF 2		B141	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE	LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
							1st 6"	2nd 6"	3rd 6"	4th 6"							
											866'						
SS	2'	0	61		22	15	12	12				30	10	48'-65'. Outwash moderately to poorly sorted sands mixed with some gravel sand portion, consists of qtz, red SS, and mafic rock fragments. Feldspar content is <5%, mostly orthoclase. Gravel grains measure up to about 3 cm. consist of well rounded pebbles of mafic rocks and quartzite.			
SS	2'	1.2"	61		16	13	14	18				35	11				11
SS	2'	0.4"	60		21	13	12	14				60	12				-
SS	2'	0	63		27	14	12	10		849'		65	13				-
														Bottom of hole			

SS - SPLIT SPOON; ST - SHELBY TUBE
D - DENNISON; P - PITCHER; O - OTHER

SITE Hwy. 7 West of Louisiana Ave. Ext.

HOLE NO. B141

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
SITE										COORDINATES		ANGLE FROM HORIZ.		BEARING			
Walker Ave. & Louisiana Ave. Ext.												90°					
BEGIN		COMPLETED		DRILLER		DRILL MAKE AND MODEL		MOLE SIZE		OVERBURDEN (ft.)		ROCK (ft.)		TOTAL DEPTH			
11/11		11/11/82		BRAUN ENGR		CME 75		4"		63.7		0		63.7 ft.			
CORE RECOVERY (ft. %)				CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK			
140 #130"						15		-		890.11		-		63.7/ 826.41'			
SAMPLE HAMMER WEIGHT/FALL				CASING LEFT IN HOLE: DIA./LENGTH				LOGGED BY:									
140 #130"								P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE	SAMPLER CORE RUN LENGTH	SAMPLER RECOVERY	SAMPLE SLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft.	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
										890.11							
SS	2.5'	2'	1'	27	50	3	6	11	10	889.61			1	0-0.5'. Top soil, organic, grass, roots			
SS	2.5'	2'	8"	30	33	6	6	9	15	888.11			2	0.5-2'. Brown fill sandy clay, fibrous, fine gravel (1 cm). No odor or contaminants present, sand amount increases.	Original site under 2' of H ₂ O due to heavy rain. Moved location across the street.		
ST	2.5'	1.9'			76					884.61			3	2'-5.5'. Brown peat, fibrous @ 3-4', non-fibrous @ 4'-5.5'.		3*	
										883.61				5.5'-6.5'. Medium to coarse sand.	Drill using shallow skin auger with RB as appropriate AW rod. Auger is 3 1/4" I.D.		
SS	2'	0.7'		29	35	9	8	11	10	880.11			4	6.5'-10'. Uniform layer of black organic soil, mostly clay with fine gravel up to 1 cm. No odor moist on top.	Sample #6 lost due to character of sediments, which are washed out due to grain size. Character of washings remains the same through about the 45' marker: predominantly fine sands.		
													5	10'-48'. Outwash: 13'-20'. Moderately sorted coarse sand with strong creosole smell contamination is not visible. 80% qtz, 5% LS, 15% mafic minerals and rock fragments.		5	
SS	2'	1.5'		37	75	11	12	13	12					23'-45'. Unstratified outwash with very poorly sorted sand and fine gravel (2-10 mm) sand composition similar to 13'-20' layer, gravel is about 50% quartzite fragments, 30% basalt chips and feldspar phenocrysts with perthitic fabric; mixed with fragments of red sandstone, limestone, and mafic rocks. Fragments are very angular of all shapes.			
SS	2'	0		24	0	9	9	8	7				6				
SS	2'	1'		42	50	20	18	12	12				7	Creosote smell is still very evident in this layer through to the 45' marker.		7	
SS	2'	0		14	0	8	13	11	10				8				
SS	2'	1'		46	50	33	15	15	16				9				9
SS	2'	8"		28	33	6	8	13	7				10				
SS	2'	1'		26	50	4	6	9	11				11				11

SB = SPLIT SPOON; ST = SHELBY TUBE
 O = DENNISON; P = PITCHER; O = OTHER

SITE Walker Ave. and Louisiana Ave. Ext.

HOLE NO. B142

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.		
										Reilly Tar		1-619-078		2 OF 2		B142		
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE	LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.	
							1st 6"	2nd 6"	3rd 6"	4th 6"								
SS	2'	2'			253	100	26	71	82	00					12	48'-55'. Unstratified red glacial till. Strong creosote odor. No visible contamination. Highly compacted silty clay, <5% fine sand; gravel of mostly basalt and angular rock fragments.		12
SS	2'	1.2'			87	60	7	13	26	48	835.11			13	55'-63'. Outwash. Brown sand (quartz, mafic rock fragments, red sandstone and LS. Gravel at bottom, LS and red sandstone. Creosote smell.		13	
SS	2'	1.5'			180	75	44	40	50	90				14			14	
											827.11				Bedrock. Weathered limestone.			
SS	0	-			0	100					826.41			15	Bottom of hole.		-	
																Auger jumps and jerks @ 63'. Truck lifted @ 63.7'.		

SS - SPLIT SPOON; ST - SHELBY TUBE
O - OENNISON; P - PITCHER; Q - OTHER

SITE Walker Ave. and Louisiana Ave. Ext.

HOLE NO. B142

FORM 10058

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB144	
SITE Filled swamp S of Hy 7; 164' W of W13				COORDINATES				ANGLE FROM HORIZ. 90°				BEARING					
BEGUN 11/17		COMPLETED 11/19/82		DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		HOLE SIZE 4"		OVERBURDEN (ft.) 51		ROCK (ft.) 8		TOTAL DEPTH 59'			
CORE RECOVERY (IL %)		CORE BOXES		SAMPLES 13		EL. TOP OF CASING 897.72'		GROUND EL. 895.02'		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK ≈ 51' / 844.02'					
SAMPLE HAMMER WEIGHT / FALL 140# / 30"				CASING LEFT IN HOLE DIA. / LENGTH 2" / 60'				LOGGED BY: P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "H"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft.	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.		
					1st 6"	2nd 6"	3rd 6"	4th 6"									
									895.02								
SS	2'	0	25		10	11	8	6				1	0-13'. Topsoil. Black sandy muck, oxidized zones. LS and SS pebles. Strong smell of rubber. Few isolated chunks of fibrous peat.				
SS	2'	1.2'	3		1	1	1	1				2			2		
SS	2'	1'	21		5	5	8	8	882.02			3	13'-15'. Brown fibrous peat. Strong creosote and H ₂ S smell.				
ST	10"	2.5'							880.02			4	15'-24'. Black peat. Very mature with shell fragments. Slightly fibrous. Strong creosote and H ₂ S smell.				
SS	2'	1.5'	10		0	3	3	4				5		@ 18' no washings come out during casing driving. Probably due to dissolution of organic materials.			
SS	2'	1.5'	19		2	7	5	7	871.02			6	24'-26.5'. Brown silty clay with black blotches. Strong odor.				
SS	2'	1'	50		9	15	18	17	868.52			7	26.5'-51'. Outwash. Poorly sorted medium to coarse sand and fine to medium gravel. Isolated chunks of bituminous material. Mineralogy of sand is mostly quartz and rock fragments. Gravel is chiefly limestone, mafic rocks, granitic rocks and agate (red). Strong odor of H ₂ S and creosote				
SS	2'	0	53		20	20	17	16				8					
SS	2'	0	26		24	12	7	7				9					
SS	2'	0.5'	99		28	41	30	28				10					
*Sample for physical measurements only																	

SS = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE
Filled swamp S of Hy 7; 164 W of W13

HOLE NO.
PB144

FORM 1003A

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078	SHEET NO. 2 OF 2	HOLE NO. PB144
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS			ELEVATION	DEPTH, 'f	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO
					1st 6"	2nd 6"	3rd 6"							
SS	2'	0	130		48	43	41	34			11			
									844.02					
SS	2'	0	89		55	36	28	25			12			
SS	1'	0	-		177	238			836.02		13	Bottom of hole.		

SS - SPLIT SPOON; ST - SHELBY TUBE
D - DENNISON; P - PITCHER; O - OTHER

SITE Filled swamp S of Hy 7; 164 W of W13

HOLE NO.
PB144

FORM 1003B

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u> SITE <u>Filled swamp;</u> COORDINATES _____ DATE COMPLETED <u>11/19/82</u> SUPERVISED BY <u>P. Huidobro</u>		WELL NO. <u>PB144</u> AQUIFER <u>Glacial Drift</u>	
---	--	---	--

GENERALIZED STRATIGRAPHY	GROUND ELEVATION 895.02		Elevation of reference point	897.72
	Top soil		Height of reference point above ground surface	2.70'
	Fibrous peat		Depth of surface seal	1'
	Black peat		Type of surface seal: <u>concrete</u>	
			I.D. of surface casing	4"
			Type of surface casing: <u>black steel</u>	
			Depth of surface casing	4.3'
			I.D. of riser pipe	2"
			Type of riser pipe: <u>galvanized, coupled 10.5' section</u>	
	Silty clay		Diameter of borehole	4"
	Outwash sand and gravel		Type of filler: <u>1:1 cement/bentonite</u>	
			Elevation / depth of top of seal	853.72/41.3'
			Type of seal: <u>6:1 cement bentonite</u>	
			Type of gravel pack <u>No. 20 silica sand</u>	
			Elev./depth of top of gravel pack	852.72/42.3'
		Elevation / depth of top of screen	850.72/44.3'	
		Description of screen <u>No. 10 slot galvanized, welded steel</u>		
		I.D. of screen section	2"	
		Elevation / depth of bottom of screen	847.72/47.3'	
Limestone		Elev./depth of bottom of gravel pack	843.02/52'	
		Elev./depth of bottom of plugged blank section	841.02/54'	
		Type of filler below plugged section <u>bentonite</u>		
		Elevation of bottom of borehole	836.02/59'	

PRELIMINARY SUMMARY OF PHYSICAL TESTING RESULTS AT REILLY TAR SITE FOR SAMPLES TAKEN DURING
OCTOBER-NOVEMBER 1982 BY GCA/TECHNOLOGY DIVISION

Test	FB 137			FB 138		FB 139	FB 140	FB 142	FB 144
	#1/4'-5' non-fibrous peat	#5/8'-10.5' till	#6/10.5'-13' till	#5/8'-10.5' lac. clay	#13/48'-50' DM outwash	#8/20'-22.5' lac. clay	#5/8'-10.5' lac. clay	#3/4'-6.5' DM outwash	#4/15'-17.5' fibrous peat
K_v (ave.)	7.4×10^{-7}	3.5×10^{-7}	2.1×10^{-7}	7.2×10^{-8}	-	7.6×10^{-8}	-	-	1.2×10^{-7}
K_h	-*	-	-	-	-	-	-	-	-*
Porosity (%)	-*	28	28	39	-	45	-	-	-*
Particle Size	0% gravel	4.7% gravel	2.2% gravel	1.3% gravel	0% gravel	0% gravel	-	-	-*
	41% sand	49.7% sand	53% sand	35.1% sand	14.6% sand	15% sand	-	-	-
	55% silt	28.1% silt	27.1% silt	44.1% silt	75.4% silt	60% silt	-	-	-
	4% clay	17.5% clay	17.5% clay	19.5% clay	10% clay	25% clay	-	-	-
TOC	190,000 mg/kg	2,500 mg/kg	2,100 mg/kg 2,800 mg/kg	3,400 mg/kg	900 mg/kg	6,600 mg/kg	7,600 mg/kg	-	110,000 mg/kg

*Test in progress.

A Hash went 4

BORING LOG										PROJECT		JOB NO.	SHEET NO.	HOLE NO.		
SITE Background: 36th & Minnehaha										COORDINATES -		ANGLE FROM HORIZ. 90°		BEARING -		
BEGIN 10/18	COMPLETED 10/25	DRILLER Braun Engr			DRILL MAKE AND MODEL CME-75			HOLE SIZE 4"	OVERBURDEN (ft.) 87.5	ROCK (ft.) 6	TOTAL DEPTH 93.5'					
CORE RECOVERY (1%)		CORE BONES		SAMPLES 21	EL. TOP OF CASING 910.53		GROUND EL. 908.88	DEPTH/EL. GROUND WATER 8.6'/900.28		DEPTH/EL. TOP OF ROCK 87.5/821.38						
SAMPLE HAMMER WEIGHT/FALL 140#/30"				CASING LEFT IN HOLE DIA/LENGTH 2"/295'				LOGGED BY: P. Huidobro								
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
						1st 6"	2nd 6"	3rd 6"	4th 6"							
SS/2.5"	2'	6"	11			2	3	3	5	908.88			1	0-4'. <u>Topsoil</u> , organic, roots, and grass.	Mud & cuttings discharged to creek as OK by Mike Hansel;	-
SS	2'	12"	13			3	3	4	6	904.88			2		standpipe with 2.65' stickup.	
SS	2'	14"	10			2	2	4	4	902.88			3	4'-6'. <u>Brown fibrous peat</u> .	Water table ≈ 8.6'.	3
SS	2'	20"	10			2	1	4	5	902.38			4	6'-6.5'. <u>Black nonfibrous peat</u> .	Operation start @ 11:00.	4
SS	2'	24"	11			4	4	4	3	899.38			5	6.5'-8'. <u>Med. to coarse sand</u> with organic rich S/C zones.	SS sampler is 2.5" ID and the tip is flush inside.	5
										898.88				8'-9.5'. <u>Nonfibrous peat</u> .		
														9.5'-10'. <u>Outwash sand</u> .		
SS	2'	23.6"	35			9	11	11	13				6	10'-26'. <u>Gray till</u> . Very fine silty clay with scattered pebbles of limestone, sandstone (red) and mafic rocks.		6
SS	2'	23.2"	38			4	10	12	16				7			
SS	2'	18"	33			6	9	12	12				8			
										882.88						
SS	2'	0	50			12	16	17	17				9	26'-38'. <u>Coarse outwash</u> . Coarse sand (reddish/brown) fine fine to medium gravel of red sandstone, limestone, and basaltic rocks, and rock fragments.		
SS	2'	0.7'	47			10	14	23	10				10			10
SS	2'	2'	57			15	21	16	20	870.88			11	38'-51.5'. <u>Gray till</u> . Similar in texture to above till layer. A few oxidized S/C rich layer (thin) are observed.		
SS	2'	4"	94			21	19	32	43				12			

SS = SPLIT SPOON; ST = SHELBY TUBE
O = DENNISON; P = PITCHER; O = OTHER

SITE
Background: 36th & Minnehaha

HOLE NO.
PB136

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078	SHEET NO 2 OF 2	HOLE NO. PB136	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "H"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"							
SS	2'	3"	77		20	26	21	30		857.38		13		Reduced sampler tip to specs.	-
SS	2'	9.5"	120		35	38	38	44		852.88		14	51.5'-56'. Outwash sand. Medium sand; quartz, feldspars and rock fragments, fine gravel of mafic rocks.		-
SH	2'	9"	55		16	18	16	21				15	56'-66'. Gray till similar in texture and composition to above till layers.		-
SS	2'	0	171		21	41	55	75		842.88		16			-
SS	2'	0	301		44	80	126	95		837.88		17	66'-71'. Medium sand, poorly sorted, with fine gravel.		-
SS	2'	0.85'	153		36	44	46	63		832.38		18	71'-76.5'. Gray till similar in texture and composition as above till layers.		18
SS	2'	1.85'	173		35	45	64	64		830.38		19	76.5'-78.5'. Sand matrix with fine gravel.		19
										827.38			78.5-81.5'. Gray till similar in texture and composition as above till layers.		
SS	2'	0.8'	225		19	60	86	79				20	81.5-87.5'. Reddish/brown medium sand matrix with pebbly gravel.		20
SS	1'	1'	180		21	180	-	-		821.38		21	87.5'-93.5'. Weathered limestone bedrock.	Loss of all washing and mud @ 87.5'.	21
										815.38			Bottom of hole.		

SS = SPLIT SPOON; ST = SHELBY TUBE D = DENNISON; P = PITCHER; O = OTHER	SITE Background: 36th & Minnehaha	HOLE NO. PB136
--	--------------------------------------	-------------------

FORM 1005B

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly TAR 1-619-078</u> SITE <u>Background clean location 36th & Minnehaha</u> COORDINATES _____ DATE COMPLETED <u>10/25/82</u> SUPERVISED BY <u>P.Huidobro</u>		WELL NO. <u>PB136</u> AQUIFER <u>Platteville</u> <u>Limestone</u>	
--	--	---	--

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>910.53</u>
		Height of reference point above ground surface	<u>1.65</u>
		Depth of surface seal	<u>1'</u>
		Type of surface seal: <u>concrete</u>	
		I.D. of surface casing	<u>4"</u>
		Type of surface casing: <u>steel with vented locking cap</u>	
		Depth of surface casing	<u>5.35'</u>
		I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>galvanized</u>	
		<u>10.5 section</u>	
		Diameter of borehole	<u>4"</u>
		Type of filler: <u>cement/bentonite 1:1</u>	<u>822.88/86'</u>
		Elevation / depth of top of seal	
		Type of seal: <u>6/1 cement/bentonite</u>	
		Type of gravel pack <u>No. 20 silica sand</u>	<u>821.38/87.5'</u>
Elev./depth of top of gravel pack	<u>819.58/89.3'</u>		
Elevation / depth of top of screen			
Description of screen <u>3"x2" welded slot No. 10 galvanized steel</u>			
I.D. of screen section			
Elevation / depth of bottom of screen	<u>816.58/92.3'</u>		
bentonite	<u>816.58/92.3'</u>		
Elev./depth of bottom of gravel pack			
Elev./depth of bottom of plugged blank section	<u>815.38/93.5'</u>		
Type of filler below plugged section <u>bentonite</u>			
Elevation of bottom of borehole	<u>815.38/93.5'</u>		

GCA BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB137							
SITE Background: 36th & Minnehaha		COORDINATES 30' N of PB136		ANGLE FROM HORIZ. 90°		BEARING -									
BBUN 10/26	COMPLETED 10/28	DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		HOLE SIZE 4"		OVERBURDEN (ft.) 85.0							
ROCK (ft.) 1.5		TOTAL DEPTH 86.5'													
CORE RECOVERY (1% %)		CORE BOXES 8		EL. TOP OF CASING 910.9		GROUND EL. 909.14		DEPTH/EL. GROUND WATER 8.7'/900.44'							
DEPTH/EL. TOP OF ROCK 85/824.14															
SAMPLE HAMMER WEIGHT/FALL 140#/30"		CASING LEFT IN HOLE DIA./LENGTH 2"/≈90'		LOGGED BY: P. Huidobro											
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	L S A M P L E N O.	
						1st 6"	2nd 6"	3rd 6"	4th 6"						
										909.14					
SS/2.5"	2'	0.7'	14			2	4	5	5			1	0-3'. <u>Topsoil</u> with grass and roots and pebbles.		-
SS	2'	0.8'	14			4	5	4	5	906.14		2	3'-7.5'. <u>Fibrous peat</u> .	ST = 3" x 30"	-
ST	1'	1'										3			3*
ST	2.5'	0										4			4*
ST	2.5'	2.5'										5	7.5'-11.5'. Top and bottom of sampler show <u>gray clays</u> .	Water table @ ≈8'	5*
ST	2.5'	2.5'								897.64		6	11.5'-25'. <u>Gray till</u> . Assumed from log of borehole PB136.		6*
												15		Washings are uniform throughout the rest of the hole. Showing fine gravels and some gray S/C. Very little sand.	
												20			
										884.14		25	25'-37.5'. <u>Coarse outwash</u> . Assumed same stratigraphy as borehole PB136.		
ST	0	0										7			-
												30			
												35			
										871.64		40	37.5'-51.5'. <u>Gray till</u> . Assumed same stratigraphy as borehole PB136.		
												45			
													*Sample for physical measurement only		
SS = SPLIT SPOON; ST = SHELBY TUBE D = DENNISON; P = PITCHER; O = OTHER						SITE Background: 36th & Minnehaha						HOLE NO. PB137			

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078		SHEET NO 2 OF 2		HOLE NO PBI37	
SAMPLE TYPE AND DIAMETER	SAMPLER APPROPRIATE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "in"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LABORATORY SAMPLE NO.		
					1st 6"	2nd 6"	3rd 6"	4th 6"									
									857.64	50							
									853.14	55			51.5'-56'. Outwash sand. Assumed same stratigraphy as borehole PBI36.				
									843.14	65			56'-66'. Gray <u>till</u> . Assumed same stratigraphy as borehole PBI36.				
									838.14	70			66'-71'. Medium <u>sand</u> . Assumed same stratigraphy as borehole PBI36.				
									832.64	75			71'-76.5'. Gray <u>till</u> . Assumed same stratigraphy as borehole PBI36.				
									830.64	80			76.5'-78.5. Sand and <u>gravel</u> . Assumed from borelog PBI36.				
										80			78.5'-85'. Gray <u>till</u> . Assumed same stratigraphy as PBI36.				
ST	1'	1'							824.14	85		8	85'-86.5'. Bedrock. Weathered <u>lime-stone</u> .	Loss of H ₂ O & mud. Roller bit to 86.5' is difficult and jumpy. No washings are recovered.		8*	
									822.64				Bottom of hole				
										90							

SS = SPLIT SPOON; ST = SHELBY TUBE
 D = DENNISON; P = PITCHER; O = OTHER

SITE Background: 36th & Minnehaha

HOLE NO.
PBI37

FORM 1003B

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly TAR</u>		WELL NO. <u>PB137</u>
SITE <u>36 & Minnehaha</u>		AQUIFER <u>Glacial Drift</u>
COORDINATES <u>-</u>		
DATE COMPLETED <u>10/27/82</u>		
SUPERVISED BY <u>P. Huidobro</u>		

<p>GROUND ELEVATION 909.14</p> <p>Topsoil</p> <p>Peat</p> <p>Sand</p> <p>Peat</p> <p>Alternating layers of gray till and outwash</p> <p>Outwash</p> <p>Gray till</p> <p>Medium sand with pebbly gravel</p> <p>Limestone bedrock</p> <p>GENERALIZED STRATIGRAPHY (Assumed to be similar to PB136)</p>	Elevation of reference point	910.9
	Height of reference point above ground surface	1.76
	Depth of surface seal	1'
	Type of surface seal: <u>concrete</u>	
	I.D. of surface casing	4"
	Type of surface casing: <u>steel with vented locking cap</u>	
	Depth of surface casing	5.24'
	I.D. of riser pipe	2"
	Type of riser pipe: <u>galvanized steel</u>	
	Diameter of borehole	4"
	Type of filler: <u>1/1 cement/bentonite</u>	
	Elevation / depth of top of seal	834.54'/74.6'
	Type of seal: <u>1/1 cement/bentonite</u>	
	Type of gravel pack <u>silica sand No. 20</u>	
	Elev./depth of top of gravel pack	833.54'/75.6'
Elevation / depth of top of screen	826.84'/82.3'	
Description of screen <u>No. 10 slot welded galvanized steel</u>		
I.D. of screen section		
Elevation / depth of bottom of screen	822.64'/86.5'	
Elev./depth of bottom of gravel pack	822.64'/86.5'	
Elev./depth of bottom of plugged blank section	822.64'/86.5'	
Type of filler below plugged section		
Elevation of bottom of borehole	822.64'/86.5'	

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB138	
SITE 34th & Xylon-Wyoming										COORDINATES		ANGLE FROM HORIZ. 90°		BEARING			
BEGIN		COMPLETED		DRILLER		DRILL MAKE AND MODEL		HOLE SIZE		OVERBURDEN (ft.)		ROCK (ft.)		TOTAL DEPTH			
10/29		11/2/82		Braun Engr		CMR-75		4"		77.8		0.7		78.5'			
CORE RECOVERY (1/4%)		CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK					
1408/30"		-		19		909.77'		907.46'		-		77.8'/829.66'					
SAMPLE HAMMER WEIGHT/FALL 1408/30"				CASING LEFT IN HOLE: DIA./LENGTH 2"/80'				LOGGED BY P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE SLOWS "s"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.		
					1st 6"	2nd 6"	3rd 6"	4th 6"									
SB/2.5"	2'	1.2'	26		4	7	8	11	907.46			1	0-4'. Topsoil. Sand and pebbles, roots, grass, and gray clay.	Drilling, uninterrupted using method of sampling ahead of the casing; RB 3' and driving casing 5' supply of mud is continuous now, due to use of a Longyear mud mixer. Operation goes faster and without problem	-		
SB	2'	0.8'	30		12	9	9	12	903.46		2		-				
SB	2'	0.6'	21		6	7	8	6	900.96		3	4'-6.5'. Brown sand, mostly quartz, chunks of tar; oxidized S/C zones.	3				
SB	2'	1.5'	20		4	5	8	7	900.46		4	6.5'-7.0'. Fibrous peat.	-				
ST/3.0"	2.5'	1.8'	-		-	-	-	-	896.96		5	7.0'-10.5'. Black/brown nonfibrous peat.	5*				
SB	2'	1'	44		16	12	14	18	892.96		6	10.5'-14.5'. Poorly sorted sand with fine gravel. Mostly quartz and feldspar.	-				
SB	2'	1.8'	23		4	6	7	10		20	7	14.5'-30'. Gray till. Dense, fine silt and clay. Pebbles of limestone, angular, and rounded mafic rocks; red sandstone and agate (red). Yellow/brown oxidation zones at the top.	7				
SB	2'	1.7'	35		7	8	11	16		25	8		-				
SB	2'	1.8'	49		23	11	17	21	877.46	30	9		-				
SB	2'	1'	290		80	66	90	134	873.46	35	10	30'-34'. Coarse gravel of weathered limestone, olivine basalt, red sandstone and granitic rocks.	10				
SB	2'	2'	147		50	49	45	53		40	11	34'-64'. Outwash sand. Brown, moderate to well sorted. Mostly quartz, agate, and mafic minerals, some orthoclase. Grain size increases with depth. Thin, very dense silt and clay layers observed at 53' and 59.5'.	-				
SB	2'	1.5'	178		55	59	56	63		45	12		*Sample for physical measurements only.	12			

SB = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE 34th & Xylon/Wyoming

HOLE NO.
PB138

FORM 1003A

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 2 OF 2	HOLE NO. PB138
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORRECTION	SAMPLER RECOVERY CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"						
SS	30"	24"	-	-	-	-	-	-	-	90	13			-
SS	2'	16"	315		84	127	100	88		95	14			-
SS	2'	1.5'	417		83	104	100	213		60	15			-
SS	2'	1.5'	167		55	47	54	66	843.46	63	16	64'-67.5'. Medium to coarse outwash sand and fine gravel with thin layers of silt and clay.		16
SS	2'	1.5'	86		28	29	30	27		70	17	67.5'-75'. Gray clay, dense, with very fine lenses of fine sand. Large rafted pebbles of basaltic composition.		-
SS	2'	14"	64		23	23	19	22	832.46	75	18			18
									829.66			75'-77.8'. Coarse sand with chips of weathered limestone.		
SS	3"	0	-		300	-	-	-	828.96	80	19	77.8'-78.5'. Bedrock, weathered limestone. Bottom of hole. 78.5'.	No loss of H ₂ O at bedrock contact. Washings from 8.0' come out with fine sand and large LS chips.	-

SS - SPLIT SPOON; ST - SHELBY TUBE
D - DENNISON; P - PITCHER; O - OTHER

SITE 34th & Xylon/Wyoming

HOLE NO.
PB138

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly TAR</u>		WELL NO. <u>FB138</u>	
SITE <u>34th & Xylon/Wyoming</u>		AQUIFER <u>Glacial Drift</u>	
COORDINATES <u>-</u>			
DATE COMPLETED <u>11/2/82</u>			
SUPERVISED BY <u>P. Huidobro</u>			

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>909.77</u>
		Height of reference point above ground surface	<u>1.81</u>
	GROUND ELEVATION 907.46	Depth of surface seal	<u>1'</u>
	Topsoil	Type of surface seal: <u>concrete</u>	
	Sand	I.D. of surface casing	<u>4"</u>
	Peat	Type of surface casing: <u>steel</u>	
	Alternating layers of gray till and outwash	Depth of surface casing	<u>5.19'</u>
		I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>galvanized steel, coupled</u>	
		Diameter of borehole	<u>4"</u>
		Type of filler: <u>cement/bentonite 1:1</u>	
	Outwash sand and fine gravel	Elevation / depth of top of seal	<u>849.96/57.5'</u>
		Type of seal: <u>6:1 cement/bentonite</u>	
		Type of gravel pack <u>silica sand #20</u>	<u>848.16/59.3'</u>
		Elev./depth of top of gravel pack	
	Elevation / depth of top of screen	<u>843.96/63.5'</u>	
	Description of screen <u>No. 10 slot welded galvanized steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>840.96/66.5'</u>	
Clay	Elev./depth of bottom of gravel pack	<u>835.46/72'</u>	
Sand	Elev./depth of bottom of plugged blank section	<u>828.96/78.5'</u>	
Limestone bedrock	Type of filler below plugged section <u>bentonite</u>		
	Elevation of bottom of borehole	<u>828.96/78.5'</u>	

GCA BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 1 OF 2	HOLE NO. PB139									
SITE 31st & Quebec		COORDINATES		ANGLE FROM HORIZ. 90°		BEARING									
BEGIN 11/3	COMPLETED 11/4/82	DRILLER Braun Engr.		DRILL MAKE AND MODEL CMZ75	HOLE SIZE 4"	OVERBURDEN (ft.) 63.5	ROCK (ft.) 4.0								
CORE RECOVERY (1% %)		CORE BOXES 17	SAMPLES 17	EL. TOP OF CASING 896.45	GROUND EL. 893.67	DEPTH/EL. GROUND WATER	DEPTH/EL. TOP OF ROCK 64'/829.67								
SAMPLE HAMMER WEIGHT / FALL 140#/30"		CASING LEFT IN HOLE: DIA./LENGTH 2"/≈70'		LOGGED BY: P. Huidobro											
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "H"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"							
SS 2.5"	2'	14"	29		3	7	11	11	893.67			1	0-6'. Topsoil. Organic rich, roots and oxidized zones. Coarse sand and gravel. Bioturbated.	Continuous sampling for top 10', after which samples are taken ahead of the H casing, after RB and introduction of casing. Safety considerations are applied as per contract requirements because site is suspected to be contaminated. No contamination by oil or creosote is observed in the RB washings and cuttings.	-
SS	2'	1.2'	49		8	15	15	19				2			-
SS	2'	2'	60		12	16	20	24	887.65			3			-
SS	2'	1.5'	11		3	3	3	5				4	6'-18'. Thin layer (3") of fibrous peat followed by black, nonfibrous peat, strong decomposition odor.		4
SS	2'	1.5'	7		0	2	2	3				5			-
SS	2'	0	13		5	4	4	5				6			-
									875.67						
SS	2'	14"	7		1	2	2	3				7	18'-21.5'. Lacustrine clayey silt with thin lenses of fine sand.		-
ST/ 30"	30"	30"							872.17 871.67			8	21.5'-22'. Medium sand.		8
									869.97				22'-23.7'. Silty clays.		
SS	2'	14"	47		13	15	20	12	868.67			9			9
													23.7'-25'. Outwash sand with <1% gravel.		
SS	2'	1.5'	52		13	11	17	24				10	25'-34.5'. Gray till. Fine sand in a S/C matrix with gravel of granitic and mafic rocks, and limestone. Red/brown oxidized zones interlayered.		10
SS	2'	1'	66		22	21	20	25	859.17			11			-
SS	2'	0	48		23	18	15	15				12	34.5'-64'. Outwash sand and gravel. Sand fraction is brown, fine to coarse consisting mostly of quartz and rock fragments. Fine to coarse gravel of both gravimitic and mafic rocks mixed with limestone and red sandstone. A one-inch layer of red till is observed at the bottom of the outwash layer in contact with the limestone bedrock.	Character of washings at the interval where no samples are recovered are consistent with those above and below those	-
SS	2'	0	72		28	27	20	25				13			-

SS = SPLIT SPOON; ST = SHELBY TUBE
O = DENNISON; P = PITCHER; Q = OTHER

SITE 31st & Quebec

HOLE NO.
PB139

FORM 1003A

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 2 OF 2	HOLE NO. PB139	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTHS CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	L S S A M P L E N O.	
						1st 6"	2nd 6"	3rd 6"	4th 6"						
SS	2'	1'		73		19	26	22	25			14		intervals. Core catcher replaced after sample # 13. Samples 15 & 16 are impossible to extrude from liners, possi- bly due to highly cohesive fine sands. @ 64', RB's jumpy and hydraulic pres- sure 800 lb. Washing con- tains checks of weathered lime- stone.	-
											50				
SS	2'	4"		117		33	38	38	41			15			-
											55				
SS	2'	1'		153		40	46	52	55			16			16
											60				
SS	0.5'	0				200	-	-	-	829.67		17			
										826.17		65	64'-67.5'. <u>Bedrock</u> . Limestone.		
												70	Bottom of hole.		

SS - SPLIT SPOON; ST - SHELBY TUBE
 O - DENNISON; P - PITCHER; Q - OTHER

SITE 31st & Quebec

HOLE NO.
PB139

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u>		WELL NO. <u>PB139</u>
SITE <u>31st & Quebec</u>		AQUIFER <u>Glacial Drift</u>
COORDINATES <u>-</u>		
DATE COMPLETED <u>11/5/82</u>		
SUPERVISED BY <u>P. Huidobro</u>		

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>896.45</u>
		Height of reference point above ground surface	<u>2.78'</u>
	GROUND ELEVATION <u>893.67</u>	Depth of surface seal	<u>1'</u>
	Topsail	Type of surface seal: <u>concrete</u>	
	Peat	I.D. of surface casing	<u>4"</u>
		Type of surface casing: <u>steel 7"x4"</u>	
	Lacustrine clay	Depth of surface casing	<u>4.22'</u>
	Alternating layers of gray till and outwash	I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>coupled</u>	
		<u>galvanized steel</u>	
	Outwash sand and gravel	Diameter of borehole	<u>4"</u>
		Type of filler: <u>1:1 cement/bentonite</u>	
		Elevation / depth of top of seal	<u>838.67/55'</u>
		Type of seal: <u>6:1 cement/bentonite</u>	
		Type of gravel pack <u>silica sand</u>	
	Elev./depth of top of gravel pack	<u>837.17/56.5'</u>	
	Elevation / depth of top of screen	<u>834.67/59.0'</u>	
	Description of screen <u>No. 10 slot welded steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>831.67/62.0'</u>	
	Elev./depth of bottom of gravel pack	<u>827.67/66.0'</u>	
	Elev./depth of bottom of plugged blank section	<u>826.17/67.5'</u>	
	Type of filler below plugged section <u>bentonite</u>		
	Elevation of bottom of borehole	<u>826.17/67.5'</u>	

904 BORA		BORING LOG		PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB140						
SITE Louisiana Ave. Near W23				COORDINATES		ANGLE FROM HORIZ. 90°		BEARING								
BEGUN 11/8/82		COMPLETED 11/10/82		DRILLER BRAUN ENGR		DRILL MAKE AND MODEL CME 75		HOLE SIZE 4"		OVERBURDEN (ft.) 70						
CORE RECOVERY (%)		CORE BOXES		SAMPLES		EL. TOP OF CASING 895.99'		GROUND EL. 893.35'		DEPTH/EL. GROUND WATER 70/823.60						
SAMPLE HAMMER WEIGHT/FALL 140 #130				CASING LEFT IN HOLE DIA./LENGTH 2"/≈ 73'				LOGGED BY: P. Huidobro								
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.
						1" 6"	2" 6"	3" 6"	4" 6"							
SS/2.5"	1.6'	1.5'	272			2	10	31	231	891.60'			1	0-1.75'. Top Soil, brown sandy clay with roots and grass.	Using existing pit to dispose of cuttings and mud. Samples recovered from tarry layer are impossible to extrude from liners; they have to be scraped off.	-
SS	2'	1.5'	126			105	53	38	35				2	1.75'-5'. Well compacted black bituminous material. Gravelly sand all coated with black material. Tar smell. Material is very brittle	Washing from smelly zones come out with an iridescent oily film on top. HNU reading is 75 ppm.	2
SS	2'	1'	31			12	14	9	8	888.35'			3	5'-8'. Coarse moderately sorted brown sand. Mostly qtz and rock frags red in color 1" layer of black sand (coated		3
SS	2'	1.8'	21			6	5	7	9	885.35'			4	8'-11.5'. Very uniform layer of fibrous peat. Gray-black silty clay with gravel (4 cm). Strong fatty smell.		4
ST	30"	18"											5	11.5'-13'. Gray medium-fine sand, most qtz with some gravel, weathered LS and x-line rocks.		5
										881.85						
										880.35						
SS	2'	16"	34			14	11	11	12				6	13'-16'. Very small silty clay gray on top and brown at bottom interlayered with coarse gravel. Till.		6
										877.35						
SS	2'	1'	59			20	21	17	21				7	16'-65'. Outwash. Mod. sorted sand and fine gravel. It is not possible to determine its color because the grains appear to be saturated with very smelly "oily" fluid that covers all particles with an iridescent sheen. Mineralogy and petrology are tentative at best, mostly qtz and rock fragments. Gravel components are LS, red SS and xtaline rocks of basaltic nature as well as perthitic igneous rocks. Subporphyritic mafic rocks are also present. Phaneritic rocks of granitic composition with subhedral fabric. Gravel component decreases with depth and the sediment becomes better sorted in the medium to coarse sand range, which is about 90% qtz with little feldspars and rock fragments. Silt and clay content of this outwash is less than 10%.	Casings does not advance beyond 27; goes through. When pulled out drill pipe is chewed up, bit brings up a large chunk of jasper.	-
SS	2'	0	71			20	19	22	29				8	48'-50' into the outwash consists of poorly sorted very fine to coarse sand; with <5% gravel and traces of silt and clay. Sand is reddish brown in color, and consists mostly of qtz with a larger component of red and black rock fragments and some red SS chips. Rock fragments are very angular and in general with a high sphericity value.	Cuttings from RB from 30'-55' consist of sand and broken gravel. Sand is fine and gravel is about 1 cm. It is possible that this material is not held properly by the core catcher, or interfering with the ball valve on top, thus the samples are flushed out.	-
SS	2'	6"	45			16	15	16	14				9		Left the site @ 16:30 after hitting bedrock heavy snow and hail/sleet.	-
SS	2'	0	55			19	20	18	17				10			-
SS	2'	0	100			18	22	32	46				11			-
SS	2'	0	111			49	32	34	45				12			-
SS	2'	4"	50			9	14	20	16				13			-

SS = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE
Louisiana Ave. Near W23

HOLE NO.
PB140

FORM 1003A

BORING LOG								PROJECT Reilly Tar		JOB NO. 1-619-078	SHEET NO. 2 OF 2	HOLE NO. PB140		
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORRECTION	SAMPLE RECOVERY CORRECTION	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LABORATORY NO.
					1st 6"	2nd 6"	3rd 6"	4th 6"						
SS	2'	0.5	65		18	29	18	18		58'-60'		Outwash zone with mineralogy and petrology similar to overlying zone. Well sorted medium sand 90% qtz 10% feldspars and fragments or mafic rx and red SS. Traces of S/C. No gravel.		14
SS	2'	0	122		34	43	41	38		63'-65'		Outwash is poorly sorted very fine to coarse brown sand with about 5% gravel.		-
SS	2'	10"	54		21	22	17	15						16
SS	2'	10"	122		24	31	59	32						-
SS	1.5'	0.5'	192		50	40	152		823.35	65'-70'		Red/brown till in contact with bedrock. This unit is composed of 70% very fine sand, 25% silt and clay and 5% medium gravel. Fine portion is mostly qtz while pebbles are of mafic rock, and LS, angular to rounded. Unstratified.		-
									822.35			Bedrock - Bottom of hole.		

*Sample for physical measurements only

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u>		WELL NO. <u>PB140</u>	
SITE <u>Louisiana Ave. next to W23</u>		AQUIFER <u>Glacial Drift</u>	
COORDINATES <u>-</u>			
DATE COMPLETED <u>11/10/82</u>			
SUPERVISED BY <u>P. Huidobro</u>			

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>895.99'</u>
		Height of reference point above ground surface	<u>2.64</u>
	GROUND ELEVATION <u>893.35'</u>	Depth of surface seal	<u>1.0'</u>
	<u>Top soil</u>	Type of surface seal: <u>concrete</u>	
	<u>Gravelly sand</u>	I.D. of surface casing	<u>4"</u>
	<u>Sand</u>	Type of surface casing: <u>steel 7' long</u>	
	<u>Fibrous peat</u>	Depth of surface casing	<u>4.46'</u>
	<u>Fine-medium sand</u>	I.D. of riser pipe	<u>2"</u>
	<u>Gray till</u>	Type of riser pipe: <u>galvanized steel</u>	
	<u>Outwash sand and gravel</u>	Diameter of borehole	<u>4"</u>
		Type of filler: <u>1:1 cement bentonite</u>	
		Elevation / depth of top of seal	<u>831.35'/62.0'</u>
		Type of seal: <u>6/1 cement bentonite</u>	
		Type of gravel pack <u>No. 20 silica sand</u>	
		Elev./depth of top of gravel pack	<u>830.35'/63.0'</u>
	Elevation / depth of top of screen	<u>827.65'/65.7'</u>	
	Description of screen <u>No. 10 slot welded galvanized steel</u>		
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>824.65'/68.7'</u>	
	Elev./depth of bottom of gravel pack	<u>823.35'/70.0'</u>	
	Elev./depth of bottom of plugged blank section	<u>822.35'/71.0'</u>	
	Type of filler below plugged section <u>bentonite pellets</u>		
	Elevation of bottom of borehole	<u>822.35'/71.0'</u>	

GCA		BORING LOG		PROJECT		JOB NO.		SHEET NO.		HOLE NO.						
		Reilly Tar		1-619-078		1 OF 2		B141								
SITE Hwy. 7, West of Louisiana Ave. EXT.				COORDINATES				ANGLE FROM HORIZ.		BEARING						
90°																
BEGUN		COMPLETED		DRILLER		DRILL MAKE AND MODEL		HOLE SIZE		OVERBURDEN (ft.)						
11/15/82		11/15/82		BHAUN ENGR		CME 75		4"		-						
CORE RECOVERY (%)		CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER						
-		-		13		-		914.00		-						
SAMPLE HAMMER WEIGHT/FALL				CASING LEFT IN HOLE DIA./LENGTH				LOGGED BY								
140 #130								P. Huidobro								
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft.	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB SAMPLE NO.
						1st 6"	2nd 6"	3rd 6"	4th 6"							
										914				0'-1'. Black sand and gravel.	Drilling on a 2-lane hwy. One lane closed time limitation for drilling.	
SS 2.5"	2'	1.1'	37			12	9	8	8		5		1	1'-30' is fill material that comprises the embankment for the Hwy 7 overpass. No particular odor or visible contaminants are detected in this interval. Fill is poorly sorted material ranging from fine sand to fine gravel. Sand fraction consists mostly of qtz and rock fragments at LS and mafic rx. Gravel is composed mostly of well rounded pebbles of gabbro and red SS. Between 18' and 30' there are small blotches of yellow-brown oxidized zones.	No casing is used. Hollow stem auger is used instead, with RB as appropriate. Sampler ahead of auger.	-
SS	2'	1.3'	41			13	11	8	9		10		2			2
SS	2'	1.5'	57			14	12	11	20		15		3			3
SS	2'	1.5'	102			26	23	18	35		20		4			-
SS	2'	1.8'	82			37	14	10	21		25		5			-
SS	2'	0.4'	60			12	12	19	17	884'	30		6			-
										881'				30'-33'. Black silty clay with LgX fine sand.		
SS	2'	2'	65			4	11	18	32	879'	35		7	33'-35'. Uniform layer of brownish peat, rich in light-brown fibers. Odorless		7
SS	2'	2'	27			3	6	8	10		40		8	35'-43.5'. Organic rich, well compacted dark grey decomposed peat with abundance of fresh H ₂ O shell fragments. Layer is odorless acid structureless.. Mostly silt with some clay.		8
SS	2'	1.8'	41			3	8	14	16	870.5'	45		9	43.5'-48'. Grey till made up of about 90% very fine sand and silt with clay and fine gravel. Strong creosote smell.		9
										866'						

SS = SPLIT SPOON; ST = SHELBY TUBE
D = DENNISON; P = PITCHER; O = OTHER

SITE Hwy. 7 West of Louisiana Ave. Ext.

HOLE NO. B141

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078		SHEET NO 207 2		HOLE NO B141	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, " GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.			
					1st 6"	2nd 6"	3rd 6"	4th 6"									
SS	2'	0	61		22	15	12	12	866'		10	48'-65'. Outwash moderately to poorly sorted sands mixed with some gravel sand portion, consists of qtz, red SS, and mafic rock fragments. Feldspar content is <5%, mostly orthoclase. Gravel grains measure up to about 3 cm. consist of well rounded pebbles of mafic rocks and quartzite.	Forced to abandon site at 15:30. Boring grouted to the top and cuttings discarded on site.	-			
SS	2'	1.2'	61		16	13	14	18		11	11						
SS	2'	0.4'	60		21	13	12	14		12	-						
SS	2'	0	63		27	14	12	10	849'	13	-						
											Bottom of hole						

SS - SPLIT SPOON ST - SHELBY TUBE
D - DENNISON P - PITCHER O - OTHER

SITE Hwy. 7 West of Louisiana Ave. Ext.

HOLE NO.
B141

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
Walker Ave. & Louisiana Ave. Ext.										Reilly Tar		1-619-078		1 OF 2		B142	
SITE										COORDINATES		ANGLE FROM HORIZ.		BEARING			
Walker Ave. & Louisiana Ave. Ext.												90°					
BEGIN		COMPLETED		DRILLER		DRILL MAKE AND MODEL		HOLE SIZE		OVERBURDEN (ft.)		ROCK (ft.)		TOTAL DEPTH			
11/11		11/11/82		BRAUN ENGR		CME 75		4"		63.7		0		63.7 ft.			
CORE RECOVERY (ft. %)		CORE BOXES		SAMPLES		EL. TOP OF CASING		GROUND EL.		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK					
				15				890.11				63.7/ 826.41'					
SAMPLE HAMMER WEIGHT/FALL				CASING LEFT IN HOLE: DIA./LENGTH				LOGGED BY:									
140 #130"								P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE	SAMPLER CORE RUN LENGTH	SAMPLER CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC.	LAB. SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
										890.11							
SS 2.5"	2'	1'	27	50	3	6	11	10		889.61			1	0-0.5'. Top soil, organic, grass, roots			
SS	2'	8"	30	33	6	6	9	15		888.11			2	0.5-2'. Brown fill sandy clay, fibrous, fine gravel (1 cm). No odor or contaminants present, sand amount increases.	Original site under 2' of H ₂ O due to heavy rain. Moved location across the street.		
ST	2.5'	1.9'		76						884.61			3	2'-5.5'. Brown peat, fibrous @ 3-4' non-fibrous @ 4'-5.5'.		34	
										883.61				5.5'-6.5'. Medium to coarse sand.			
SS	2'	0.7'	29	35	9	8	11	10		880.11			4	6.5'-10'. Uniform layer of black organic soil, mostly clay with fine gravel up to 1 cm. No odor moist on top.	Drill using shallow skin auger with RB as appropriate AW rod. Auger is 3 1/4" I.D.		
														10'-48'. Outwash:	Sample #6 lost due to character of sediments, which are washed out due to grain size. Character of washings remains the same through about the 45' marker: predominantly fine sands.		
SS	2'	1.5'	37	75	11	12	13	12					5	13'-20'. Moderately sorted coarse sand with strong cresole smell contamination is not visible. 80% qtz, 5% LS, 15% mafic minerals and rock fragments.		5	
														23'-45'. Unstratified outwash with very poorly sorted sand and fine gravel (2-10 mm) sand composition similar to 13'-20' layer, gravel is about 50% quartzite fragments, 30% basalt chips and feldspar phenocrysts with perthitic fabric; mixed with fragments of red sandstone, limestone, and mafic rocks. Fragments are very angular of all shapes.			
SS	2'	0	24	0	9	9	8	7					6				
SS	2'	1'	42	50	20	18	12	12					7	Creosote smell is still very evident in this layer through to the 45' marker.		7	
SS	2'	0	34	0	8	13	11	10					8				
SS	2'	1'	46	50	33	15	15	16					9			9	
SS	2'	8"	28	33	6	8	13	7					10				
SS	2'	1'	26	50	4	6	9	11					11			11	

SS = SPLIT SPOON; ST = SHELBY TUBE
O = DENNISON; P = PITCHER; O = OTHER

SITE
Walker Ave. and Louisiana Ave. Ext.

HOLE NO.
B142

FORM 1003A

BORING LOG										PROJECT		JOB NO.		SHEET NO.		HOLE NO.	
										Reilly Tar		1-819-078		2 of 2		B142	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY	CORE RECOVERY	SAMPLE BLOWS	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, "	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.	
						1st 6"	2nd 6"	3rd 6"	4th 6"								
SS	2'	2'		253	100	26	71	82	100		50		12	48'-55'. Unstratified red glacial till. Strong creosote odor. No visible contamination. Highly compacted silty clay, <5% fine sand; gravel of mostly basalt and angular rock fragments.		12	
SS	2'	1.2'		87	60	7	13	26	48	835.11	55	13	55'-63'. Outwash. Brown sand (quartz, mafic rock fragments, red sandstone and LS. Gravel at bottom, LS and red sandstone. Creosote smell.		13		
SS	2'	1.5'		180	75	44	40	50	90		60	14			14		
										827.11			Bedrock. Weathered limestone.				
SS	0	-	-	0	100					826.41	65	15	Bottom of hole.				
														Auger jumps and jerks @ 63'. Truck lifted @ 63.7'.			

SS - SPLIT SPOON; ST - SHELBY TUBE
D - DENNISON; P - PITCHER; O - OTHER

SITE Walker Ave. and Louisiana Ave. Ext.

HOLE NO.
B142

BORING LOG										PROJECT Reilly Tar		JOB NO. 1-619-078		SHEET NO. 1 OF 2		HOLE NO. PB144	
SITE Filled swamp S of Hy 7; 164' W of W13				COORDINATES				ANGLE FROM HORIZ. 90°				BEARING					
BEGUN 11/17		COMPLETED 11/19/82		DRILLER Braun Engr		DRILL MAKE AND MODEL CME-75		MOLE SIZE 4"		OVERBURDEN (ft.) 51		ROCK (ft.) 8		TOTAL DEPTH 59'			
CORE RECOVERY (1/4 %)				CORE BOXES		SAMPLES 13		EL. TOP OF CASING 897.72'		GROUND EL. 895.02'		DEPTH/EL. GROUND WATER		DEPTH/EL. TOP OF ROCK ≈ 51' / 844.02'			
SAMPLE HAMMER WEIGHT / FALL 1400 / 30"				CASING LEFT IN MOLE: DIA. / LENGTH 2" / 60'				LOGGED BY: P. Huidobro									
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH	CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS				ELEVATION	DEPTH, ft.	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO.		
					1st 6"	2nd 6"	3rd 6"	4th 6"									
									895.02								
SS	2'	0	25		10	11	8	6				1	0-13'. <u>Topsoil</u> . Black sandy muck, oxidized zones. LS and SS pebbles. Strong smell of rubber. Few isolated chunks of <u>fibrous peat</u> .		-		
SS	2'	1.2'	3		1	1	1	1				2			2		
									882.02								
SS	2'	1'	21		5	5	8	8	880.02			3	13'-15'. Brown fibrous <u>peat</u> . Strong creosote and H ₂ S smell.		3		
ST	10"	2.5'										4	15'-24'. Black <u>peat</u> . Very mature with shell fragments. Slightly fibrous. Strong creosote and H ₂ S smell.	@ 18' no washings come out during casing driving. Probably due to dissolution of organic materials.	4*		
SS	2'	1.5'	10		0	3	3	4				5			5		
SS	2'	1.5'	19		2	7	5	7	871.02			6	24'-26.5'. Brown silty <u>clay</u> with black blotches. Strong odor.		6		
									868.52								
SS	2'	1'	50		9	15	18	17				7	26.5'-51'. <u>Outwash</u> . Poorly sorted medium to coarse sand and fine to medium gravel. Isolated chunks of bituminous material. Mineralogy of sand is mostly quartz and rock fragments. Gravel is chiefly limestone, mafic rocks, granitic rocks and agate (red). Strong odor of H ₂ S and creosote		7		
SS	2'	0	53		20	20	17	16				8			-		
SS	2'	0	26		24	12	7	7				9			-		
SS	2'	0.5'	99		28	41	30	28				10			-		
														*Sample for physical measurements only			
SS = SPLIT SPOON; ST = SHELBY TUBE O = DENNISON; P = PITCHER; Q = OTHER										SITE Filled swamp S of Hy 7; 164 W of W13				HOLE NO. PB144			

BORING LOG										PROJECT Reilly Tar		JOB NO 1-619-078	SHEET NO 2 OF 2	HOLE NO PB144	
SAMPLE TYPE AND DIAMETER	SAMPLER ADVANCE LENGTH CORE RUN	SAMPLE RECOVERY CORE RECOVERY	SAMPLE BLOWS "N"	PERCENT CORE RECOVERY	PENETRATION BLOWS			ELEVATION	DEPTH, FT	GRAPHIC LOG	SAMPLE	DESCRIPTION AND CLASSIFICATION	NOTES ON: WATER LEVELS, WATER RETURN, CHARACTER OF DRILLING, ETC	LAB SAMPLE NO	
					1st 6"	2nd 6"	3rd 6"								
SS	2'	0	130		48	43	41	34				11			
									844.02						
SS	2'	0	89		55	36	28	25				12			
SS	1'	0	-		177	238			836.02			13	Bottom of hole.		

SS - SPLIT SPOON; ST - SHELBY TUBE
O - DENNISON; P - PITCHER; Q - OTHER

SITE Filled swamp S of Hy 7; 164 W of W13

HOLE NO.
PB144

OBSERVATION WELL CONSTRUCTION SUMMARY

PROJECT <u>Reilly Tar</u>		WELL NO. <u>PB144</u>	
SITE <u>Filled swamp;</u>		AQUIFER <u>Glacial Drift</u>	
COORDINATES _____		DATE COMPLETED <u>11/19/82</u>	
SUPERVISED BY <u>P. Huidobro</u>			

GENERALIZED STRATIGRAPHY		Elevation of reference point	<u>897.72</u>
		Height of reference point above ground surface	<u>2.70'</u>
	GROUND ELEVATION <u>895.02</u>	Depth of surface seal	<u>1'</u>
	Top soil	Type of surface seal: <u>concrete</u>	
		I.D. of surface casing	<u>4"</u>
	Fibrous peat	Type of surface casing: <u>black steel</u>	
	Black peat	Depth of surface casing	<u>4.3'</u>
		I.D. of riser pipe	<u>2"</u>
		Type of riser pipe: <u>galvanized, coupled 10.5' section</u>	
		Diameter of borehole	<u>4"</u>
		Type of filler: <u>1:1 cement/bentonite</u>	
		Elevation / depth of top of seal	<u>853.72/41.3'</u>
		Type of seal: <u>6:1 cement bentonite</u>	
		Type of gravel pack <u>No. 20 silica sand</u>	
		Elev./depth of top of gravel pack	<u>852.72/42.3'</u>
	Elevation / depth of top of screen	<u>850.72/44.3'</u>	
	Description of screen	<u>No. 10 slot galvanized, welded steel</u>	
	I.D. of screen section	<u>2"</u>	
	Elevation / depth of bottom of screen	<u>847.72/47.3'</u>	
	Elev./depth of bottom of gravel pack	<u>843.02/52'</u>	
	Elev./depth of bottom of plugged blank section	<u>841.02/54'</u>	
	Type of filler below plugged section <u>bentonite</u>		
	Elevation of bottom of borehole	<u>836.02/59'</u>	

11/82
N.

ELEVATIONS OF MONITORING WELLS AND BORINGS INSTALLED BY

GCA Corp./Technology Division, Oct-Nov. 1982.

(Drilling Subcontractor: Braun Engineering Testing, Inc.)

Boring and/or Well #	Surface Elev.	Measuring Point Elev. (Well)	Stick Up	Benchmark Used
PB136	908.88	910.53	1.65	(1)*
PB137	909.14	910.90	1.76	(1)*
PB138	907.46	909.27	1.81	(2)*
PB139	893.67	896.45	2.78	(3)*
PB140	893.35	895.99	2.64	(4)**
B141	914.00	N/A***	N/A	(5)*
B142	890.11	N/A***	N/A	(5)*
PB144	895.02	897.72	2.70	(6)**

* St. Louis Park Benchmarks used: conversion factor = 710.30:

- * (1) Top of fire hydrant in SE corner of 36th Street and Burlington Northern RR spur; St. Louis Park Datum = 206.39.
- * (2) Top of fire hydrant in NE corner of Xylon Ave. and 34th St.; St. Louis Park Datum = 204.20.
- * (3) Top of fire hydrant in SW corner of Quebec Ave. and 34th St.; St. Louis Park Datum = 219.66.
- ** (4) Measuring Point on Well #W-27 = 910.49.
- * (5) Top of fire hydrant in SE corner of Louisiana Ave. and Walker St.; St. Louis Park Datum = 185.35.
- * (6) Measuring Point on Well #W-137 = 893.05

Survey conducted by David D. Vieau and Gregory L. Grabow of Braun Engineering Testing, Inc. on 3 December 1982 and 22 March 1983 (to remeasure wells PB140 and PB144 at request of Marc Hult, USGS).

Instruments used: Path Instruments Micro Level L-11, No. 6170011; adjustable tri-pod; adjustable rod marked off in 0.01-foot increments.

** Benchmark Locations and Elevations provided by M. Greg Juston, USGS, 22 March 1983.

*** Boring only - no well installed.

10/29/82
N.

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

From LOCATION : B. M. Hughes, Dayton Laboratory

DATE : 29 October 1982

SUBJECT : Reilly Tar and Chemical Corp. Project

REFERENCE :

Bill Roder (RTCC)
Files (MRC-Hughes)

RECEIVED

NOV 01 1982

TO : Gary Wilson
ERT
696 Virginia Road
Concord, Mass 01742

ERT

Enclosed are PNA screening chromatograms for RTCC extraction numbers 133-141 and volatile wide-scan screening chromatograms for the CH₂M Hill samples. Also enclosed are copies of MRC analytical request sheets associated with the Well 23 tar analysis and a summary table of all water samples received before September 20. At a later time, I will send copies of analytical request sheets for water samples received since September 20.





B. M. Hughes

BMH/cvd

Enc.

106390





ERT Task: 120

10/22/82
N.

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

From LOCATION : B. M. Hughes, Dayton Laboratory
DATE : 22 October 1982
SUBJECT : Reilly Tar and Chemical Corp. Project
REFERENCE :

cc: John Craun (ERT)
Bill Roder (RTCC)
Files (MRC-Hughes)

RECEIVED

OCT 25 1982

ERT

TO : Gary Wilson
ERT
696 Virginia Road
Concord, Mass 01742

incl 1) 9/82 SLR15 test
2) W13 samples
3) SLR 4, 5, 7, 9; H3; MW13 & 70 — in this file

Enclosed are PNA and wide-scan screening chromatograms for RTCC extraction numbers 106-129. In addition, I have enclosed a summary of documents which are contained in MRC's Reilly Tar and Chemical Corp. files. I will be sending you other deliverables as they become available, along with a set of MRC analytical request sheets for this project.

W13 analyses —
(the full set of analyses
...ie. PDCS wells & are in
the PDCS file).
wells sampled Aug-Sept
1982

B. M. Hughes
B. M. Hughes

BMH/cvd

Encs.

MRC will supply add to table 10/1/82

rec'd 10/1/82

I. SUMMARY OF REILLY TAR & CHEMICAL "ROUTINE" EXTRACTIONS AND ANALYSES

SAMPLE IDENTIFICATION	RTCC EXTRACTION NUMBER	COST ELEMENT ^a /BILLING MONTH ^b						
		A-1 ^c	A-2	A-3	B-1	B-2	A-3	B-3, B-4
		Extraction	PNA Screen	Wide Scan Screen	Coal Tar Quant.	PNA Quant.	VOA Screen	Detailed MS Interpret
CW #15 (After chlorination)	106	1 (Sept)	1(Sept)	1(Sept)	1(Sept)	1(Sept)		
CW #15 (After chlorination and filtration)	107	1	1	1	1	1		
CW #15 (At well head)	108	1	1	1	1	1		
Method Blank	109	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #15 (At well head)	110	1	1	1	1	1		
CW #15 (After well head and aeration)	111	1	1	1	1	1		
CW #15 (After chlorination)	112	1	1	1	1	1		
CW #15(After chlorination and filtration)	113	1	1	1	1	1		
CW #15 (After well head and aeration)	114	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #4	115	1	1	1	1	1		
CW #7	116	1	1	1	1	1		
MW #70	117	1	1	1	1	1		
MW #13	118	1	1	1	1	1		
CW #9	119	1	1	1	1	1		

if better results
been with better
if no better results, then
wide planned to be done

^a Number of cost element indicates the number of samples or fractions being billed in each category. N.C. indicates no charge for this unit (A certain number of Quality Control Samples are indicated).

^b Billing month indicates the actual month in which charges for the fraction/cost unit are made.

^c Key for cost unit charges (refer to 22 September 1982 letter and estimates to John Craun for full explanations).

A-1 = \$210/s; 1e; A-2 = \$159/sample; A-3 = \$159/sample; B-1 = \$200/sample; B-2 = \$200/s; 1e; B-3, B-4 = \$600/s; 1e.

1060397

I.

SUMMARY OF REILLY TAR & CHEMICAL "ROUTINE" EXTRACTIONS AND ANALYSES

SAMPLE IDENTIFICATION	RTCC EXTRACTION NUMBER	COST ELEMENT ^a /BILLING MONTH ^b						
		A-1 ^c Extraction	A-2 PNA Screen	A-3 Wide Scan Screen	B-1 Coal Tar Quant.	B-2 PNA Quant.	A-3 VOA Screen	B-3, B-4 Detailed MS Interpret
Method Blank	120	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #5	121	1	1	1	1	1		
Hopkins Well #3	122	1	1	1	1	1		
Deionized Water Spiked with Coal Tar	123	1	1	1	1	1		
Well #23 9/14/82 15:00	124	1	1	1	1	1		
Well #23 9/17/82 16:30	125	1	1	1	1	1		
Well #23 9/17/82 16:30	126	1	1	1	1	1		
Method Blank	127	N.C	N.C	N.C	N.C	N.C		
Well #23 7/29/82 861'	128	1	1	1	1	1		
Well #23 8/7/82 804.5'	129	1	1	1	1	1		

^a Number of cost element indicates the number of samples or fractions being billed in each category. N.C. indicates no charge for this unit (A certain number of Quality Control Samples are indicated).


^b Billing month indicates the actual month in which charges for the fraction/cost unit are made.

^c Key for cost unit charges (refer to 22 Sept 1982 letter and estimates to John Craun for full explanations).

A-1 = \$210/sample; A-2 = \$159/sample; A-3 = \$159/sample; B-1 = \$200/sample; B-2 = \$200/sample; B-3, B-4 = \$600/s le.


106398

106339




PNA Screen - QA/QC

106400




PNA Screen - QA/QC

106401



Wide Scan Screen - Cost Element A-3


ERT Task: 210



Wide Scan Screen - Cost Element A-3

ERT Task: 210


106402



Wide Scan Screen - QA/QC


106403

106404



Wide Scan Screen - Cost Element A-3.


FRT Task: 210



PNA Screen - Cost Element A-2

ERT Task: 120


106405



PNA Screen - Cost Element A-2

ERT Task: 120


106406




PNA Screen - Cost Element A-2

ERT Task: 120,220


106407





PNA Screen - QA/QC

106409




Wide Scan Screen - Cost Element A-3

ERT Task: 220

106440


Titte packov



PNA Screen - Cost Element A-2

ERT Task: 220


106411



Wide Scan Screen - Cost Element A-3

ERT Task: 120,220


106412



Wide Scan Screen - Cost Element A-3


ERT Task: 120

106413




PNA Screen - QA/QC

106414




PNA Screen - QA/QC

106415



Wide Scan Screen - QA/QC


106416



PNA Screen - Cost Element A-2

ERT Task: 120,220


106417



PNA Screen - Cost Element A-2


ERT Task: 220

106418




PNA Screen - QA/QC

106419



PNA Screen - QA/QC


106420



PNA Screen - Cost Element A-2

ERT Task: 210


106421



PNA Screen - Cost Element A-2

ERT Task: 210

106422



PNA Screen - Cost Element A-2

ERT Task: 210

106423

rec'd 10/1/83

TABLE 6. RESULTS OF SIM ANALYSES FOR PNAs FOR CH₂M HILL WATER SAMPLES

SLP #9

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Method Blank RTCC-120	Monitor Well #9 RTCC-119	Monitor Well #70 RTCC-117	
					Concentration (ng/L)			
Naphthalene	1	1.3	11.42	128	38	90	34	
Methyl naphthalene (#1)	2	2.1	13.60	141	11	17	11	
" " (#2)	3	2.1	13.90	"	5.4	3.3	5.4	
Biphenyl	4	6.1	15.13	152	8.9	7.3	94	
Me ₂ -naphthalene (#1)	5			141				
" (#2)	6	3.4	15.43	"	4.6	6.9	59	
" (#3)	7	3.4	15.82	"	10	15	19	
" (#4)	8	3.4	16.17	"	8.2	5.3	4.3	
" (#5)	9	3.4	16.43	"	8.4	3.7	7.9	
" (#6)	10	3.4	16.93	"	4.0	4.1	9.0	
" (#7)	11	3.4		"				
Acenaphthalene	12	1.1	16.32	152	1.0	2.6	130	

TABLE 6 (continued)

SLP #9

1106425

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Method Blank RTCC-120	Monitor Well #9 RTCC-119	Monitor Well #70 RTCC-117	
					Concentration (ng/L)			
Dihydroacenaphthene	13	4.7	16.90	152	4.8	13	660	
Dibenzofuran	14	1.4	17.42	168	7.0	8.8	21	
Fluorene	15	2.2	18.48	166	3.7	9.1	380	
Me-dihydronaphthene (#1)	16	2.7	18.78	168	ND ^b	3.6	66	
" (#2)	17	2.7	18.88	"	ND	4.2	47	
Me-dibenzofuran (#1)	18	2.2	19.07	182	1.0	1.7	45	
" (#2)	19	2.2	19.27	"	1.5	2.3	79	
Phenanthrene	20	1.7	21.35	178	24	35	13	
Anthracene	22	1.7	21.48	"	ND	4.3	6.7	
Me-phenanthrene (#1)	23	2.6	22.90	192	0.51	1.7	52	
" (#2)	24	2.6	22.98	"	ND	ND	ND	
" (#3)	25	2.6	23.23	"	0.71	0.91	36	
" (#4)	26	2.6	23.30	"	ND	ND	ND	

TABLE 6 (continued)

SLP #9

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Method Blank RTCC-120	Monitor Well #9 RTCC-119	Monitor Well #70 RTCC-117	
					Concentration (ng/L)			
Me-phenanthrene (#5)	27	2.6	23.30	192	ND	ND	ND	
Phenyl naphthalene	28	2.5	23.90	204	1.3	2.0	21	
MW = 188	29		23.18	188	ND	ND	1.2	
Fluoranthene	31	2.0	25.02	202	4.7	16	24	
Pyrene	32	2.0	25.65	"	4.4	15	180	
Benzo(a)anthracene	33	5.3	29.38	228	ND	1.7	10	
Chrysene	34	5.3	29.52	"	1.6	ND	ND	
MW = 252 (#1)	36	6.8	32.50	252	ND	4.8	ND	
" (#2)	37	6.8	32.80	"	ND	ND	ND	
" (#3)	38	6.8	33.20	"	ND	0.6	ND	
Benzo(a)pyrene	39	6.8	33.30	"	ND	ND	ND	
MW = 252 (#4)-perylene	40	6.8	33.60	"	ND	ND	ND	
MW = 228 (#1)-Benzo(c)-phenanthrene	41	5.3	28.8	228	ND	ND	3.7	

100420

TABLE 6 (continued)

SLP #9

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Method Blank RTCC-120	Monitor Well #9 RTCC-119	Monitor Well #70 RTCC-117	
					Concentration (ng/L)			
MW = 228 (#2)	42	5.3	29.73	228	ND	ND	ND	
MW = 202	43	4.1	25.32	202	ND	ND	2.7	
MW = 276 (#1)	44	10	35.90	276	ND	ND	ND	
Indeno(1,2,3,cd)pyrene	45	10	36.21	"	ND	ND	ND	
Benzo(g,h,i)perylene	46	10	36.82	"	ND	ND	ND	
MW = 276 (#2)	47	10	37.20	"	ND	ND	ND	
Dibenzothiophene	62	1.7	20.97	184	2.3	2.6	45	

TABLE 6 (continued)

SLP #9

100428

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Method Blank RTCC-120	Monitor Well #9 RTCC-119	Monitor Well #70 RTCC-117	
					Concentration (ng/L)			
Anthracene-d ₁₀ (IS)	21	1.7	21.43	188	25	25	25	
Surrogate Spiking Compound		Amount added (ng/L)			Recovery (%)			
Naphthalene-d ₈	63	100	11.42	136	42	55	42	
Chrysene-d ₁₂	35	100	29.42	240	58	53	59	

^a L.O.D. = limit of detection in ng/L.^b ND = none detected with a detection limit given by the L.O.D. value for each feature.

TABLE 7. RESULTS OF SIM ANALYSES FOR PNAs CH₂M HILL WATER SAMPLES

SLP 4 SLP 5 SLP 7

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Hopkins Well #3 RTCC-122	City Well #4 RTCC-115	Monitor Well #5 RTCC-121	City Well #7 RTCC-116
					Concentration (ng/L)			
Naphthalene	1	1.3	11.42	128	35	30	31	27
Methyl naphthalene (#1)	2	2.1	13.60	141	9.9	9.8	8.9	9.3
" (#2)	3	2.1	13.90	"	4.7	14	5.4	2.0
Biphenyl	4	6.1	15.13	152	9.0	13	5.5	12
Me ₂ -naphthalene (#1)	5			141				
" (#2)	6	3.4	15.43	"	5.6	8.5	6.0	9.2
" (#3)	7	3.4	15.82	"	10	9.3	6.0	7.8
" (#4)	8	3.4	16.17	"	3.9	9.5	6.9	8.1
" (#5)	9	3.4	16.43	"	6.4	5.2	5.6	6.6
" (#6)	10	3.4	16.93	"	ND ^b	ND	4.0	ND
" (#7)	11	3.4		"				
Acenaphthalene	12	1.1	16.32	152	1.8	4.6	12	11

TABLE 7 (continued)

SLP 4 SLP 5 SLP 7

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Hopkins Well #3 RTCC-122	City Well #4 RTCC-115	Monitor Well #5 RTCC-121	City Well #7 RTCC-116
					Concentration (ng/L)			
Dihydroacenaphthene	13	4.7	16.90	152	5.6	94	ND	26
Dibenzofuran	14	1.4	17.42	168	7.2	ND	1.2	9.5
Fluorene	15	2.2	18.48	166	3.5	13	6.8	10
Me-dihydronaphthene (#1)	16	2.7	18.78	168	ND	ND	ND	4.3
" (#2)	17	2.7	18.88	"	ND	6.9	ND	5.0
Me-dibenzofuran (#1)	18	2.2	19.07	182	1.3	3.1	9.0	1.9
" (#2)	19	2.2	19.27	"	1.6	2.3	ND	2.9
Phenanthrene	20	1.7	21.35	178	9.3	29	6.8	11
Anthracene	22	1.7	21.48	"	0.61	1.0	14	1.2
Me-phenanthrene (#1)	23	2.6	22.90	192	0.46	2.5	ND	2.9
" (#2)	24	2.6	22.98	"	ND	ND	ND	ND
" (#3)	25	2.6	23.23	"	ND	2.9	2.0	2.5
" (#4)	26	2.6	23.30	"	1.8	ND	ND	ND

106430

TABLE 7 (continued)

S2P 4 S2P 5 S2P 7

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Hopkins Well #3 RTCC-122	City Well #4 RTCC-115	Monitor Well #5 RTCC-121	City Well #7 RTCC-116
					Concentration (ng/L)			
Me-phenanthrene (#5)	27	2.6	23.30	192	ND	ND	ND	ND
Phenyl naphthalene	28	2.5	23.90	204	0.89	1.1	ND	2.0
MW = 188	29		23.18	188	ND	ND	ND	ND
Fluoranthene	31	2.0	25.02	202	5.4	7.1	1.5	3.6
Pyrene	32	2.0	25.65	"	6.6	6.9	3.1	7.8
Benzo(a)anthracene	33	5.3	29.38	228	ND	0.63	ND	ND
Chrysene	34	5.3	29.52	"	2.3	1.4	3.4	2.7
MW = 252 (#1)	36	6.8	32.50	252	ND	2.1	ND	ND
" (#2)	37	6.8	32.80	"	ND	ND	ND	ND
" (#3)	38	6.8	33.20	"	ND	ND	ND	ND
Benzo(a)pyrene	39	6.8	33.30	"	ND	ND	ND	ND
MW = 252 (#4)-perylene	40	6.8	33.60	"	ND	ND	ND	ND
MW = 228 (#1)-Benzo(c)-phenanthrene	41	5.3	28.8	228	ND	ND	ND	ND

TABLE 7 (continued)

SLP 4 SLP 5 SLP 7

1006432

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Hopkins Well #3 RTCC-122	City Well #4 RTCC-115	Monitor Well #5 RTCC-121	City Well #7 RTCC-116
					Concentration (ng/L)			
MW = 228 (#2)	42	5.3	29.73	228	ND	ND	ND	ND
MW = 202	43	4.1	25.32	202	ND	ND	ND	ND
MW = 276 (#1)	44	10	35.90	276	ND	ND	ND	ND
Indeno(1,2,3,cd)pyrene	45	10	36.21	"	ND	ND	ND	ND
Benzo(g,h,i)perylene	46	10	36.82	"	ND	ND	ND	ND
MW = 276 (#2)	47	10	37.20	"	ND	ND	ND	ND
Dibenzothiophene	62	1.7	20.97	184	1.9	2.1	13	2.6

TABLE 7 (continued)

SLP 4 SLP 5 SLP 7

Feature Identification	Feature Number	Feature L.O.D. ^a	Feature RT (min)	Feature Mass	Sample Identification			
					Hopkins Well #3 RTCC-122	City Well #4 RTCC-115	Monitor Well #5 RTCC-121	City Well #7 RTCC-116
					Concentration (ng/L)			
Anthracene-d ₁₀ (IS)	21	1.7	21.43	188				
Surrogate Spiking Compound		Amount added (ng/L)			Recovery (%)			
Naphthalene-d ₈	63	100	11.42	136	50	44	39	49
Chrysene-d ₁₂	35	100	29.42	240	57	82	53	63

^aL.O.D. = limit of detection in ng/L.^bND = none detected with a detection limit given by the L.O.D. value for each feature.

10/22/82
N/

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

FROM LOCATION : B. M. Hughes, Dayton Laboratory
DATE : 22 October 1982
SUBJECT : Reilly Tar and Chemical Corp. Project
REFERENCE :

cc : John Craun (ERT)
Bill Roder (RTCC)
Files (MRC-Hughes)

RECEIVED

OCT 23 1982

TO : Gary Wilson
ERT
696 Virginia Road
Concord, Mass 01742

*Incl. 4/9/82 sep 15 test.
2) w23 samples
3) sep 4, 5, 7, 9; H3; MW13470 ← in this file*

ERT

Enclosed are PNA and wide-scan screening chromatograms for RTCC extraction numbers 106-129. In addition, I have enclosed a summary of documents which are contained in MRC's Reilly Tar and Chemical Corp. files. I will be sending you other deliverables as they become available, along with a set of MRC analytical request sheets for this project.



B. M. Hughes

BMH/cvd

Encs.

106316

SC will supply add to table

rec'd 10/14/82

1.

SUMMARY OF REILLY TAR & CHEMICAL "ROUTINE" EXTRACTIONS AND ANALYSES

SAMPLE IDENTIFICATION	RTCC EXTRACTION NUMBER	COST ELEMENT ^a /BILLING MONTH ^b						
		A-1 ^c	A-2	A-3	B-1	B-2	A-3	B-3, B-4
		Extraction	PNA Screen	Wide Scan Screen	Coal Tar Quant.	PNA Quant.	VOA Screen	Detailed MS Interpret
CW #15 (After chlorination)	106	1 (Sept)	1(Sept)	1(Sept)	1(Sept)	1(Sept)		
CW #15 (After chlorination and filtration)	107	1	1	1	1	1		
CW #15 (At well head)	108	1	1	1	1	1		
Method Blank	109	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #15 (At well head)	110	1	1	1	1	1		
CW #15 (After well head and aeration)	111	1	1	1	1	1		
CW #15 (After chlorination)	112	1	1	1	1	1		
CW #15(After chlorination and filtration)	113	1	1	1	1	1		
CW #15 (After well head and aeration)	114	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #4	115	1	1	1	1	1		
CW #7	116	1	1	1	1	1		
MW #70	117	1	1	1	1	1		
MW #13	118	1	1	1	1	1		
CW #9	119	1	1	1	1	1		

Number of cost element indicates the number of samples or fractions being billed in each category. N.C. indicates no charge for this unit (A certain number of Quality Control Samples are indicated).

^b Billing month indicates the actual month in which charges for the fraction/cost unit are made.

^c Key for cost unit charges (refer to 22 September 1982 letter and estimates to John Craun for full explanations).

A-1 = \$250/sample; A-2 = \$150/sample; A-3 = \$150/sample; B-1 = \$200/sample; B-2 = \$200/sample; B-3 = \$100/sample; B-4 = \$100/sample

105317

1.

SUMMARY OF REILLY TAR & CHEMICAL "ROUTINE" EXTRACTIONS AND ANALYSES

SAMPLE IDENTIFICATION	RTCC EXTRACTION NUMBER	COST ELEMENT ^a /BILLING MONTH ^b						
		A-1 ^c Extraction	A-2 PNA Screen	A-3 Wide Scan Screen	B-1 Coal Tar Quant.	B-2 PNA Quant.	A-3 VOA Screen	B-3, B-4 Detailed MS Interpret
Method Blank	120	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #5	121	1	1	1	1	1		
Hopkins Well #3	122	1	1	1	1	1		
Deionized Water Spiked with Coal Tar	123	1	1	1	1	1		
Well #23 9/14/82 15:00	124	1	1	1	1	1		
Well #23 9/17/82 16:30	125	1	1	1	1	1		
Well #23 9/17/82 16:30	126	1	1	1	1	1		
Method Blank	127	N.C	N.C	N.C	N.C	N.C		
Well #23 7/29/82 861'	128	1	1	1	1	1		
Well #23 8/7/82 804.5'	129	1	1	1	1	1		

^a Number of cost element indicates the number of samples or fractions being billed in each category. N.C. indicates no charge for this unit (A certain number of Quality Control Samples are indicated).

^b Billing th indicates the actual month in which charges for the fraction/cost unit are made.

^c Key for cost unit charges (refer to 22 September 1982 letter and estimates to John Craun for full explanations).

106348

[illegible]

ERT Task: 120

FRN:	X =	.25	Y =	1.00																																								
CU #9																																												
MW #70																																												
ORGANIC-FREE WATER BLANK																																												
TIME	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45

ERT Task: 120




Figure 3. Comparison of selected screening chromatograms for RTCC Study. Full Scale response for each chromatogram corresponds to 2.5 µg/L anthracene-d10.

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

From LOCATION : B. M. Hughes, Dayton Laboratory
DATE : 22 October 1982
SUBJECT : Reilly Tar and Chemical Corp. Project
REFERENCE :

cc: John Craun (ERT)
Bill Roder (RTCC)
Files (MRC-Hughes)

RECEIVED

OCT 25 1982

TO : Gary Wilson
ERT
696 Virginia Road
Concord, Mass 01742

*incl. 9/82 SLPIS test**2) W23 samples**3) SLP 4, 5, 7, 9; H3; MW13170***ERT***← in this file*

Enclosed are PNA and wide-scan screening chromatograms for RTCC extraction numbers 106-129. In addition, I have enclosed a summary of documents which are contained in MRC's Reilly Tar and Chemical Corp. files. I will be sending you other deliverables as they become available, along with a set of MRC analytical request sheets for this project.



B. M. Hughes

BMH/cvd

Encs.

106352

AKC will simply add to bill

rec'd 10/14/82

1.

SUMMARY OF REILLY TAR & CHEMICAL "ROUTINE" EXTRACTIONS AND ANALYSES

11/11/82
addition for 10/1/82

SAMPLE IDENTIFICATION	RTCC EXTRACTION NUMBER	COST ELEMENT ^a /BILLING MONTH ^b						
		A-1 ^c Extraction	A-2 PNA Screen	A-3 Wide Scan Screen	B-1 ^c Coal Tar Quant.	B-2 PNA Quant.	A-3 VOA Screen	B-3, B-4 ^c Detailed MS Interpret
CW #15 (After chlorination)	106	1 (Sept)	1 (Sept)	1 (Sept)	1 (Sept)	1 (Sept)		
CW #15 (After chlorination and filtration)	107	1	1	1	1	1		
CW #15 (At well head)	108	1	1	1	1	1		
Method Blank	109	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #15 (At well head)	110	1	1	1	1	1		
CW #15 (After well head and aeration)	111	1	1	1	1	1		
CW #15 (After chlorination)	112	1	1	1	1	1		
CW #15 (After chlorination and filtration)	113	1	1	1	1	1		
CW #15 (After well head and aeration)	114	N.C.	N.C.	N.C.	N.C.	N.C.		
CW #4	115	1	1	1	1	1		
CW #7	116	1	1	1	1	1		
MW #70	117	1	1	1	1	1		
MW #13	118	1	1	1	1	1		
CW #9	119	1	1	1	1	1		

if 1/1/82
Review to see if
1/1/82
wide spread

^a Number of cost element indicates the number of samples or fractions being billed in each category. N.C. indicates no charge for this unit (A certain number of Quality Control Samples are indicated).


^b Billing month indicates the actual month in which charges for the fraction/cost unit are made.

^c Key for cost unit charges (refer to 22 September 1982 letter and estimates to John Craun for full explanations).

A-1 = \$210/sample; A-2 = \$159/sample; A-3 = \$159/sample; B-1 = \$200/sample; B-2 = \$200/sample; B-3 = \$200/sample; B-4 = \$200/sample


106353

106355



PNA Screen - Cost Element A-2


ERT Task: 220



PNA Screen - Cost Element A-2

ERT Task: 220


106356



PNA Screen - Cost Element A-2

ERT Task: 220


106357



PNA Screen - Cost Element A-2

ERT Task: 220


106358



PNA Screen - Cost Element A-2

ERT Task: 220


106359



PNA Screen - Cost Element A-2

ERT Task: 220

106360



PNA Screen - Cost Element A-2

ERT Task: 120

106361

TABLE 30. RESULTS OF SIM ANALYSES FOR PNAs FOR THE NOVEMBER 1982 OW #23 TREATMENT SYSTEM STUDY

Date: January 21, 1983

ERT Task: 220

Feature Identification (Q. Mass)	Feature Number	Feature L.O.D. ^a	Sample Identification					
			148 (dil 1:1000)	149 (dil 1:1000)	150 (dil 1:100)	151 (dil 1:1000)	152 (dil 1:100)	
			Concentration (ng/L)					
Indene (116)	64	3.2x10 ²	3.8 x 10 ⁴	6.1 x 10 ⁴	1.4 x 10 ⁵	6.7 x 10 ⁴	6.0 x 10 ⁴	
2,3-Dihydroindene (118)	65	4.5x10 ²	2.3 x 10 ⁴	4.2 x 10 ⁴	4.7 x 10 ⁴	4.4 x 10 ⁴	2.6 x 10 ⁴	
Naphthalene (128)	1	200	6.0 x 10 ⁴	4.6 x 10 ⁵	8.5 x 10 ⁵	5.8 x 10 ⁵	4.7 x 10 ⁵	
2-Methylnaphthalene (141)	2	3.6x10 ²	7.5 x 10 ⁴	3.0 x 10 ⁵	3.2 x 10 ⁵	3.4 x 10 ⁵	2.3 x 10 ⁵	
1-Methylnaphthalene (141)	3	3.7x10 ²	1.7 x 10 ⁵	2.7 x 10 ⁵	1.8 x 10 ⁵	2.6 x 10 ⁵	1.4 x 10 ⁵	
Biphenyl (154)	4	2.5x10 ²	4.7 x 10 ⁴	9.0 x 10 ⁴	5.4 x 10 ⁴	7.5 x 10 ⁴	4.3 x 10 ⁵	
C ₂ -naphthalene (141) - Total	5-11	3.7x10 ²	2.0 x 10 ⁴	2.7 x 10 ⁵	9.5 x 10 ⁴	1.9 x 10 ⁵	8.7 x 10 ⁴	
Acenaphthylene (152)	12	1.1x10 ³	3.6 x 10 ⁴	6.5 x 10 ⁴	4.3 x 10 ⁴	1.2 x 10 ⁵	3.0 x 10 ⁴	
Dihydroacenaphthylene (154)	13	50	1.2 x 10 ⁵	2.0 x 10 ⁵	1.0 x 10 ⁵	2.0 x 10 ⁵	9.3 x 10 ⁴	
Fluorene (166)	15	300	2.4 x 10 ⁵	2.2 x 10 ⁵	1.2 x 10 ⁵	2.5 x 10 ⁵	1.1 x 10 ⁵	
Phenanthrene (178)	20	300	5.6 x 10 ⁵	6.5 x 10 ⁵	1.6 x 10 ⁵	4.4 x 10 ⁵	1.3 x 10 ⁵	
Anthracene (178)	22	300	2.4 x 10 ⁵	2.3 x 10 ⁵	2.9 x 10 ⁴	1.7 x 10 ⁵	2.5 x 10 ⁴	


TABLE 30 (continued)

Feature Identification (Q. Mass)	Feature Number	Feature L.O.D. ^a	Sample Identification					
			148 (dil 1:1000)	149 (dil 1:1000)	150 (dil 1:100)	151 (dil 1:1000)	152 (dil 1:100)	
			Concentration (ng/L)					
Fluoranthene (202)	31	300	2.6 × 10 ⁵	3.6 × 10 ⁵	3.5 × 10 ⁴	2.1 × 10 ⁵	2.4 × 10 ⁴	
Pyrene (202)	32	900	1.9 × 10 ⁵	2.8 × 10 ⁵	2.7 × 10 ⁴	1.7 × 10 ⁵	1.5 × 10 ⁴	
Benzo(a)anthracene (228)	33	100	1.2 × 10 ⁵	2.9 × 10 ⁵	1.1 × 10 ⁴	9.2 × 10 ⁴	6.4 × 10 ³	
Chrysene (228)	34	800	2.4 × 10 ⁵	2.1 × 10 ⁵	9.2 × 10 ³	1.3 × 10 ⁵	5.9 × 10 ³	
Benzo(b)fluoranthene (252)	36	2.4x10 ³	2.9 × 10 ³	2.6 × 10 ⁵	3.6 × 10 ⁴	2.9 × 10 ⁵	1.5 × 10 ⁴	
Benzo(k)fluoranthene (252)	37	2.4x10 ³	2.9 × 10 ³	2.6 × 10 ⁵				
Benzo(e)pyrene (as 39) (252)	38	1.3x10 ³	3.8 × 10 ⁴	2.5 × 10 ⁴	2.4 × 10 ³	1.9 × 10 ⁴	1.1 × 10 ³	
Benzo(a)pyrene (252)	39	1.3x10 ³	5.7 × 10 ⁴	6.5 × 10 ⁴	4.2 × 10 ³	3.0 × 10 ⁴	1.9 × 10 ³	
Perylene (as 39) (252)	40	1.3x10 ³	6.9 × 10 ³	8.5 × 10 ³	9.0 × 10 ²	5.8 × 10 ³	ND ^b	
Indeno(1,2,3,cd)pyrene (276)	45	2.3x10 ³	2.9 × 10 ⁴	2.4 × 10 ⁴	2.7 × 10 ³	2.3 × 10 ⁴	ND	
Dibenz(a,h)anthracene (278)	66	1.9x10 ³	ND	ND	ND	ND	ND	
Benzo(g,h,i)perylene (276)	46	1.4x10 ³	6.3 × 10 ³	1.2 × 10 ⁴	1.7 × 10 ³	1.2 × 10 ⁴	ND	
Acridine (178)	67	2.9x10 ³	ND	2.5 × 10 ⁵	1.5 × 10 ⁴	ND	1.1 × 10 ⁴	

TABLE 30 (continued)

Feature Identification (Q. Mass)	Feature Number	Feature L.O.D. ^a	Sample Identification					
			148 (dil 1:1000)	149 (dil 1:1000)	150 (dil 1:100)	151 (dil 1:1000)	152 (dil 1:100)	
			Concentration (ng/L)					
Carbazole (166)	68	1.9x10 ³	2.4 x 10 ⁴	6.6 x 10 ⁴	3.6 x 10 ⁴	3.5 x 10 ⁴	3.3 x 10 ⁴	
Anthracene-d ₁₀ (IS) (188)	21	-	25	25	25	25	25	
		Amount added (ng/L)	Recovery (%)					
Surrogate Spiking Compound								
Naphthalene-d ₈ (136)	63	100	-	-	-	-	-	
Chrysene-d ₁₂ (240)	35	100	-	-	-	-	-	

^a L.O.D. = limit of detection.^b ND = none detected with a detection limit given by the L.O.D. value (in ng/L) for each compound for 1:100 dilution.




PNA Screen - Cost Element A-2

ERT Task: 220

106365

106366



PNA Screen - Cost Element A-2


ERT Task: 220

REILLY 1638 + D6 (20 UG/L)
11-17-82 SM

** SPECTRUM DISPLAY/EDIT **

FRN 16372
1ST SC/PQ: 1
X= .25 Y= 1.00

FS = 50 μ S/L



VOA Screen - OW#23(11051010) - Cost Element A-3

ERT Task: 220

106367

20 OCT 82 15:27 7

GCA Soils Boring Project
Reilly Tar Site
St. Louis Park, Minnesota

10/20/82 N.
Mike Kogutsky
Off. Waste Program
Enforcement

382-4833 14

EPA CONCENTER

USGS
Project
Number

Boring
Number

Piezometer
Number

Location

Detail
Map

Purpose

PB 137

1

1

36th & Minnehaha Creek

Yes

Shake down; un-
contaminated peat
sample, drift well

PB 136

2

2

36th & Minnehaha Creek

Yes

Uncontaminated
Platteville well;
samples of
uncontaminated
drift soils

PB 138

3

3

34th & Wyoming near
SLP #5

No

Platteville well
at edge of known
contamination; drift
samples near edge of
known contamination

PB 139

4

4

32nd & Rhode Island/
Quebec, Oak Hill Park

Yes

Drift well near
area of suspected
disposal, previously
not investigated

PB 140

5

5

Rear W23, Reilly
deep well

No

Drift well to
determine conta-
mination of drift
near major source of
PbC/D contamination

PB 141

6

--

On Highway 7, west of
Louisiana Ave. Extension

Yes

Drift boring to
determine effect of
highway construction
on lacustrine
deposits

PB 142

7

--

Walker Ave. and
Louisiana Ave. Extension

Yes

Drift boring to
determine northern
extent of contami-
nation in major
disposal area

PB 144

8

--

400' west of Boring #7

Yes

9

--


(Reserve)

If heavy contami-
nation found in
boring #7 or 8,
wait till second
round. If contami-
nation not found,
place near USGS K12

604 Soils Boring Project
Reilly Tar Site
St. Louis Park, Minnesota

*Mike Kogut
Off. Waste Program
Enforcement*

Boring Number	Piezometer Number	USGS Project Number	Location	Detail Map	Purpose
1	1		36th & Minnehaha Creek	Yes	Shake down; un-contaminated plat sample, drift well
2	2		36th & Minnehaha Creek	Yes	Uncontaminated Platterville well; samples of uncontaminated drift soils
3	3		34th & Wyoming near SLP #5	No	Platterville well at edge of known contamination; drift samples near edge of known contamination
4	4		32nd & Rhode Island/Quebec, Oak Hill Park	Yes	Drift well near area of suspected disposal, previously not investigated
5	5		Near W23, Reilly deep well	No	Drift well to determine contamination of drift near major source of POC/J contamination
6	--		On Highway 7, west of Louisiana Ave. Extension	Yes	Drift boring to determine effect of highway construction on lacustrine deposits
7	--		Walker Ave. and Louisiana Ave. Extension	Yes	Drift boring to determine northern extent of contamination in major disposal area
8	--		400' west of Boring #7	Yes	"
9	--		(Reserve)		If heavy contamination found in boring #7 or 8, wait til second round. If contamination not found, place near USGS #2





Boring # 7
(Either location)

WALKER

ST

Boring # 6

Railroad

STATE Hwy 7

186

HI

RLS.
S B

163

TRAC LAKE

13-3

159

V. C. I

N:1"
Scale: 1"=100'

3

272

322

70.74

Walker STREET

285.44

SUB.

327

Frontage road

VACATED

324

Boring AS

323

Hwy 7

OF

NO.

2' 5" VAC. FILED 9-9-57

FILED

274.9

(73)

5

123.6

2

(52)

9/24/82
N.



GCA CORPORATION
Technology Division

213 Burlington Road
Bedford, Massachusetts 01730
Telephone: 617-275-5444
Telex: 92-3339

September 24, 1982

Mike Kosakowski
U.S. Environmental Protection Agency
Office of Hazardous Waste Enforcement
Fairchild Building, 2nd Floor
499 S. Capital, S.W.
Washington, D.C. 20460

Subject: EPA Contract No. 68-01-6316
(GCA 1-452-124)

Dear Mike:

Enclosed please find base-neutral extractables results for the following samples:

- MWCC 1/20/82
- Presscake 1/22/82
- Presscake 1/27/82
- Presscake 1/29/82

All samples were prepared as specified in Interim Methods for the Sampling and Analysis of Priority Pollutants in Sediments and Fish Tissue (U.S. EPA, EMSL, Cinn., Ohio). Subsequent Priority Pollutant analyses were provided via GC/MS using a fused silica capillary column. Please note that all component concentrations are reported in mg/kg (ppm) of wet sample. Results are also provided for a replicate of GCA 19106 spiked with several polynuclear aromatic components (Table 1).

Should you have any questions concerning the enclosed information please do not hesitate to contact me.

Sincerely,

Mike Rennekamp
(1/4/82)

Mike Rennekamp
Senior Staff Scientist
Laboratory Analysis Department

cc: File 1-452-124

MER/mdp

TABLE I
Quality Control Sample
Spiked GCA 19106

Compound	Concentration mg/kg ^a		
	Expected	Reported	% Recovery
Acenaphthylene	3.6	2.8	78
Phenanthrene	1.4	1.4 ^b	100
Benzo (a) anthracene	2.1	2.1	100
Fluoranthene	3.6	3.8	105

a. Wet Weight Values

b. Corrected for Amount in the Sample (GCA 19106)

DATA REPORT SHEET
Base/Neutral Extractables

Sample I.D. Presscake 1/27/82

Analysis Date 7/14/82

Sample Matrix Sludge

Instrument HP 5985 GC/MS

Parameter	Ion Used to Quantitate	Concentration (mg/kg)	Remarks
acenaphthene		ND	
acenaphthylene		ND	
anthracene		ND	
phenanthrene	178	1.3	
benzo(a)anthracene		ND	
chrysene		ND	
benzo(a)pyrene		ND	
benzo(b)fluoranthene		ND	
benzo(k)fluoranthene		ND	
benzo(g,h,i)perylene		ND*	
indeno(1,2,3-cd)pyrene		ND*	
dibenzo(a,h)anthracene		ND*	
fluoranthene		ND	
pyrene		ND	
fluorene		ND	
naphthalene		ND	
2-chloronaphthalene		ND	
1,2-dichlorobenzene		ND	
1,3-dichlorobenzene		ND	
1,4-dichlorobenzene		ND	
1,2,4-trichlorobenzene		ND	
hexachlorobenzene		ND	
nitrobenzene		ND	
2,4-dinitrotoluene		ND	
2,6-dinitrotoluene		ND	
dimethyl phthalate		ND	
diethyl phthalate		ND	
di-n-butyl phthalate		ND	
dioctyl phthalate		ND	
butyl benzyl phthalate		ND	
bis(2-ethylhexyl) phthalate	149	58	
bis(chloromethyl) ether		ND	
bis(2-chloroethyl) ether		ND	
bis(2-chloroisopropyl) ether		ND	
4-bromophenyl phenyl ether		ND	
4-chlorophenyl phenyl ether		ND	
N-nitrosodimethyl amine		ND	
N-nitrosodiphenyl amine		ND	
N-nitrosodi-n-propyl amine		ND	
hexachloroethane		ND	
bis(2-chloroethoxy) methane		ND	
isophorone		ND	
hexachlorobutadiene		ND	
3,3'-dichlorobenzidine		ND*	
benzidine		ND*	
1,2-diphenylhydrazine		ND	
hexachlorocyclopentadiene		ND	
2,3,7,8-tetrachlorodibenzo-p-dioxin		ND	

ND = < 1 mg/kg

ND* = < 4 µg/kg



GCA CORPORATION
Technology Division

DATA REPORT SHEET
Base/Neutral Extractables

Sample I.D. Presscake 1/29/82

Analysis Date 8/28/82

Sample Matrix Sludge

Instrument HP 5985 GC/MS

Parameter	Ion Used to Quantitate	Concentration (mg/kg)	Remarks
acenaphthene		ND	
acenaphthylene		ND	
anthracene		ND	
phenanthrene	178	1.1	
benzo(a)anthracene		ND	
chrysene		ND	
benzo(a)pyrene		ND	
benzo(b)fluoranthene		ND	
benzo(k)fluoranthene		ND	
benzo(g,h,i)perylene		ND*	
indeno(1,2,3-cd)pyrene		ND*	
dibenzo(a,h)anthracene		ND*	
fluoranthene		ND	
pyrene		ND	
fluorene		ND	
naphthalene		ND	
2-chloronaphthalene		ND	
1,2-dichlorobenzene		ND	
1,3-dichlorobenzene		ND	
1,4-dichlorobenzene		ND	
1,2,4-trichlorobenzene		ND	
hexachlorobenzene		ND	
nitrobenzene		ND	
2,4-dinitrotoluene		ND	
2,6-dinitrotoluene		ND	
dimethyl phthalate		ND	
diethyl phthalate		ND	
di-n-butyl phthalate		ND	
dioctyl phthalate		ND	
butyl benzyl phthalate		ND	
bis(2-ethylhexyl) phthalate	149	29	
bis(chloromethyl) ether		ND	
bis(2-chloroethyl) ether		ND	
bis(2-chloroisopropyl) ether		ND	
4-bromophenyl phenyl ether		ND	
4-chlorophenyl phenyl ether		ND	
N-nitrosodimethyl amine		ND	
N-nitrosodiphenyl amine		ND	
N-nitrosodi-n-propyl amine		ND	
hexachloroethane		ND	
bis(2-chloroethoxy) methane		ND	
isophorone		ND	
hexachlorobutadiene		ND	
3,3'-dichlorobenzidine		ND*	
benzidine		ND*	
1,2-diphenylhydrazine		ND	
hexachlorocyclopentadiene		ND	
2,3,7,8-tetrachlorodibenzo-p-dioxin		ND	

ND = < 1 mg/kg

ND* = < 4 mg/kg

GCA CORPORATION
Technology Division

DATA REPORT SHEET
Base/Neutral Extractables

Sample I.D. MWCC 1/20/82

Analysis Date 7/14/82

Sample Matrix Sludge

Instrument HP 5985 GC/MS

Parameter	Ion Used to Quantitate	Concentration (mg/kg)	Remarks
acenaphthene		ND	
acenaphthylene		ND	
anthracene		ND	
phenanthrene	178	1.2	
benzo(a)anthracene		ND	
chrysene		ND	
benzo(a)pyrene		ND	
benzo(b)fluoranthene		ND	
benzo(k)fluoranthene		ND	
benzo(g,h,i)perylene		ND*	
indeno(1,2,3-cd)pyrene		ND*	
dibenzo(a,h)anthracene		ND*	
fluoranthene		ND	
pyrene		ND	
fluorene		ND	
naphthalene	128	1.4	
2-chloronaphthalene		ND	
1,2-dichlorobenzene		ND	
1,3-dichlorobenzene		ND	
1,4-dichlorobenzene		ND	
1,2,4-trichlorobenzene		ND	
hexachlorobenzene		ND	
nitrobenzene		ND	
2,4-dinitrotoluene		ND	
2,6-dinitrotoluene		ND	
dimethyl phthalate		ND	
diethyl phthalate		ND	
di-n-butyl phthalate		ND	
dioctyl phthalate		ND	
butyl benzyl phthalate		ND	
bis(2-ethylhexyl) phthalate	149	67	
bis(chloromethyl) ether		ND	
bis(2-chloroethyl) ether		ND	
bis(2-chloroisopropyl) ether		ND	
4-bromophenyl phenyl ether		ND	
4-chlorophenyl phenyl ether		ND	
N-nitrosodimethyl amine		ND	
N-nitrosodiphenyl amine		ND	
N-nitrosodi-n-propyl amine		ND	
hexachloroethane		ND	
bis(2-chloroethoxy) methane		ND	
isophorone		ND	
hexachlorobutadiene		ND	
3,3'-dichlorobenzidine		ND*	
benzidine		ND*	
1,2-diphenylhydrazine		ND	
hexachlorocyclopentadiene		ND	
2,3,7,8-tetrachlorodibenzo-p-dioxin		ND	

ND = < 1 mg/kg

ND* = < 4 mg/kg



GCA CORPORATION
Technology Division

DATA REPORT SHEET
Base/Neutral Extractables

Sample I.D. Presscake 1/22/82Analysis Date 8/2/82Sample Matrix SludgeInstrument HP 5985 GC/MS

Parameter	Ion Used to Quantitate	Concentration (mg/kg)	Remarks
acenaphthene		ND	
acenaphthylene		ND	
anthracene		ND	
phenanthrene		ND	
benzo(a)anthracene		ND	
chrysene		ND	
benzo(a)pyrene		ND	
benzo(b)fluoranthene		ND	
benzo(k)fluoranthene		ND	
benzo(g,h,i)perylene		ND*	
indeno(1,2,3-cd)pyrene		ND*	
dibenzo(a,h)anthracene		ND*	
fluoranthene		ND	
pyrene		ND	
fluorene		ND	
naphthalene		ND	
2-chloronaphthalene		ND	
1,2-dichlorobenzene		ND	
1,3-dichlorobenzene		ND	
1,4-dichlorobenzene		ND	
1,2,4-trichlorobenzene		ND	
hexachlorobenzene		ND	
nitrobenzene		ND	
2,4-dinitrotoluene		ND	
2,6-dinitrotoluene		ND	
dimethyl phthalate		ND	
diethyl phthalate		ND	
di-n-butyl phthalate		ND	
dioctyl phthalate		ND	
butyl benzyl phthalate		ND	
bis(2-ethylhexyl) phthalate	149	61	
bis(chloromethyl) ether		ND	
bis(2-chloroethyl) ether		ND	
bis(2-chloroisopropyl) ether		ND	
4-bromophenyl phenyl ether		ND	
4-chlorophenyl phenyl ether		ND	
N-nitrosodimethyl amine		ND	
N-nitrosodiphenyl amine		ND	
N-nitrosodi-n-propyl amine		ND	
hexachloroethane		ND	
bis(2-chloroethoxy) methane		ND	
isophorone		ND	
hexachlorobutadiene		ND	
3,3'-dichlorobenzidine		ND*	
benzidine		ND*	
1,2-diphenylhydrazine		ND	
hexachlorocyclopentadiene		ND	
2,3,7,8-tetrachlorodibenzo-p-dioxin		ND	

ND = < 1 mg/kg

ND* = < 4 mg/kg



GCA CORPORATION
Technology Division

PAH Samples
St. Louis PARK, Minnesota
Municipal Raw Water Samples

DATE Collected: December 9, 1981

FIELD #

Municipal Well #

1 g

15

(code as #17)

2 g

15

3 l

14

4 l

14

5 l

14

6 l

14

7 l

14

8 g

16

SLP 15 = Municipal Well #

1 = Field #

PAH Samples
St. Louis Park, Minnesota
Municipal Raw Water Samples

Date Collected: December 9, 1981

Municipal Well number

1	17
2	15
3	14
4	14
5	14
6	14
7	14
8	16

recorded on bottle
followers
[SLP 15] = municipal
well no.
[2] = yield no.

Eight municipal raw water samples were collected on December 9, 1981 from the St Louis Park, Mn. municipal water system. The samples were collected between 1 p.m. and 3 p.m. according to standard state Department methods. The samples were placed in 200 ml bottles in coolers and packed with ice. The samples were turned over to Rick Brown at 4:30 p.m. December 9, 1981 X-ray fluorescence

Richard A. Jorgensen
Took possession at 4:30 pm on
December 9, 1981

Samples were left with me at 5:00 pm for pick up
at 5:15 by Andrew Brown.

Analysis of Polynuclear Aromatic Hydrocarbons
EPA Method 610

Instrument Conditions

- 1) Dupont Model 850 High Pressure Liquid Chromatograph.
- 2) Perkin-Elmer Analytical PAH 0258-0082 column.
- 3) Perkin-Elmer 650-10S Fluorescence Spectrophotometer; 15 nm slit setting; 280 nm Excitation, 389 nm Emission.
- 4) Perkin-Elmer LC-75 UV Spectrophotometric detector; 254 nm.
- 5) Gradient Elution - Linear gradient of 30% Acetonitrile/70% water, increasing to 100% Acetonitrile over 60 minutes; flow rate of 1.0 ml./min.
- 6) Injection volume - 30 microliters.



GCA CORPORATION
Technology Division


Calibration
Standard
No. 4

30 microliter injection
Flow: 1.0 ml./min.
chr. Spd.: 0.1 in./min.

ID	50 PW	40000 SS	1 BL	30 TP	AREA
526117					
216060					
142494					
106719					
333760B					
172151					
73211					
155388					
51065					
29962					
82212B					
39683					
32729B					
09115C					
98343					
7962					
47852					
43140					
99032					
02995T					

TIME	AREA
145	647397
500	23668
710	6995341
890	762341
1055	9741736
1140	3343406
1275	5174601
1380	54348
1410	63049
1550	2888437
1625	5391395
1795	860327
1845	255937
2030	8388238
2390	344619238
2585	412414538
2980	632384
3045	2969749
3425	143424
3495	95859
3695	13489066
	37694079T

NOTE: Acenaphthene and Benzo (a) Pyrene
calculated on separate calibration
curve due to co-eluting nature.




Calibration Standards for Naphthalene and Acenaphthene

30 microliter injection
Flow: 1.0 ml./min.
Chrt. Spd.: 0.1 in./min.

TIME	AREA
134	795584
544	52238
789	1049987
864	45932
924	77850
1124	6595159
1269	268035
1349	267651
	9172438T

TIME	AREA
149	757101
469	37094
599	57590
779	464262
929	255130
1114	2960336
1364	445521
1599	4640333
	9617367T



GCA No. 18/31-1

SLP-14

#10

ID

50 PW

40000 SS

1 BL

30 TP

TIME

AREA

136	24231371
741	1084934
871	4326934
1056	207227
1111	169796
1281	2144431
1641	572952
1756	245007
1866	208939
1981	165209
2056	4602060
2341	663593
2511	315029
2636	78560
2781	46067
2846	20671
2891	5611
3116	40817
3286	123504
	39252712T

30 ml #18/31-1 (3.0 ml in 4.5 cc)
30-7/08 1/2 C45 C48, 60 min.


3/26/82
Naphthalene

chest oil/water

Phenanthrene

Anthracene

Benzo(a) Anthracene



GCA No. 18131-2

SLP-14

9

ID

50 PW

40000 SS

1 BL

30 TP

TIME

AREA

135

25650567B

465

44144

730

1028817

875

4402428

1045

273839

1090

64690

1270

2478633

1620

330565

1730

488561

1845

144041

2025

4697240

2305

352509

2810

11473

3455

136894

40104401T

Benzo(a)Anthracene

Anthracene

Phenanthrene

Naphthalene

3/26/82

30ml 18131-2 (2ml in CH₃Cl)

30 → 100 CH₃Cl, 60 min

30 → 100 CH₃Cl, 60 min

305

4.4

5.3

6.35

8.4

GCA No. 18132

SLP-15

1:10 dilution
of extract

Anthracene 16.6

Acenaphthene

Fluorene 13.5

Fluoranthene 10.5

Triphenylene

Benzo (a) Anthracene 8.3

#	TIME	AREA	ID
39	39	16071	30 PW
179	179	992203	40000 SS
309	309	5035947	1 BL
489	489	2131758	30 TP
594	594	1835321	
879	879	18052973	
1159	1159	30732097	
1374	1374	6255104	
1479	1479	2224480	
1584	1584	1884864798	
1704	1704	85323	
1709	1709	515727	
1879	1879	2137413	
1984	1984	3480046	
2594	2594	66367	
2684	2684	46173	
2744	2744	96391	
2804	2804	222071	
3419	3419	37380	
3474	3474	11111	
3509	3509	31111	
3669	3669	333013	93304 741

30 ml #18132, 1:10 diln of 2.0 ml extract
30 ml #18132, 1:10 diln of 2.0 ml extract

GCA No. 18134
SLP-17

Acenaphthene

Fluorene

Triphenylene
Benzo

Anthracene

8

ID

50 PW

40000 SS

1 BL

30 TP

TIME

AREA

14	38895
129	164742168
299	232874
394	376101
469	685568
529	497711
564	222210
619	580395
734	393704
2004	229560820
2434	148204
2644	230265
2389	160034
3014	46435
3124	7294
3169	21437
3274	124432
3399	117841
3459	30787
3489	26365
3549	10959
3609	4455
3669	30037
3709	43300031

30 mL #18134 (2.0 mL CH₂Cl₂)

30 → 100% CH₂Cl₂ 1.60 min

1.4 min 3/30/82

19.09 min

1.65

5.75

745.535 8.4

GCA No. 18134

SLP-17

1:5 dilution
of extract

Anthracene

(27.9)

Acenaphthene

Fluorene

p-Triphenylene

Benzo(a) Anthracene

#10

ID

50 PW

40000 SS

1 BL

30 TP

TIME

AREA

132

3652691

292

65675

837

5025016

1032

4426000

1102

234625

1167

1232769

1377

2410763

1582

26449352B

1772

213573

1977

3742473

2057

153441

2577

81681

47608079T

30 uL #18134 1:5 dil'n

30 - 100% CH₂Cl₂

3/30/82

5.0

13.5

30 uL GC-562 (Blank)

30 - 100% CH₂Cl₂

3/30/82

4.3 4.9 5.75 6.26 6.5

GCA No. 18133

SLP-16

8

ID

50 PW

40000 SS

1 BL

30 TP

TIME

AREA

133 21123274

713 1364125

848 2434957

1028 71543

1078 76521

1243 3002297

1678 5154887

1808 490296

199301A 12851701

2643 948084

2933 167762

3018 150876

3258 97668

3408 83345

3543 40143

48057479T


Benzo(a)Anthracene

Phenanthrene

Naphthalene

30 mL 18133-2 (2 mL in CH₂Cl₂)
30 → 100% CH₂Cl₂ 60 min

30 mL 18133 (2.0 mL in CH₂Cl₂)
30 → 100% CH₂Cl₂ 60 min




GCA Soils Boring Project
Reilly Tar Site
St. Louis Park, Minnesota

*ike tosa
Waste Program
Enforcement*

Boring Number	Piezometer Number	USGS Project Number	Location	Detail Map	Purpose
1	1		36th & Minnehaha Creek	Yes	Shake down; un-contaminated peat sample, drift well
2	2		36th & Minnehaha Creek	Yes	Uncontaminated Platteville well; samples of uncontaminated drift soils
3	3		34th & Wyoming near SLP #5	No	Platteville well at edge of known contamination; drift samples near edge of known contamination
4	4		32nd & Rhode Island/Quebec, Oak Hill Park	Yes	Drift well near area of suspected disposal, previously not investigated
5	5		Near W23, Reilly deep well	No	Drift well to determine contamination of drift near major source of PdC/J contamination
6	--		On Highway 7, west of Louisiana Ave. Extension	Yes	Drift boring to determine effect of highway construction on lacustrine deposits
7	--		Walker Ave. and Louisiana Ave. Extension	Yes	Drift boring to determine northern extent of contamination in major disposal area
8	--		400' west of Boring #7	Yes	"
9	--		(Reserve)		If heavy contamination found in boring #7 or 8, wait til second round. If contamination not found, place near USGS W13

City of St. Louis Park, Minnesota

Exhibit No. 2



(4)

WEST 31st St

ISLAND

RHOE

2ND

22

PENNSYLVANIA

12-3

SCALE: 1 INCH = 100 FEET



Boring # 7
(Either location)

WALKER

① Boring # 6

STATE Hwy 7

Railroad

186

НЮ

RLS.

5 B 12

S.

LAKE

13-3

150

R.21

N: ↑
Scale: 1" = 100'

103

272

322

70.74

Walker STREET

285.44

SUB.

327

324

323

OF

July 7

NO.

Boring 108

FILED

FILED 99-57
VAC.
S.

EGGON
IN AV

123.6

(73)

274.9

2

(50)



CROSS REFERENCE LIST OF WATER SAMPLES RECEIVED FOR PAH ANALYSIS
(EPA Contract No. 68-01-6316)
(GCA 1-452-124)

Sampling date	Sample code	GCA Control No.
1/13/82	UM-827	18825
	UM-840	18826
	UM-847	18827
	UM-859	18828
	Ford Dam	18829
1/19/82	Field Blank (1/19/82)	18931
	EFF E	18932
	EFF W	18933
	Ford Dam	18934
	Gray Cloud	18935
	INF	18936
	UM-827	18937
	UM-840	18938
	UM-847	18939
1/21/82	UM-859	18940
	Field Blank (1/21/82)	18977
	EFF E	18978
	EFF W	18979
	INF E	18980
	INF ISCO	18981
1/26/82	Field Blank (1/26/82)	19099
	INF E	19100
	INF E ISCO	19101
	EFF E	19102
	EFF W	19103
1/28/82	Field Blank (1/28/82)	19157
	EFF E II ⁰	19158
	EFF W II ⁰	19159
	INF E I ⁰	19160
	INF I ⁰ E ISCO	19161


Project 1-452-124bGCA Control No. 18132DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 610Sample I.D. SLP 15

Additional Comments _____

Analyst(s) M. GardellChecked By R. RobillardAnalysis Date 3/31/82Report Date 4/13/82

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 57	
Acenaphthene ¹	2,200	
Fluorene	25,000	
Phenanthrene	< 10	
Fluoranthene	20,000	
Anthracene	270	
Triphenylene	86	
Pyrene	< 8	370
Benzo(a)Anthracene	17	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene



2

ID
50 PM
40000 SS
1 BL
30 TP

TIME	AREA
51	17072
141	2045277
281	120907
451	20700
731	3493490
856	397321
956	24005
1051	10800303
1131	3090719
1261	5815527
1601	20499300
1771	3920437
1996	14651221
2340	30044300
2531	427390778
2921	903726
2981	3050373
3211	30053
3341	12715
3421	132256
3631	10595039
3896	2050062 1
	659204417

30 ml PMA cal mix - 4

30 -> 100% CH₃CN, 60 min.

8/31/82

Monsanto

9/22/82
REC'D SEP 27 1982

9-22-82

MONSANTO RESEARCH CORPORATION

Dayton Laboratory
1515 Nicholas Road
P. O. Box 8, Station B
Dayton, Ohio 45407
Phone: (513) 268-3411
TWX 810-459-1681

W23 Samples
taken as of
9/22/82

22 Wednesday 1982


Mr. John C. Craun
Environmental Research and Technology, Inc.
Porter Building - Tenth Floor
601 Grant Street
Pittsburgh, Pennsylvania 15219

Dear John:

The attached table is a listing of the water samples presently on hand at MRC from OW23.

Sincerely,

MONSANTO RESEARCH CORPORATION



Joseph J. Brooks, Ph.D.
Research Group Leader
GC/MS Technology

cc: Paul Rivers/RTC
Ed Schwartzbauer/Dorsey, Windhorst, Hannaford, Whitney * Halladay

498705

St. Louis Park OW23 Water Samples on Hand at MRC (9/20/82)


<u>MRC Log Number</u>	<u>Date</u>	<u>Time</u>	<u>Depth</u>	<u>Quantity</u>	<u>Description</u>
1-82-07-19-06	7/16	9:30	824'	1L	Bailer Sample - water, suspended shale and possible tar within (liquid), green
1-82-07-28-05	7/27	12:00	850'	1L	Bailer Sample - grayish, soupy liquid, watery, some tar odor, gas film on top, some sand
1-82-07-30-01	7/28	15:50	861'	1L	Bailer Sample - soupy, watery-gray liquid, some tar floating on top (film), also some sand and shale
1-82-07-30-01	7/29	9:00	861'	1L	Bailer Sample - soupy, watery-gray material, some sand and pieces of shale within, note tarry film on top
1-82-08-11-02	8/5	9:25	100'	1L	Pump Sample - sample taken at discharge before filter
1-82-08-11-02	8/5	9:28	100'	~0.3L	Pump Sample - sample taken after discharge filter before entering pond.
1-82-08-11-02	8/5	14:30	668.5'	1L	Pump Sample
1-82-08-11-02	8/6	8:23	752.5'	1L	Pump Sample - pH 7.36, 16 min. since pumping began
*1-82-08-11-02	8/7	10:00	804.5'	1L	Pump Sample - sample from 24-hour pumping test at 804.5'
1-82-09-15-03	9/13	12:20	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-15-03	9/13	12:45	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-15-03	9/13	13:15	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-15-03	9/13	14:15	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-15-03	9/13	16:15	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-15-03	9/14	15:00	810'	4L	Pump Sample - 24-hour pumping test
1-82-09-20-02	9/17	16:30	810'	8L	Pump Sample

*Two other samples taken at 804.5' at 08/06/18:00 and 08/07/02:00 were broken during shipment and lost.

408706

9-20-82

9/14/82
N.



545 Indian Mound
Wayzata, Minnesota 55391
(612) 473-4224

September 14, 1982

Mr. Mike Hansel
Regulatory Compliance Section
Solid and Hazardous Waste Division
Minnesota Pollution Control Agency
1935 West County Road B2
Roseville, Minnesota 55113

Re: St. Louis Park Well Abandonment Program

Dear Mr. Hansel:

Enclosed please find one (1) copy of the results of the pumping test performed on September 6th and 7th (24 hour) as well as the results of the clean-out pumping of September 5, 1982. The results are not corrected for recoveries or extraction efficiency.

The samples are coded as follows:

OW 23 F. MS 0	Well W 23 Formation - Mt. Simon Time into pumping test
OW 23 F. MS 0800	Well W 23 Formation - Mt. Simon Time into pumping test (8 hrs)
OW 23 F. MS 1600	Well W 23 Formation - Mt. Simon Time into pumping test (16 hrs)
OW 23 F. MS 24	Well W 23 Formation - Mt. Simon Time into pumping test (24 hrs)
OW 23 F. Pond 0	Well W 23 Stormwater Pond West of W 23 Grab sample - prior to discharge in pond
OW 23 F. EC 0	Well W 23 Formation - Eau Claire (752.5 ft) Time 0 represents 6.5 minutes after pump turned on

9626726

Mr. Mike Hansel
Page Two
September 14, 1982

OW 23
F.100
9:10

Well W 23
Pump setting - 100 feet
Time sample taken - 13 minutes
after pump turned on


OW 23
F.FS
0

Well 23
Pump setting - 668.5 feet
Time sample taken - 13 minutes
after pump turned on

If you have any questions and/or comments please feel free to
contact me at 473-4224.

Sincerely,

EUGENE A. HICKOK AND ASSOCIATES


George W. Boyer, P.E.
Vice President

bt

9626-27

The University of Iowa

Iowa City, Iowa 52242

RECEIVED SEP 13 1982



University Hygienic Laboratory

(319) 353-5990

10 September 1982

E.A. Hickok and Associates
545 Indian Mound
Wayzata, MN 55391

Attn: Mr. George Boyer

Dear George:

Attached are the results from the St. Louis Park samples.

The results are not corrected for recoveries or extraction efficiency. If you have any questions contact us.

Sincerely,

Armand F. Lange, Ph.D.

Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

mh

cc: Dr. Splinter
Dr. Hahne
Mr. Brewer
Ms. Cain
File

9626728

% recoveries

1 µg/L 10 µg/L
spike spike

Q m/e Compound

Q m/e Compound	1 µg/L spike	10 µg/L spike									
117 2,3-dihydroindene	27	54									
115 Indene	36	62									
128 Naphthalene	47	74									
134 Benzo[b]thiophene	48	79									
129 Quinoline	46	110									
142 2-methylnaphthalene	50	92									
117 Indole	53	103									
142 1-methylnaphthalene	50	102									
154 1,1'-biphenyl	59	103									
152 Acenaphthylene	62	108									
154 Acenaphthene	73	121									
166 Fluorene	80	104									
178 Phenanthrene	85	120									
178 Anthracene	83	97									
179 Acridine	74	120									
179 Phenanthridine	75	115									
167 Carbazole	115	117									
202 Fluoranthene	95	68									
202 Pyrene		123									
228 Benz[a]anthracene	89	120									
228 Chrysene	97	122									
252 Benzo[b]fluoranthene	85	108									
252 Benzo[k]fluoranthene	72	106									
252 Benzo[e]pyrene	84	107									
252 Benzo[a]pyrene	82	106									
252 Perylene		105									
276 Indeno[1,2,3 CD]pyrene	91	90									
278 Dibenz[a,h]anthracene	74	103									
276 Benzo[g,h,i]perylene	84	110									

9626729

9626730

9626731

OW 23 Formation MS

Q m/e Compound

 $\mu\text{g/L}$

Lab # 2-2776

74154

0800

8-6-82

117	2,3-dihydroindene	12										
115	Indene	32										
128	Naphthalene	71										
134	Benzo[b]thiophene	9										
129	Quinoline	<5										
142	2-methylnaphthalene	47										
117	Indole	<1*										
142	1-methylnaphthalene	49										
154	1,1'-biphenyl	9										
152	Acenaphthylene	12										
154	Acenaphthene	26										
166	Fluorene	26										
178	Phenanthrene	29										
178	Anthracene	7										
179	Acridine	<1*										
179	Phenanthridine	<1*										
167	Carbazole	7										
202	Fluoranthene	14										
202	Pyrene	12										
228	Benzo[a]anthracene	6										
228	Chrysene	4										
252	Benzo[b]fluoranthene	2										
252	Benzo[k]fluoranthene	1										
252	Benzo[e]pyrene	1										
252	Benzo[a]pyrene	2										
252	Perylene	<1*										
276	Indeno[1,2,3 CD]pyrene	1										
278	Dibenz[a,h]anthracene	<1*										
276	Benzo[g,h,i]perylene	1										

* compound present, but below quantitation limits

9626-33

OW 23 F. MS
1600 8-7-82

Q m/e Compound	μ g/L	Lab # 2-2777	/4155								
117 2,3-dihydroindene	5										
115 Indene	14										
128 Naphthalene	52										
134 Benzo[b]thiophene	5										
129 Quinoline	<5										
142 2-methylnaphthalene	12										
117 Indole	<1*										
142 1-methylnaphthalene	16										
154 1,1'-biphenyl	3										
152 Acenaphthylene	8										
154 Acenaphthene	9										
166 Fluorene	17										
178 Phenanthrene	16										
178 Anthracene	3										
179 Acridine	<1*										
179 Phenanthridine	<1*										
167 Carbazole	4										
202 Fluoranthene	7										
202 Pyrene	5										
228 Benz[a]anthracene	<1*										
228 Chrysene	<1*										
252 Benzo[b]fluoranthene	<1*										
252 Benzo[k]fluoranthene	<1*										
252 Benzo[e]pyrene	<1*										
252 Benzo[a]pyrene	<1*										
252 Perylene	<1*										
276 Indeno[1,2,3 CD]pyrene	<1*										
278 Dibenz[a,h]anthracene	<1*										
276 Benzo[g,h,i]perylene	<1*										

* compound present, but below quantitation limits

9626-34

OW 23 F. MS

Q m/e Compound $\mu\text{g/L}$ Lab # 2-2779 /4156 24 8-7-82

117	2,3-dihydroindene	12										
115	Indene	31										
128	Naphthalene	78										
134	Benzo[b]thiophene	10										
129	Quinoline	<5										
142	2-methylnaphthalene	25										
117	Indole	1										
142	1-methylnaphthalene	27										
154	1,1'-biphenyl	8										
152	Acenaphthylene	12										
154	Acenaphthene	24										
166	Fluorene	20										
178	Phenanthrene	22										
178	Anthracene	4										
179	Acridine	5										
179	Phenanthridine	<1*										
167	Carbazole	7										
202	Fluoranthene	8										
202	Pyrene	7										
228	Benz[a]anthracene	1										
228	Chrysene	<1*										
252	Benzo[b]fluoranthene	<1*										
252	Benzo[k]fluoranthene	<1*										
252	Benzo[e]pyrene	<1*										
252	Benzo[a]pyrene	1										
252	Perylene	<1*										
276	Indeno[1,2,3 CD]pyrene	<1*										
278	Dibenz[a,h]anthracene	<1*										
276	Benzo[g,h,i]perylene	<1*										

* compound present, but below quantitation limits

9626735

OW 23 F. Pond

Q m/e Compound

4 g/L

Lab # 2-2781

/4 158

0

8-5-82

[illegible]

9626-36

OW 23 F. EC
Q m/s Compound μ g/L Lab # 2-2780 /4157 0 8-6-82

117	2,3-dihydroindene	15									
115	Indene	16									
128	Naphthalene	6									
134	Benzo[b]thiophene	7									
129	Quinoline	<5									
142	2-methylnaphthalene	17									
117	Indole	2									
142	1-methylnaphthalene	53									
154	1,1'-biphenyl	16									
152	Acenaphthylene	22									
154	Acenaphthene	41									
166	Fluorene	62									
178	Phenanthrene	114									
178	Anthracene	37									
179	Acridine	5									
179	Phenanthridine	1									
167	Carbazole	3									
202	Fluoranthene	68									
202	Pyrene	52									
228	Benz[a]anthracene	21									
228	Chrysene	19									
252	Benzo[b]fluoranthene	15									
252	Benzo[k]fluoranthene	11									
252	Benzo[e]pyrene	11									
252	Benzo[a]pyrene	16									
252	Perylene	5									
276	Indeno[1,2,3 CD]pyrene	15									
278	Dibenz[a,h]anthracene	5									
276	Benzo[g,h,i]perylene	17									

9626737

OW 23 F. FS

Q m/e Compound

 $\mu\text{g/L}$

Lab # 2-2783

/4160

0

8-5-82

117	2,3-dihydroindene	14										
115	Indene	21										
128	Naphthalene	72										
134	Benzo[b]thiophene	13										
129	Quinoline	<5										
142	2-methylnaphthalene	40										
117	Indole	<1*										
142	1-methylnaphthalene	42										
154	1,1'-biphenyl	19										
152	Acenaphthylene	22										
154	Acenaphthene	31										
66	Fluorene	36										
178	Phenanthrene	85										
178	Anthracene	16										
179	Acridine	5										
179	Phenanthridine	<1*										
167	Carbazole	12										
202	Fluoranthene	40										
202	Pyrene	26										
228	Benz[a]anthracene	16										
228	Chrysene	12										
252	Benzo[b]fluoranthene	11										
252	Benzo[k]fluoranthene	7										
252	Benzo[e]pyrene	7										
252	Benzo[a]pyrene	12										
252	Perylene	3										
276	Indeno[1,2,3 CD]pyrene	3										
278	Dibenz[a,h]anthracene	1										
276	Benzo[g,h,i]perylene	3										

* Compound present, but below quantitation limits

9626779

UNIVERSITY HYGIENIC LABORATORY

<u>Sample</u>	2-Fluoronaphthalene	D ₁₂ Chrysene
	<u>% recovery</u>	<u>% recovery</u>
2-2776	58	149
2-2777	56	103
2-2779	59	115
2-2780	72	73
2-2781	37	45
2-2783	64	101
SOL BLK	57	129
	\bar{X}	
	57.6	102.1
	S. DEV	
	10.6	34.6

9626740

REILLY TAR & CHEMICAL CORPORATION

ST. LOUIS PARK TRIAL PREPARATION DOCUMENT

TO: Mr. C. F. Leshar - Main Office

OFFICE: Laboratory

FROM: William Roder

DATE: September 2, 1982

SUBJECT: SLP - WELL 23

cc: Dr. T. D. Bailey - Lab
Mr. R. Polack - MO
Dr. P. Rivers

The analysis of the tarry scrappings from the bailer and drill bit used in the exploration of W-23 gave the following results:

Sample taken on June 29, 1982
Depth 630-645 ft.

Elemental Analysis

	Tarry Scrapping	CH ₂ Cl ₂ Extract of Tar Scrappings	74°C S.P. pitch from distillation of CH ₂ Cl ₂ Extract
% C	47.76%	88.35%	87.09%
% H	4.45	5.98	5.26
% N	0.36	0.48	0.66
% S	5.30	1.42	1.63
% O	20.94	2.27	2.35
Atomic C/H	0.893	1.230	1.380
Atomic H/C	1.119	0.813	0.725
IR Index	-	0.912	0.720
fa	-	0.897	

Solvent Fractionation of the Tarry Scrappings

Normal heptane Insoluble	51.60%
CH ₂ Cl ₂ Insoluble	48.50
CDCl ₃ Insoluble	38.87
Xylene Insoluble	37.90
Quinoline Insoluble	37.65
Ash	33.50

$$\text{NHI} - \text{XI} = 51.60\% - 37.90\% = 13.7\%$$

$$\text{XI} - \text{QI} = 37.90\% - 37.65\% = 0.25\%$$

Distillation of the Tarry Scrappings

		IR Index	fa
1st drop 98°C			
0-170°C	12.66% H ₂ O 3.03% oil	1.234	0.780
170-210	1.95	1.161	0.832
210-235	2.06	1.005	0.831
235-270	6.39	1.048	0.809
270-282	4.76	1.039	0.791
Lig Residue	3.35	0.569	
Char Residue	60.93		
	95.3%		

off gasing occurred from 98 to 260°C - Decomposition Loss 4.87%.

RECEIVED

NOV 11 1982

ERT

106301

INTER OFFICE CORRESPONDENCE

REILLY TAR & CHEMICAL CORPORATION

ST. LOUIS PARK TRIAL PREPARATION DOCUMENT

Mr. C. F. Leshner

Page 2

September 2, 1982 - SLP - WELL 23

G. C. analysis of the distillate fractions are tabulated in Table I attached.

Distillation of the CH_2Cl_2 Extractables

		IR Index	fa
0-170°	1.56	3.42	0.897
170-210	0.42	3.54	0.782
210-235	1.15	1.55	0.807
235-270	7.19	1.58	0.810
270-315	7.40	1.21	0.830
315-355	16.35	1.14	0.852
Residue	61.46	0.720	0.878
S.P. of Residue (R & B) = 74°C			
Vapor Loss decomposition = 4.47%			

G. C. Analysis of the CH_2Cl_2 extractables, plus the distillate fractions of the CH_2Cl_2 extractables are tabulated in table II.

Very truly yours,

Wm Roder
Wm. Roder

WR/jr
attchmt.

106302

ST. LOUIS PARK TRIAL PREPARATION DOCUMENT
G. C. Analysis of Distillate tion

Table I

12' W98

-3- 4.87 gm 100%
plus 12.66 gm H₂O
60.93 gm ch
100.00 gm

	0-170°C		170-210		210-235		235-270		270-282		Residue Liq.		Total g
wt. of fraction g	3.03 oil		1.95		2.06		6.39		4.76		3.35		21.54
	%	grams	%	grams	%	grams	%	grams	%	grams	%	grams	7.
Indane	-	-	-	-	0.62	0.01	0.70	0.04	-	-	-	-	0.05 0.23
Naphthalene	10.39	0.31	5.70	0.11	4.94	0.10	5.09	0.33	0.63	0.03	-	-	0.88 4.09
Methyl Naphthalene	27.24	0.83	16.08	0.31	13.99	0.29	24.57	1.57	9.15	0.44	-	-	3.44 15.97
dimethyl Naphthalene	3.62	0.11	4.10	0.08	4.52	0.09	6.69	0.43	7.54	0.36	-	-	1.07 4.97
Acenaphthene	5.35	0.16	4.49	0.09	4.95	0.10	7.98	0.51	7.75	0.37	-	-	1.23 5.71
fluorene	4.02	0.12	3.57	0.07	6.01	0.12	5.07	0.33	12.58	0.60	-	-	1.24 5.76
Phenanthrene & Anthracene	10.15	0.31	14.56	0.28	13.68	0.28	12.22	0.78	24.16	1.15	19.72	0.66	3.46 16.06
fluoranthene	3.63	0.11	7.63	0.15	7.47	0.15	3.62	0.23	4.06	0.19	17.87	0.60	1.43 6.64
pyrene	3.57	0.11	7.95	0.16	7.27	0.15	3.74	0.24	3.73	0.18	17.79	0.60	1.44 6.64
Chrysene	1.97	0.06	6.02	0.12	5.25	0.11	1.62	0.10	1.14	0.05	9.38	0.31	0.75 3.48
	69.77	2.12	66.67	1.30	67.96	1.40	11.36	4.56	70.80	3.37	64.18	2.17	14.11 67.60

1.5% BMBT Liquid Crystal

	3.03g oil		1.95		2.06		6.39		4.76		3.35		21.54
wt. of fraction g													
Indane													
Naphthalene													
methyl naphthalene													
dimethyl naphthalene													
acenaphthene	1.77	0.05	1.57	0.03	1.24	0.03	3.90	0.25	2.23	0.11			0.47 2.18
fluorene	2.01	0.06	1.51	0.03	1.13	0.02	2.95	0.19	5.01	0.24	0.06	-	0.54 2.51
phenanthrene	8.13	0.25	8.89	0.17	6.58	0.14	10.66	0.68	21.59	1.03	15.69	0.53	2.80 13.00
anthracene	3.02	0.09	2.98	0.06	2.24	0.05	3.13	0.20	6.36	0.3	7.40	0.23	0.93 4.32
carbazole	-	-	-	-	-	-	-	-	-	-	-	-	-
fluoranthene	3.82	0.12	5.86	0.11	4.16	0.09	4.24	0.27	4.95	0.24	18.45	0.62	1.45 6.73
pyrene	3.57	0.11	5.62	0.11	4.06	0.08	3.80	0.24	3.83	0.18	17.45	0.58	1.30 6.04
Chrysene	1.69	0.05	4.59	0.09	2.15	0.04	1.81	0.12	1.33	0.05	6.01	0.20	0.56 2.60
	24.09	0.73	30.74	0.60	21.84	0.45	30.52	1.95	45.38	2.16	64.47	2.16	8.05 37.37

106303

C. Analysis of the CH₂Cl₂ Extractables

-4-

Table II

12' W-98

CH ₂ Cl ₂ Extract 60-170°C		170-210		210-235		235-270		270-315		315-355		Residue		Total gram
wt. of fraction g.		1.56g		0.42g		1.15		7.19		7.40		16.35		61.46
		%	grams	%	grams	%	grams	%	grams	%	grams	%	grams	
Indane	<.01%	1.7	0.03	1.5	0.01	1.40	0.02	0.14	0.01	.01	-			0.07
Naphthalene	2.45	18.64	0.29	16.86	0.07	19.16	0.22	15.57	1.12	3.28	0.24	0.21	0.03	1.97
Methyl naphthalene	4.48	14.55	0.23	22.43	0.09	19.22	0.22	25.15	1.81	12.47	0.92	1.53	0.25	3.52
Dimethyl naphthalene	3.37	10.85	0.17	6.45	0.03	4.17	0.05	7.91	0.57	10.83	0.80	4.84	0.79	2.41
Acenaphthene	3.23	8.68	0.14	9.01	0.04	3.65	0.04	6.68	0.48	9.68	0.72	4.64	0.75	2.18
fluorene	4.79	3.62	0.06	2.46	0.01	1.96	0.02	3.79	0.27	11.12	0.82	5.44	0.89	2.07
phenanthrene & anthracene	14.68	2.46	0.04	2.50	0.01	3.57	0.04	5.61	0.40	10.90	0.81	26.40	4.30	6.74 4.14
fluoranthene	8.43	0.26	0.01	0.67	0.01	0.85	0.01	0.70	0.05	2.25	0.17	6.13	1.0	13.08 8.03
pyrene	7.86	0.18	0.01	0.70	0.01	0.57	0.01	0.54	0.05	1.98	0.15	5.57	0.91	12.18 7.48
Chrysene	6.21	-								0.38	0.03	1.74	0.28	12.47 7.66

1.5% BMBT Liquid Crystal

Acenaphthene	-							3.81	0.28	3.24	0.53			0.81
Fluorene	1.04					0.77	0.01	1.74	0.13	3.43	0.25	2.88	0.47	0.86
phenanthrene	6.57	NOT ANALYZED DUE TO LACK OF SUFFICIENT SAMPLE				2.44	0.03	5.02	0.36	9.43	0.70	18.90	3.09	1.52 0.93
anthracene	1.42					0.51	0.01	1.22	0.09	1.68	0.12	5.09	0.83	0.45 0.28
carbazole	-													
Fluoranthene	3.93					0.28	-	1.08	0.08	1.85	0.14	5.24	0.86	3.53 2.17
pyrene	3.95					0.05	-	0.69	0.05	1.19	0.09	3.88	0.63	3.61 2.22
Chrysene	1.66					0.04	-	0.02	-	0.04	-	0.67	0.11	2.15 1.32

106304

8-17-82

REC'D AUG 19 1982

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

From LOCATION : B. M. Hughes, Dayton Laboratory
(513) 268-3411 (Ext. 436, 409, 209)

DATE : 17 August 1982

SUBJECT : Analysis Request Forms Received - 215.45718

REFERENCE : U.S.A. v. Reilly Tar & Chemical Corporation

cc: William Gregg/ERT
Jerry R. Rick/SEC
J. J. Brooks/MRC
P. M. Rivers/RTCC

TO : Edward J. Schwartzbauer
Dorsey, Windhorst, Hannaford, Whitney, & Hallada
2200 First Bank Place East
Minneapolis, Minnesota 55402

Field logs/chain-of-custody
of samples submitted to
Reilly/MRC

7/13 - 8/10/82

W23

Enclosed are copies of analytical request forms which have been submitted for the analysis of samples received in conjunction with the project referenced above. MRC has assigned a unique log number for each set of samples and has outlined the requested analyses on the enclosed analytical request forms. If any incorrect information is included on the enclosed forms, please notify me immediately.

B. M. Hughes

B. M. Hughes

Note: Three sludge samples and 2 water samples have been received broken. The three sludge samples were of such a consistency that they were transferred to alternate sample bottles. However, the two water samples were lost due to breakage. Breakage will be minimized if MRC's shipping kits are used, or the bottles are individually wrapped with bubble pack.

408011

ANALYSIS REQUEST | DATE 7/13/82 | LOG NO. 1-82-07-13-03

ONSANTO RESEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**

Reilly TAR: Chem.

CHARGE NO.**

215.45718

REPORT RESULTS TO**
FILES/KULIK

Brooks

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

Reilly TAR

7/12/8:30

OW 23/ST, Louis Park MN
Bailer sample

Depth 780'

ANALYSIS REQUEST TO
FILESBrooks
Gridley

SAMPLES FOR:

Brooks

SAMPLE LOCATION

1-21
FREEZER

Original Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

→ B.M. Hughes

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OTHER

SAMPLE TRANSMITTAL LETTER

Client REILLY TAR + CHEM REP REILLY INC Project Title ST. LOUIS PARK MN (OW-23)
 Date Shipped 7-12-82 Shipped by Soil Exploration Comp. Inc. Ross / Olson
 Shipped From Soil Exp. Comp. 6602 Cromwell Ave ST. PAUL, MN 55114
 Shipped To Monsanto Attention of JOE BECKLES
 Additional Shipping Information or Comments contains Dry Ice.

Sample Description Code

COMMENTS:

REILLY TAR

OW 23 / ST LOUIS PARK MN

(7-12/8:30)

DEPTH → 780'

TARRY RUNNY LIQUID

SOME PIECES OF SHALE

FROM BAILER ~~500~~ @ 780'

Samples Received by Alan H. Ford "seal" intact.

Date Samples Received 7/13/82 10:30 AM

Return Letter Received by Contract Laboratory _____ Date _____

ANALYSIS REQUEST | DATE 7/15/82 | LOG NO. 1-82-07-15-01

INSANTO RESEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**

Reilly TAR

CHARGE NO.**

215.45718

REPORT RESULTS TO**

FILES/KULIK

Gridley
Brooks

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

Run #: 7-13-14:75

Depth 801'

Sample Location: OW 23 ST Louis PARK MN.

Type: Bailer sample

ANALYSIS REQUEST TO:

FILES

Gridley
BrooksSAMPLE WAS RECEIVED WITH JAR CONTAINER
BROKEN.

SAMPLES FOR:

Brooks

Transferred sample and original label to mother bottle.
Original chain of Custody to Gridley

SAMPLE LOCATION

1-21
FREEZER

RECORDED BY:

a Ford

REQUIRED ANALYSIS**

GC/MS Hold Analysis.

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

☐ GAS CHROMATOGRAPHY☐ NMR☐ ULTRAVIOLET☐ HPLC☐ VISIBLE☐ XRD☐ INFRARED☐ ICP☐ EMISSION☐ ATOMIC ABSORPTION☐ EDAX XRF☐ MASS SPEC☐ MICROSCOPY☐ GC/MS☐ OTHER _____☐ AUTO ANALYZER

QUAL. _____ SEMIQUANT. _____ QUANT. _____

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

BM Hughes

REQUIRED QA/QC

118011

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OTH

To B.M. Hughes,

Concerning Memo Requested:

The sample which you have an aliquot
of is labeled: Job: Reilly Depth=574
#: 6-11-1021

Location: DW-23

Type: Core from Well

Date: 6-11-82

This is the sample which you found the bottle broken after unsealing it from its bag. The sample has been transferred to another bottle and the original label was taped onto it. All other Reilly Tar samples have been taken out of their bags on your request and checked for breakage - none other was found broken. Labels on other samples were taken from bag and taped directly on bottles where needed (not already duplicated).

Please be careful with the sample which was found broken and transferred, as there are glass fragments in the sample from breakage.

Al Ford - Lab 21

SAMPLE TRANSMITTAL LETTER

Client MONSANTO (REILLY TART) Project Title REILLY TART + CHEM ST. LOUIS PARK
Date Shipped 7-14-82 Shipped by ROSS L. CHAMBERLAIN (SOIL EXPLORATION CAMP)
Shipped From SOIL EXPLORATION CO. 662 COLUMBIA AVE ST. PAUL MN
Shipped To MONSANTO RESEARCH CORP. 1515 N. MILWAUKEE RD. Attention of JOE BROOKS
Additional Shipping Information or Comments DRY ICE
→ FROZEN SAMPLE (7-13-82)
NOTE DRY ICE

Sample Description Code

COMMENTS:

7/13/14: ~~TS~~

DEPTH \rightarrow 80'

BLACK TARRY WATERY LIQUID

SOME PIECES OF SHALE

BAILER SAMPLE

Samples Received by Alan H. Ford "seal" intact - sample broken.

Date Samples Received 7/15/82

Return Letter Received by Contract Laboratory _____ Date _____

ANALYSIS REQUEST | DATE 7/28/82 | LOG NO. 1-82-07-28-05

ONSANTO RESEARCH CORPORATION | REQUESTER** Reilly TAR/ SOIL EXPLORATION | CHARGE NO.** 215,45718

PLE DESCRIPTION | NUMBER OF BOTTLES: 1 | NUMBER OF SAMPLES ** 1

REPORT RESULTS TO**
FILES / KULIK

Gridley
Brooks

7/27/12:00
OW 23 St. Louis Park, MN

ANALYSIS REQUEST TO
FILES

Gridley
Brooks

SAMPLES FOR:
Brooks

SAMPLE LOCATION
1-21
FREEZER

Original Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS**

GC/MS - Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST	HOURS	INST. TIME
B. M. Hughes		

REQUIRED QA/QC

**SAMPLE DISPOSAL: AFTER REPORT COMPLETE ☐ DISCARD ☐ RETURN HOLD FOR ☐ 30 DAYS ☐ 60 DAYS Hold OTI

SAMPLE TRANSMITTAL LETTER

Client MONSANTO (REILLY TAR) Project Title REILLY TAR (ST LOUIS PARK, MN)
 Date Shipped 7-27-82 Shipped by ROSS Ohman SOIL EXPLORATION CO.
 Shipped From Soil Exploration Company, 662 Cornwell Ave. ST PAUL MN 55114
 Shipped To MONSANTO RESEARCH CORP. Attention of JOE BROOKS
 Additional Shipping Information or Comments (H₂O ICE FREEZE)

Sample Description Code

COMMENTS:

7-27-12:00

GRAVIST - WATERY SOUPY LIQUID

OL23 ST LOUIS PARK MN

SOME TAR ODOR, SOME GAS FILM

DEPTH → 850'

ON TOP, SOME SAND AND A PIECE

(BAILER SAMPLE)

OF SHALE.

Samples Received by

Alan H Ford

Date Samples Received

7/28/82 seal intact.

Return Letter Received by Contract Laboratory

Date

ANALYSIS REQUEST | DATE 7-30-82 | LOG NO. 1-82-07-30-01

ONSANTO RESEARCH CORPORATION | REQUESTER** REILLY TAYLOR | CHARGE NO.** 215,45718

REPORT RESULTS TO:
FILES / KULIK
GRIDLEY
BROOKS

SAMPLE DESCRIPTION | NUMBER OF BOTTLES: 2 | NUMBER OF SAMPLES ** 2

- ① 7/28/3:50PM OW 23 St Louis Park, Minn
Bailer Sample Depth 861' Primarily Water Samples
- ② 7/29/9:00 OW 23 St Louis Park, Minn
Bailer Sample Depth 861'B

ANALYSIS REQUEST TO
FILES
GRIDLEY
BROOKS

Samples rec'd coal, not frozen, contain water.

SAMPLES FOR:
BROOKS

ORIG. CHAIN OF CUSTODY LETTER TO GRIDLEY

SAMPLE LOCATION
1-21
R-8

RECORDED BY: AP

REQUIRED ANALYSIS**

GC/MS - Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

Sa

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input checked="" type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST	HOURS	INST. TIME
<u>B.M. Hughes</u>		

REQUIRED QA/QC

41811750

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE

☐ DISCARD ☐ RETURN

HOLD FOR ☐ 30 DAYS ☐ 60 DAYS Hold OTH

SAMPLE TRANSMITTAL LETTER

Client MOWSANTO, REILLY TAR Project Title REILLY TAR
 Date Shipped 7-29-82 Shipped by ROSS O'HAN. S.S.C.
 Shipped From SOIL EXPLORATION CO. 602 CROMWELL AVE ST PAUL ST 14
 Shipped To MOWSANTO, 1515 NICHOLAS RD. Attention of JOE BROOKS
 Additional Shipping Information or Comments (H2O ICE FREEZER)

Sample Description Code

COMMENTS:

~~COMMENTS~~

7/28/82 3:50 pm

OW 23 ST LOUIS PARK, MN

BAILER SAMPLE

DEPTH → 8' 01"

WATERY - SOUPY, GRAY LIQUID
SOME TAR FILM ON TOP.

7/29/82 3:00

OW 23 ST LOUIS PARK, MN

BAILER SAMPLE.

DEPTH - "8' 01" B"

WATERY SOUPY GRAY LIQUID
SOME TAR FILM ON TOP
OF SAMPLE.

Samples Rec'd Cool (not frozen).

Samples Received by

Date Samples Received

7-30-82 1:30 PM

Return Letter Received by Contract Laboratory

Date

ANALYSIS REQUEST DATE 8/11/82 LOG NO. 1-82-08-11-02

ONSANTO RESEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**

Reilly TAR / Gridley

CHARGE NO.**

215,45718

REPORT RESULTS TO**

FILES / KULIK

Gridley

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 7

NUMBER OF SAMPLES ** 7

08/05/09:25 - 100'

08/05/09:28 - 100'

08/05/14:30 - 468 1/2'

08/06/08:23 - 752 1/2'

08/06/18:00

08/07/02:00

08/07/10:00

These two received broken - samples
apparently liquid which mixed with
packing mat'l, wet ice etc.
804 1/2'Primarily water
SamplesANALYSIS REQUEST TO
FILESBrooks
Gridley
(SAMPLES)

SAMPLES FOR:

Brooks

SAMPLE LOCATION

1-216 8

Original Chain of Custody to Gridley

RECORDED BY:

a Ford

REQUIRED ANALYSIS**

Hold GC/MS

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

☐ GAS CHROMATOGRAPHY☐ NMR☐ ULTRAVIOLET☐ HPLC☐ VISIBLE☐ XRD☐ INFRARED☐ ICP☐ EMISSION☐ ATOMIC ABSORPTION☐ EDAX XRF☐ MASS SPEC☐ MICROSCOPY☐ GC/MS☐ OTHER _____☐ AUTO ANALYZER

QUAL. _____ SEMIQUANT. _____ QUANT. _____

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

BMH

REQUIRED QA/QC

408121

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OTI

SAMPLE TRANSMITTAL LETTER

Client REILLY TAR + CHEM Project Title REILLY TAR + CHEM ST LOUIS PARK, MN (CW #23)
 Date Shipped 8/10/82 Shipped by ROSS O'HANIAN, SOIL EXP. CO.
 Shipped From Soil Exploration company, 602 Cromwell Ave ST PAUL MN
 Shipped To MONSANTO RESEARCH CORPORATION Attention of DE BROOKS
 Additional Shipping Information or Comments PACKED WITH H2O ICE.

Sample Description Code

COMMENTS:

0805/09:25	
0805/09:25	Sample taken AT DISCHARGE BEFORE FILTER. (PUMP @ 100')
0805/09:28	SAMPLE TAKEN AFTER DISCHARGE FILTER BEFORE ENTERING PUMP (PUMP @ 100')
08 05 14:30	SAMPLE TAKEN AT PUMP @ 668 1/2'
08 06 08:23	SAMPLE TAKEN AT PUMP @ 752 1/2' 4" @ 60.18' @ 7:36, 16 MIN SINCE AMP BEG
18/06/1800	SAMPLE TAKEN AT PUMP @ 804 1/2'
0807 02:00	SAMPLE TAKEN AT PUMP @ 804 1/2'
08 07 10:00	SAMPLE TAKEN AT PUMP @ 804 1/2'

Samples Received by Alan H Ford (seal intact)

Date Samples Received 8/11/82 11:00

Return Letter Received by Contract Laboratory _____ Date _____

8/12/82

N.

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC
HYDROCARBONS IN MUNICIPAL WATER
WELLS FOR THE
CITY OF ST. LOUIS PARK

Prepared by:

CAPSULE LABORATORIES
605 West County Rd E.
Shoreview, Minnesota 55112

Date Submitted:

August 12, 1982

May Sampling



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Report Typed: August 12, 1982
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)¹

<u>Test</u>	Well 7	Well 11	Well 12	Well 3	Well 4
	Capsule # <u>13734.6</u>	Capsule # <u>13734.7</u>	Capsule # <u>13734.8</u>	Capsule # <u>13734.9</u>	Capsule # <u>13734.10</u>
Acenaphthene	ND	ND	ND	ND	20
Acenaphthylene	ND	ND	ND	ND	ND
Anthracene	9.5	ND	11	ND	ND
Benzo(a)anthracene	ND	ND	ND	ND	ND
Benzo(b)fluoranthene	ND	ND	ND	ND	ND
Benzo(k)fluoranthene	ND	ND	ND	ND	ND
Benzo(a)pyrene	ND	ND	ND	ND	ND
Benzo(g,h,i)perylene	ND	ND	ND	ND	ND
Chrysene	ND	ND	ND	ND	ND
Dibenzo(a,h)anthracene	ND	ND	ND	ND	ND
Fluoranthene	ND	ND	ND	ND	ND
Fluorene	ND	ND	ND	ND	ND
Benzo(1,2,3-cd)pyrene	ND	ND	ND	ND	ND
Benzo(e)fluoranthene	ND	33	18	9.3	ND
Phenanthrene	ND	ND	ND	ND	68
Pyrene	ND	ND	ND	ND	ND

¹ Concentration expressed in parts-per-trillion (ng/l)

ND = Signal not observed or does not meet criteria for quantitation.



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Report Typed: August 12, 1982
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)

<u>Test</u>	Well 6	Well 8	Well 13	Well 14	Well 16
	Capsule # <u>13734-1</u>	Capsule # <u>13734-2</u>	Capsule # <u>13734.3</u>	Capsule # <u>13734.4</u>	Capsule # <u>13734.5</u>
Acenaphthene	ND	ND	ND	ND	ND
Acenaphthylene	ND	ND	ND	ND	ND
Anthracene	ND	ND	80	54	ND
Benzo(a)anthracene	ND	ND	ND	ND	ND
Benzo(b)fluoranthene	ND	ND	ND	ND	ND
Benzo(k)fluoranthene	ND	ND	ND	ND	ND
Benzo(a)pyrene	ND	ND	ND	ND	ND
Benzo(g,h,i)perylene	ND	ND	ND	ND	ND
Chrysene	ND	ND	ND	ND	ND
Dibenzo(a,h)anthracene	ND	ND	ND	ND	ND
Fluoranthene	ND	ND	ND	ND	ND
Fluorene	ND	ND	ND	ND	ND
Benzo(1,2,3-cd)pyrene	ND	ND	ND	ND	ND
Benzo(e)fluoranthene	ND	ND	ND	ND	ND
Phenanthrene	ND	ND	ND	ND	ND
Pyrene	ND	ND	ND	ND	ND

¹ Concentration expressed in parts-per-trillion (ng/l)

ND = Signal not observed or does not meet criteria for quantitation.



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Report Typed: August 12, 1982
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)

% Recoveries of Deuterated Spikes

<u>Test</u>	Well 7	Well 11	Well 12	Well 3	Well 4
	Capsule # <u>13734.6</u>	Capsule # <u>13734.7</u>	Capsule # <u>13734.8</u>	Capsule # <u>13734.9</u>	Capsule # <u>13734.10</u>
Acenaphthene					
Acenaphthylene					
Anthracene					
Benzo(a)anthracene					
Benzo(b)fluoranthene					
Benzo(k)fluoranthene					
Benzo(a)pyrene					
Benzo(g,h,i)perylene					
D ₁₂ Chrysene	200	18	16	35	30
Dibenzo(a,h)anthracene					
Fluoranthene					
Fluorene					
eno(1,2,3-cd)pyrene					
aphthalene	2.0	3.0	0.74	0.74	0.07
D ₁₀ Phenanthrene	6.2	53	42	47	50
D ₁₀ Pyrene	18	37	83	48	48
Spike Level	Medium	Low	Medium	Low	High



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Report Typed: August 12, 1982
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)

% Recoveries of Deuterated Spikes

	Well 6	Well 8	Well 13	Well 14	Well 16
	Capsule #	Capsule #	Capsule #	Capsule #	Capsule #
	<u>13734.1</u>	<u>13734.2</u>	<u>13734.3</u>	<u>13734.4</u>	<u>13734.5</u>
<u>Test</u>					
Acenaphthene					
Acenaphthylene					
Anthracene					
Benzo(a)anthracene					
Benzo(b)fluoranthene					
Benzo(k)fluoranthene					
Benzo(a)pyrene					
Benzo(g,h,i)perylene					
D ₁₂ Chrysene	72	110	47	21	58
Dibenzo(a,h)anthracene					
Fluoranthene					
Fluorene					
deho(1,2,3-cd)pyrene					
D ₈ Naphthalene	0.07	0.33	2.6	0.74	3.0
D ₁₀ Phenanthrene	37	120	87	40	65
D ₁₀ Pyrene	5.9	52	52	42	55
Spike Level	High	High	Low	Medium	Low

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC HYDROCARBONS

Sampling Equipment

Sampling resin beds used for organic enrichment are connected to a water source by an all-teflon manifold. The teflon manifold is designed to collect samples in duplicate by splitting sample flow with a tee to two resin beds. The inlet of the manifold is compatible with a 1/8" NPT female fitting on the water source. Two teflon needle valves (one on each side of the tee) are used to control water flow through the resin beds. A differential pressure of at least 20 psig is necessary for adequate flow control. When particulate levels are high, a teflon prefilter is placed upstream of the resin beds to remove particulates.

Sampling Procedure

Before sampling, all manifold parts are cleaned with HPLC-grade acetone and hexane. Preparation of the resin beds consists of flushing each with 4.0 ml HPLC-grade methanol, then 10.0 ml HPLC-grade water. One of the beds is spiked with isotope compounds in the laboratory. The spike level should be similar in concentration to the non-isotopic compounds being analyzed.

At the sampling site, the assembled teflon manifold and resin bed connections are leak-tested. The flow rate through each resin bed is adjusted using the flow valve and the sample flow volume maintained throughout sampling by periodic checks. The water after passing through each resin bed is collected in tared carboys. At the end of the sampling period, the water volume sampled is determined by weighing the carboy and water. At the completion of the sampling, the resin beds are wrapped in foil and kept refrigerated until analysis.

Resin Bed Elution

Each resin bed used to collect and concentrate polynuclear aromatic compounds is eluted using acidified tetrahydrofuran (THF). The acidified THF is then passed through a micro-drying column to remove water. The dried THF extract is collected in a 0.1 ml graduated vial. The micro-drying column is rinsed several times with acidified THF. The extract is then solvent exchanged and filtered. The volume of the extract is reduced under a gentle stream of nitrogen at room temperature. Finally, the concentrated extract is spiked with an isotope internal standard (D_{10} anthracene).

GC/MS Analysis

The extracts are stored in suitable vials until ready for analysis. A 1 μ l aliquot is injected on the column in a splitless injection mode. Single ion monitoring data is continuously acquired and the data stored for later workup. Instrumental parameters are described in Table I.

Data Reduction - Quantitation

The single ion chromatograms are plotted for the characteristic ion of each polynuclear aromatic being analyzed. Areas are then obtained for any peak with a retention time falling within a one minute window relative to the

standard run. Confirmation of identity is based on presence of the EPA selected ions (see Table II) for the individual compound, and all ions must maximize within one scan of each other. Furthermore, the ions must meet spectral integrity criteria for relative ratios ($\pm 20\%$). The areas under each characteristic ion are used to determine the extract concentration. The areas are compared to the internal standard intensity based on the following formula.

$$\text{Concentration}_{\text{unk}} = \frac{(\text{Area}_{\text{unk}}) (\text{Conc}_{\text{IS}})}{(\text{Area}_{\text{IS}}) (\text{R.F.}_{\text{unk}}) (\text{Dilution})}$$

where: unk = priority pollutant being quantitated

IS = internal standard D₁₀ anthracene

R.F. = response factor for the particular compound

Recovery Determinations

Each sample to be extracted is spiked with a surrogate standard (a deuterated analog). These materials are carried through the work-up procedure and quantitated along with the normal pollutants. The intensity of these spikes when compared to the area for D₁₀ anthracene added to the final extract allows a percent recovery to be determined for each extraction.

$$\text{Percent Recovery} = \frac{\text{Concentration of Spike Observed}}{\text{Concentration of Spike Added to Sample}} \times 100$$

Matrix Spikes

In addition, a matrix spike is analyzed with each set of samples. The material being extracted is spiked with a mixture of polyaromatic hydrocarbons appropriate for the fractions being analyzed. The recoveries of compounds in the spiking mix will provide information about the matrix effect of the sample on the analytical methodology. Individual component recoveries of the matrix spike are calculated as follows:

$$\text{Percent Recovery} = \frac{\text{SSR} - \text{SR}}{\text{SA}} \times 100$$

Where: SSR = Spike sample results ($\mu\text{g/g}$)

SR = Sample results ($\mu\text{g/g}$)

SA = Spike added ($\mu\text{g/g}$) from spiking mix

Duplicate Samples

Duplicate analyses are performed every 20 samples or one for each project, whichever is more frequent.

$$\text{Percent Difference} = \frac{D_1 - D_2}{(D_1 + D_2)} \times 100$$

Where: D_1 = First sample value
 D_2 = Second sample value (duplicate)

Detection Limits¹

The method detection limit is defined as the minimum concentration of a substance that can be identified, measured and reported with 99% confidence that the analyte concentration is greater than zero and is determined from replicate analysis of a sample of a given matrix containing analyte².

$$\text{MDL} = t (N-1, 1-\alpha = .99) \times S_c$$

Where: $t (N-1, 1-\alpha = .99)$ is student's t value for one-tailed test at the 99% confidence level with $N-1$ degree of freedom.
 S_c is the standard deviation of replicate analyses.

The method detection limit refers to samples processed through all steps comprising an established analytical procedure.

¹Glaser, J.A., et al, "Trace Analyses for Wastewater," Environ. Sci. Tech., 15, 1426(1981).

²"Definition and Procedure for the Determination of the Method Detection Limit," Rev.1.12 45 EPA, Environmental Monitoring and Support Lab., Cincinnati, Jan. 1981.

The detection limit for each PNA is four parts-per-trillion in the well water.

TABLE I

INSTRUMENT PARAMETERS

Polynuclear Aromatics Analysis

Gas Chromatograph

Hewlett Packard 5840 with HP7671A Autosampler
Column 30m x 0.24mm DB-5 Fused Silicon Capillary (J & W)
Column directly coupled to MS

Injection

Mode: Splitless
Sweep Initiation @ 0.5 minutes
Sweep Flow: 40ml/min. Helium
Carrier Flow: 1cm/sec. linear velocity

Temperatures

Injector: 300°C
Temp. 1: 40°C for 3 minutes
Ramp: 10°C/minute
Temp. 2: 280°C for 20 minutes
Interface Temp: 300°C
Injection Volume: 2 µl

Mass Spectrometer

Hewlett Packard 5985B GCMS
Electron Impact Mode: 70eV
Delay: 11.5 minutes
SIM MODE
Dwell time: 100ms per ion
Multiplier Voltage: 2000V
Source Temp. 225°C

Computer

Hewlett Packard 21MX-E
Disk Drives: HP7906 (20M byte) HP7920 (50M byte)
Tape Drive: Kennedy 9300 9-track dual density

TABLE II

Ion (abundances)

<u>Compound</u>	<u>Primary</u>	<u>Confirming</u>		<u>R.T.</u>
Naphthalene	128(100)	127(12)	129(10)	12.8
Acenaphthylene	152(100)	151(21)	153(13)	16.7
Acenaphthene	154(100)	153(118)	152(59)	17.2
Fluorene	166(100)	165(98)	167(14)	18.5
Phenanthrene	178(100)	176(20)	179(16)	20.8
Anthracene	178(100)	176(22)	179(19)	21.0
Fluoranthene	202(100)	101(19)	100(14)	23.8
Pyrene	202(100)	101(21)	100(18)	24.3
Benzo(a)anthracene	228(100)	226(25)	229(20)	27.3
Chrysene	228(100)	229(19)	226(28)	27.5
Benzo(b)fluoranthene	252(100)	253(23)	125(15)	30.6
Benzo(k)fluoranthene	252(100)	253(22)	125(16)	30.9
Benzo(a)pyrene	252(100)	253(24)	125(16)	32.0
Indeno(1,2,3-c,d)pyrene	276(100)	138(31)	277(24)	37.8
Dibenzo(a,h)anthracene	278(100)	139(25)	279(24)	38.2
Benzo(g,h,i)perylene	276(100)	138(34)	277(22)	39.7

8/6/82
N.



GCA CORPORATION
Technology Division

213 Burlington Road
Bedford, Massachusetts 01730
Telephone: 617-275-5444
Telex: 92-3339

6 August 1982

Environmental Protection Agency
401 M Street, S.W.
Washington, DC 20460

Attention: Julie Klaas

Subject: Contract No. 68-01-6316, Technical Service Area 1,
Assignment 24, Task A - E, (GCA 1-452-124)

Gentlemen:

In accordance with Paragraph VI, Reporting Requirements of the subject Assignment, enclosed herewith is one (1) copy of Monthly Progress Report Nos. 7,8,9,10,11 and 12 covering the period 1 February through 31 July 1982.

Very truly yours,

Arthur Engelman
Manager, Contract Administration

AE:eia

Enclosure (1)

cc: Mr. John R. Busik
(w/1 copy)

✓ Mr. Mike Kosakowski
(w/1 copy)

ANALYSIS OF ENVIRONMENTAL SAMPLES FOR REGION V

Monthly Progress Report Nos. 7,8,9,10,11,12, for the Period

1 February through 31 July 1982

Prepared for

U.S. ENVIRONMENTAL PROTECTION AGENCY
DIVISION OF STATIONARY SOURCE ENFORCEMENT
Washington, D.C. 20460

Contract No. 68-01-6316
Technical Service Area 1
Assignment No. 24

August 1982


Kenneth T. McGregor

GCA CORPORATION
GCA/TECHNOLOGY DIVISION
Bedford, Massachusetts

SECTION 1

PURPOSE OF TASK

The purpose of this work assignment is to provide support services to EPA Region V for the analysis of environmental samples. These services will consist of analyses of water, soil, sludge, and oil-phase water samples for several organic and inorganic components. Specifically, the samples will be analyzed for some or all of the following parameters:

- Priority pollutants
 - Volatile organics
 - Extractable organics
 - Pesticides/PCBs
 - Trace metals
 - Cyanide and phenols
- Nonpriority pollutants
 - PAH compounds
 - Methyl ethyl ketone
 - Hexavalent chromium
 - Nonfilterable residue
 - Total organic carbon
 - Cation exchange capacity
 - Conventional pollutants

The five tasks included in this work assignment will be conducted in accordance with the analytical procedures and quality assurance/quality control protocols outlined in the Work Plans submitted for these tasks.

SECTION 2

PROGRESS DURING REPORTING PERIOD

TASK A

Photographs were taken of five samples from the Fisher-Calo program.

TASK B

Analysis has been completed and data transmitted on four municipal well water samples.

TASK C

The following sample preparation, analysis, and transmittal procedures were initiated and/or completed during this reporting period.

- PAH analysis by HPLC-fluorescence of eleven water samples from the Mississippi River.
- PAH analysis by HPLC-fluorescence of fifteen water samples from the MWCC.
- PAH analysis by HPLC-fluorescence of four empty sample containers (field blanks).
- Sample preparation was carried out on four sludge samples from MWCC for PAH analysis by GC/MS.

Preliminary data are available, and included with this report, for nonfilterable residue from eleven water samples from the Mississippi River.

TASKS D AND E

To date, no work has been performed under these tasks.

SECTION 3

CURRENT PROBLEMS

TASK C

A delay occurred during the analysis of the water samples from the Mississippi River and MWCC. The delay was due to a malfunctioning integrator on the HPLC-fluorescence system.

SECTION 4

WORK TO BE PERFORMED DURING NEXT REPORTING PERIOD

TASK C

Results of analysis for PAHs on the four sludge samples from the MWCC will be submitted.

TASKS D AND E

No activity is planned during August.

NONFILTERABLE RESIDUE

Project: 1-452-124C

Sample Matrix: Water

Analytical Method: Methods for Chemical Analysis of Water and Wastes
EPA-600/4-79-020

<u>Sample I.D.</u>	<u>GCA Control No.</u>	<u>Residue (mg/l)</u>
UM-827	18830	< 10
UM-840	18831	< 10
UM-847	18832	< 10
UM-859	18833	< 10
FORD DAM	18834	< 10
FORD DAM	18942	< 10
GRAY CLOUD	18943	< 10
UM-827	18944	< 10
UM-840	18945	< 10
UM-847	18946	< 10
UM-859	18947	< 10

An aliquot of EPA WP/080, concentrate 1, gave a recovery of 87 percent.

CONTRACT NO. 68-01-6316

TSA I, TASK 24


(GCA 1-452-124) REVISED 12/16/81


X——X ESTIMATED EXPENDITURES

X-----X ACTUAL EXPENDITURES

○——○ ESTIMATED MAN-HOURS

○-----○ ACTUAL MAN-HOURS





CAPSULE LABORATORIES

ADVANCED TECHNOLOGY DIVISION

A Division of Economics Laboratory, Inc.
605 West County Road E. St. Paul, MN 55112, (612) 482-8855

August 2, 1982

Mr. Vern Tollefsrud
City of St. Louis Park
5005 Minnetonka Blvd.
St. Louis Park, MN 55416

Dear Mr. Tollefsrud:

Enclosed are the results of the analysis for polynuclear aromatic hydrocarbons in St. Louis Park Well #5 well water. Two separate 8 liter samples of well water collected July 13, 1982, and July 14, 1982, were analyzed. The analyses were conducted by single ion monitoring (SIM) GC/MS on extracts of the samples prepared using the EPA Method #610 liquid-liquid technique. The samples were spiked with deuterated analogs for percent recovery determinations.

If you have any questions regarding these results, please feel free to contact us.

Sincerely,


CAPSULE LABORATORIES

Wayne A. Olson

Wayne A. Olson
Principal Chemist *PAZ*

WAO:jjd

8/2/82
N.



TECHNICAL DATA

Report of Analyses to: City of Saint Louis Park

PRIORITY POLLUTANT ANALYSIS (PNA'S) ⁽¹⁾

	<u>Sampled 7/13/82 Capsule # 13931.01 Well # 5</u>	<u>Sampled 7/14/82 Capsule # 13931.02 Well # 5</u>
Acenaphthene	12	42
Acenaphthylene	ND	19
Anthracene	ND	ND
Benzo (a) anthracene	ND	ND
Benzo (b) fluoranthene	ND	ND
Benzo (k) fluoranthene	ND	ND
Benzo (a) pyrene	ND	ND
Benzo (g,h,i) perylene	ND	ND
Chrysene	ND	ND
Dibenzo (a,h) anthracene	ND	ND
Fluoranthene	ND	ND
Fluorene	20	46
Indeno (1,2,3-c,d) pyrene	ND	ND
Naphthalene	ND	ND
Phenanthrene	ND	ND
Pyrene	ND	ND

(1) Concentration expressed as parts-per-trillion (ng/l)

N.D. = Signal not observed or does not meet criteria for quantitation



TECHNICAL DATA

Report of Analyses to: City of Saint Louis Park

PRIORITY POLLUTANT ANALYSIS (PNA'S)

	<u>µg Spiked</u>	<u>Deuterated Spike % Recovery 13931.01 Well # 5</u>	<u>Deuterated Spike % Recovery 13931.02 Well # 5</u>
D ₁₂ Benzo (a) pyrene	24	130%	63%
D ₁₂ Chrysene	22	43%	34%
D ₈ Naphthalene	22	29%	17%
D ₁₀ Phenanthrene	26	46%	34%
D ₁₀ Pyrene	22	45%	34%

TABLE II
Ion (abundances)

<u>Compound</u>	<u>Primary</u>	<u>Confirming</u>		<u>R.T.</u>
Naphthalene	128(100)	127(13)	129(11)	12.8
Acenaphthylene	152(100)	151(21)	153(13)	16.7
Acenaphthene	154(100)	153(110)	152(54)	17.2
Fluorene	166(100)	165(96)	167(13)	18.5
Phenanthrene	178(100)	176(20)	179(16)	20.8
Anthracene	178(100)	176(21)	179(18)	21.0
Fluoranthene	202(100)	101(20)	100(14)	23.8
Pyrene	202(100)	101(23)	100(18)	24.3
Benzo(a)anthracene	228(100)	226(24)	229(19)	27.3
Chrysene	228(100)	229(19)	226(27)	27.5
Benzo(b)fluoranthene	252(100)	253(23)	125(15)	30.6
Benzo(k)fluoranthene	252(100)	253(22)	125(16)	30.9
Benzo(a)pyrene	252(100)	253(24)	125(16)	32.0
Indeno(1,2,3-c,d)pyrene	276(100)	138(31)	277(24)	37.8
Dibenzo(a,h)anthracene	278(100)	139(25)	279(24)	38.2
Benzo(g,h,i)perylene	276(100)	138(34)	277(22)	39.7

$$\text{Percent Difference} = \frac{D_1 - D_2}{(D_1 + D_2)} \times 100$$

Where: D_1 = First sample value
 D_2 = Second sample value (duplicate)

Detection Limits¹

The method detection limit is defined as the minimum concentration of a substance that can be identified, measured and reported with 99% confidence that the analyte concentration is greater than zero and is determined from replicate analysis of a sample of a given matrix containing analyte².

$$\text{MDL} = t (N-1, 1-\alpha = .99) \times S_c$$

Where: $t (N-1, 1-\alpha = .99)$ is students t value for one-tailed test at the 99% confidence level with $N-1$ degree of freedom.
 S_c is the standard deviation of replicate analyses.

The method detection limit refers to samples processed through all steps comprising an established analytical procedure.

¹Glaser, J.A., et al, "Trace Analyses for Wastewater," Environ. Sci. Tech., 15, 1426(1981).

²"Definition and Procedure for the Determination of the Method Detection Limit," Rev.1.12 45 EPA, Environmental Monitoring and Support Lab., Cincinnati, Jan. 1981.

The detection limit for each PNA is four parts-per-trillion in the well water.

TABLE I

INSTRUMENT PARAMETERS

Polynuclear Aromatics Analysis

Gas Chromatograph

Hewlett Packard 5840 with HP7671A Autosampler
Column 30m x 0.24mm DB-5 Fused Silicon Capillary (J & W)
Column directly coupled to MS

Injection

Mode: Splitless
Sweep Initiation @ 0.5 minutes
Sweep Flow: 40ml/min. Helium
Carrier Flow: 1cm/sec. linear velocity

Temperatures

Injector: 300°C
Temp. 1: 40°C for 3 minutes
Ramp: 10°C/minute
Temp. 2: 280°C for 20 minutes
Interface Temp: 300°C
Injection Volume: 2 µl

Mass Spectrometer

Hewlett Packard 5985B GCMS
Electron Impact Mode: 70eV
Delay: 11.5 minutes
SIM MODE
Dwell time: 100ms per ion
Multiplier Voltage: 2000V
Source Temp. 225°C

Computer

Hewlett Packard 21MX-E
Disk Drives: HP7906 (20M byte) HP7920 (50M byte)
Tape Drive: Kennedy 9300 9-track dual density

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC
HYDROCARBONS IN MUNICIPAL WATER
WELLS FOR THE
CITY OF ST. LOUIS PARK

Prepared by:

CAPSULE LABORATORIES
605 West County Rd E.
Shoreview, Minnesota 55112

Date Submitted:

August 6, 1982



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)¹

Well 3	Well 6	Well 8	Well 14	Well 16
Capsule #	Capsule #	Capsule #	Capsule #	Capsule #
<u>13889.01</u>	<u>13889.02</u>	<u>13889.03</u>	<u>13889.04</u>	<u>13889.05</u>

Test

naphthene	ND	ND	ND	ND	ND
naphthylene	ND	ND	ND	ND	ND
Anthracene	ND	ND	ND	60	ND
Benzo (a)anthracene	ND	ND	ND	ND	ND
Benzo (b)fluoranthene	ND	ND	ND	ND	ND
Benzo (k)fluoranthene	ND	ND	ND	ND	ND
Benzo (a)pyrene	ND	ND	ND	ND	ND
Benzo (g,h,i)perylene	ND	ND	ND	ND	ND
Chrysene	ND	ND	ND	ND	ND
Dibenzo (a,h)anthracene	ND	ND	ND	ND	ND
Fluoranthene	ND	ND	ND	ND	ND
Fluorene	ND	ND	ND	ND	ND
Indeno (1,2,3-cd)pyrene	ND	ND	ND	ND	ND
Naphthalene	ND	5.3	ND	ND	4.8
Phenanthrene	ND	ND	ND	5.2	ND
Pyrene	ND	ND	ND	4.0	ND

Concentration expressed in parts-per-trillion (ng/l).

N.D. = Signal not observed or does not meet criteria for quantitation.



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park

Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA's)

% Recoveries of Deuterated Spikes

Well 3	Well 6	Well 8	Well 14	Well 16
Capsule #	Capsule #	Capsule #	Capsule #	Capsule #
<u>13889.01</u>	<u>13889.02</u>	<u>13889.03</u>	<u>13889.04</u>	<u>13889.05</u>

Test

Acenaphthene					
Acenaphthylene					
Anthracene					
Benzo(a)anthracene					
Benzo(b)fluoranthene					
Benzo(k)fluoranthene					
Benzo(a)pyrene					
Benzo(g,h,i)perylene					
D ₁₂ Chrysene	85	77	68	68	47
Dibenzo(a,h)anthracene					
Fluoranthene					
Fluorene					
Indeno(1,2,3-cd)pyrene					
D ₈ Naphthalene	0.6	0.3	0.2	0.1	0.8
D ₁₀ Phenanthrene	110	50	50	71	68
D ₁₀ Pyrene	63	81	48	76	57
Spike Level	Low	High	High	Medium	Low



TECHNICAL DATA

Report of Analyses to: City of St. Louis Park
Date Samples Submitted: June 4, 1982

PRIORITY POLLUTANT ANALYSIS (PNA'S)

Level of Deuterated Spikes

<u>Test</u>	<u>Low Spike (ng)</u>	<u>Medium Spike (ng)</u>	<u>High Spike (ng)</u>
Benaphthene			
Acenaphthylene			
Anthracene			
Benzo (a) anthracene			
Benzo (b) fluoranthene			
Benzo (k) fluoranthene			
Benzo (a) pyrene			
Benzo (g,h,i) perylene			
D ₁₂ -Chrysene	555	1110	5550
Dibenzo (a,h) anthracene			
Fluoranthene			
Fluorene			
Indeno (1,2,3-cd) pyrene			
D ₈ -Naphthalene	538	1077	5385
D ₁₀ -Phenathrene	643	1286	6430
D ₁₀ -Pyrene	542	1085	5425

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC HYDROCARBONS

Sampling Equipment

Sampling resin beds used for organic enrichment are connected to a water source by an all-teflon manifold. The teflon manifold is designed to collect samples in duplicate by splitting sample flow with a tee to two resin beds. The inlet of the manifold is compatible with a 1/8" NPT female fitting on the water source. Two teflon needle valves (one on each side of the tee) are used to control water flow through the resin beds. A differential pressure of at least 20 psig is necessary for adequate flow control. When particulate levels are high, a teflon prefilter is placed upstream of the resin beds to remove particulates.

Sampling Procedure

Before sampling, all manifold parts are cleaned with HPLC-grade acetone and hexane. Preparation of the resin beds consists of flushing each with 4.0 ml HPLC-grade methanol, then 10.0 ml HPLC-grade water. One of the beds is spiked with isotope compounds in the laboratory. The spike level should be similar in concentration to the non-isotopic compounds being analyzed.

At the sampling site, the assembled teflon manifold and resin bed connections are leak-tested. The flow rate through each resin bed is adjusted using the flow valve and the sample flow volume maintained throughout sampling by periodic checks. The water after passing through each resin bed is collected in tared carboys. At the end of the sampling period, the water volume sampled is determined by weighing the carboy and water. At the completion of the sampling, the resin beds are wrapped in foil and kept refrigerated until analysis.

Resin Bed Elution

Each resin bed used to collect and concentrate polynuclear aromatic compounds is eluted using acidified tetrahydrofuran (THF). The acidified THF is then passed through a micro-drying column to remove water. The dried THF extract is collected in a 0.1 ml graduated vial. The micro-drying column is rinsed several times with acidified THF. The extract is then solvent exchanged and filtered. The volume of the extract is reduced under a gentle stream of nitrogen at room temperature. Finally, the concentrated extract is spiked with an isotope internal standard (D_{10} anthracene).

GC/MS Analysis

The extracts are stored in suitable vials until ready for analysis. A 1 μ l aliquot is injected on the column in a splitless injection mode. Single ion monitoring data is continuously acquired and the data stored for later workup. Instrumental parameters are described in Table I.

Data Reduction - Quantitation

The single ion chromatograms are plotted for the characteristic ion of each polynuclear aromatic being analyzed. Areas are then obtained for any peak with a retention time falling within a one minute window relative to the

standard run. Confirmation of identity is based on presence of the EPA selected ions (see Table II) for the individual compound, and all ions must maximize within one scan of each other. Furthermore, the ions must meet spectral integrity criteria for relative ratios ($\pm 20\%$). The areas under each characteristic ion are used to determine the extract concentration. The areas are compared to the internal standard intensity based on the following formula.

$$\text{Concentration}_{\text{unk}} = \frac{(\text{Area}_{\text{unk}}) (\text{Conc}_{\text{IS}})}{(\text{Area}_{\text{IS}}) (\text{R.F.}_{\text{unk}}) (\text{Dilution})}$$

where: unk = priority pollutant being quantitated

IS = internal standard D₁₀ anthracene

R.F. = response factor for the particular compound

Recovery Determinations

Each sample to be extracted is spiked with a surrogate standard (a deuterated analog). These materials are carried through the work-up procedure and quantitated along with the normal pollutants. The intensity of these spikes when compared to the area for D₁₀ anthracene added to the final extract allows a percent recovery to be determined for each extraction.

$$\text{Percent Recovery} = \frac{\text{Concentration of Spike Observed}}{\text{Concentration of Spike Added to Sample}} \times 100$$

Matrix Spikes

In addition, a matrix spike is analyzed with each set of samples. The material being extracted is spiked with a mixture of polyaromatic hydrocarbons appropriate for the fractions being analyzed. The recoveries of compounds in the spiking mix will provide information about the matrix effect of the sample on the analytical methodology. Individual component recoveries of the matrix spike are calculated as follows:

$$\text{Percent Recovery} = \frac{\text{SSR} - \text{SR}}{\text{SA}} \times 100$$

Where: SSR = Spike sample results ($\mu\text{g/g}$)

SR = Sample results ($\mu\text{g/g}$)

SA = Spike added ($\mu\text{g/g}$) from spiking mix

Duplicate Samples


Duplicate analyses are performed every 20 samples or one for each project, whichever is more frequent.

RECEIVED

JUL 27 1982

**MINN. POLLUTION
CONTROL AGENCY**

545 Indian Mound
Wayzata, Minnesota 55391
(612) 473-4224



July 26, 1982

**Mr. Mike Hansel
Regulatory Compliance Section
Solid and Hazardous Waste Division
Minnesota Pollution Control Agency
1935 West County Road B-2
Roseville, Minnesota 55113**

Re: St. Louis Park Well Abandonment Program

Dear Mr. Hansel:

Attached are the results of the soil sample submitted to the Iowa Hygienic Laboratory. This sample was taken from a depth of 690 feet on July 6, 1982.

The sample was split into three fractions by dissolving the sample in dichloromethane (85% soluble) and extracting with acid (1% soluble) and then base (1% soluble). All compounds identified are at concentrations greater than 10 mg/l.

Sincerely,

EUGENE A. HICKOK AND ASSOCIATES

**George W. Boyer, P.E.
Vice President**

bt

Enclosure

9626741

The University of Iowa

Iowa City, Iowa 52242

University Hygienic Laboratory

(319) 353-5990



RECEIVED JUL 23 1982

20 July 1982

E.A. Hickok and Associates
545 Indian Mound
Wayzata, MN 55391

Attn: Mr. George Boyer

RE: UHL #2-2346

Dear George:

Attached are the results of the "soil" analysis from St. Louis Park. As discussed with Ms. Patt Cain the sample was split into three fractions by dissolving the sample in dichloromethane (85% soluble) and extracting with acid (1% soluble) and then base (1% soluble). All compounds identified are at concentrations greater than 10 ppm.

Sincerely,

Armand F. Lange, Ph.D.
Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

lm

enclosure

cc: Dr. Splinter
Dr. Hahne
Ms. Cain
Mr. Brewer
File

*Analysis of soil sample
made in lab. for 9/10/82
by David D. Hahne and J. L. Hahne
all. M. C. Hahne 4/87*

9626742

Qualitative Analysis

Sample 2-2346

Acid Extract

<u>Scan #</u>	<u>Compound</u>
826	Naphthalene
962	2-Methyl naphthalene
982	1-Methyl naphthalene
979	2-Methyl quinoline
1055	
1103	Dimethyl quinoline (3 isomers)
1126	
1169	
1192	
1195	C ₃ Quinoline* (6 isomers)
1198	
1204	
1239	
1264	C ₄ Quinoline*
1314	9H-Carbazole
1329	2-Methyl naphthylisocyanide
1380	9-Methyl-9H-carbazole
1399	N-(phenylmethyl)-benzenemethanamine
1439	[1,1'-Biphenyl]-2-carboxamide
1457	Anthracene/phenanthrene
1466	Acridine
1476	Benzo[h]quinoline
1497	9H-Fluoren-9-imine
1519	Methyl acridine

9626743

Qualitative Analysis

Sample 2-2346

Acid Extract

<u>Scan #</u>	<u>Compound</u>
1555	
1565	Methyl benzo[f]quinoline (4 isomers)
1578	
1595	
1617	Phenylindole (2 isomers)
1626	
1610	
1618	
1625	•
1631	
1639	Methyl-phenyl-1H-indole (12 isomers)
1652	
1658	
1661	
1669	
1675	
1688	
1692	
1703	
1719	Anthracenecarbonitrile (4 isomers)
1765	
1788	
1809	
1821	Methyl anthracenecarbonitrile (4 isomers)
1856	
1881	

9626744

Qualitative Analysis

Sample 2-2346

Acid Extract

<u>Scan #</u>	<u>Compound</u>	
1853		
1895	Diphenylpyridene	(3 isomers)
1907		
2040		
2047	Methyl benz[c]acridene	(2 isomers)
2451	Dibenz[a,j]acridene	

*C₃, C₄ etc - the compound has additional Methyl (CH₃), Ethyl (CH₃, CH₂) etc. Groups attached to total the subscripted number of additional carbon atoms.

9626745

Qualitative Analysis

Sample 2-2346

Base Extract

<u>Scan #</u>	<u>Compound</u>
850	Naphthalene
992	2-Methyl naphthalene
1012	1-Methyl naphthalene
1121	
1137	
1141	C ₂ Naphthalene * (4 isomers)
1159	
1172	Acenaphthylene
1209	1,2-Dihydroacenaphthylene
1244	Dibenzofuran
1244	Naphthalenol
1311	9H-Fluorene
1341	Methyl naphthalenol
1442	Dimethyl-1-naphthol
1489	Dibenzodioxin (2 isomers)
1556	
1502	Anthracene/Phenanthrene
1528	3-Methoxy-1,1'-biphenyl
1569	
1586	Methyl dibenzothiophene (4 isomers)
1662	
1674	
1639	Methyl 9H-Pyrido[3,4-b]indol-7-ol (2 isomers)
1650	

9626746

Qualitative Analysis

Sample 2-2346

Base Extract

<u>Scan #</u>	<u>Compound</u>
1608	Methyl dibenzofuran (2 isomers)
1628	
1742	Fluoranthene
1785	Pyrene
1794	4-Methyl benzo[c]cinnoline
1804	1-Phenanthrenol

* C_3, C_4 etc The compound has additional Methyl(CH_3), Ethyl(CH_3CH_2) etc.
Groups attached to total the subscripted number of additional carbon atoms.

9626747

Qualitative Analysis
Sample 2-2346
Neutral Extract

<u>Scan #</u>	<u>Compound</u>	
362	Ethylbenzene	
374	Xylene	(3 isomers)
411		
524		
533		
573	C ₃ Benzene *	(4 isomers)
618		
638	1-Propenyl benzene	
652	1H-Indene	
672		
703		
712	C ₄ Benzene *	(5 isomers)
756		
762		
714	1-Ethenyl-3-ethylbenzene	
728	1-Ethenyl-3,5-dimethylbenzene	
741	Methyl benzofuran	
769	1-Methyl-2-(2-propenyl)benzene	
789	2,3-Dihydro-4-methyl-1H-indene	
804		
812	Methyl-1H-indene	(3 isomers)
824		
856	Naphthalene	
863	Benzo[b]thiophene	
866	Methyl decane	

9626748

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>
930	1,2-Dihydro-2-methyl naphthalene
935	2,3-Dihydro-4,7-dimethyl-1H-indene
942	1,2-Dihydro-3-methyl naphthalene
945	1,1-Dimethyl-1H-indene
956	1,2-Dihydro-6-methyl naphthalene
997	2-Methyl naphthalene
1005	6-Methyl benzo[b]thiophene
1017	1-Methyl naphthalene
1093	1,1'-Biphenyl
1110	
1123	
1140	C ₂ Naphthalene* (6 isomers)
1144	
1162	
1179	
1131	Dihydroacenaphthylene (2 isomers)
1150	
1175	Acenaphthylene
1208	
1218	
1270	Methyl-1,1'-biphenyl (5 isomers)
1283	
1259	
1213	Acenaphthene

9626749

Qualitative Analysis
Sample 2-2346
Neutral Extract

<u>Scan #</u>	<u>Compound</u>
1229	2-(1-Methylethyl)-naphthalene
1246	Dibenzofuran
1252	
1258	
1275	C ₃ Naphthalene * (5 isomers)
1278	
1292	
1295	1H-Phenylene
1316	9H-Fluorene
1340	1-(2-Propenyl)-naphthalene
1351	
1364	Methyl dibenzofuran (3 isomers)
1376	
1386	Dimethyl Biphenyl
1397	1-Methyl-7-(1-methylethyl)-naphthalene
1406	9,10-Dihydrophenanthrene
1427	
1434	Methyl-9H-fluorene (3 isomers)
1444	
1459	2-Methoxy-9H-fluorene
1480	Dibenzothiophene
1510	Anthracene/Phenanthrene
1545	Dimethyl-9H-fluorene
1555	9H-Carbazole

9626750

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>	
1571	1-Phenyl naphthalene	
1605		
1611		
1619	Methyl phenanthrene	(5 isomers)
1628		
1632		
1697		
1704	C ₂ Phenanthrene *	(3 isomers)
1720		
1747	Fluoranthene	
1790	Pyrene	
1839	Methyl pyrene	(2 isomers)
1860		
1873	11H-Benzo [a] fluorene	
1893	11H-Benzo [b] fluorene	
1947	1,1':2',1"-Terphenyl	
1983	Benzo [b] naphtho [1,2-d] thiophene	
1990	Benzo [c] phenanthrene	
2031	Chrysene	
2039	Benz [a] anthracene	
2054	triphenylene	
2106	Methyl chrysene benz [a] anthracene triphenylene	(4 isomers)
2114		
2121		
2131		

9626751

Qualitative Analysis
Sample 2-2346
Neutral Extract

<u>Scan #</u>	<u>Compound</u>
2239	Benzo[k]fluoranthene
2256	Benzo[j]fluoranthene
2289	Benzo[e]pyrene
2300	Benzo[a]pyrene
2317	Perylene
2577	Indeno[1,2,3,-cd]pyrene
2585	Dibenzanthracene
2651	Benzo(ghi)perylene
3088	Dibenzpyrene

* C₃, C₄ etc The compound has additional Methyl(CH₃), Ethyl(CH₃CH₂) etc.
Groups attached to total the subscripted number of additional carbon atoms.

9626752

7/20/82
N. REC'D JUL 26 1982
7-20-82

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence

From LOCATION , B. M. Hughes, Analytical Technology, Dayton
DATE , 20 July 1982
SUBJECT , 215.45718
REFERENCE , U.S.A. v. Reilly Tar and Chemical Corporation

cc: William Gregg/ERT
Jerry R. Rick/SEC
J. J. Brooks/MRC
P. M. Rivers/RTC

TO , Edward J. Schwartzbauer
Dorsey, Windhorst, Hannaford, Whitney, & Halladay
2200 First Bank Place East
Minneapolis, Minnesota 55402

In order to properly plan an analytical program which may best fit the needs of Reilly Tar and Chemical Corp., a study was conducted in which an aliquot of the tar from Well 23 (log no. 1-82-06-14-06, sample no. 6-11-1021) was analyzed for the major chromatographable species which were present. Figure 1 shows the total ion chromatogram from the capillary GC/MS analysis of a methylene chloride solution containing 0.00571 g/ml of the Well 23 tar. Table 1 shows the results of a detailed analysis of this mass spectral data and compares the present results with those from Midwest Research Institute (MRI) [authored by E. E. Conrad, et al] and entitled "Results of Analysis of Water Samples, Sludge Sample and Soil Samples for Polycyclic Aromatic Compounds (Hydrocarbons, Azaarenes, Phenols)". As can be seen, generally good agreement is seen between the two sets of data. The present results shown in Table 1 do not use specific PNA analytical standards for each PNA detected. Therefore, these data are estimates with accuracies on the order of a factor of two or three.


Several important conclusions can be drawn from the data shown in Table 1. The following paragraphs outline important features of these data, and suggest experimental approaches which may be of interest to Reilly Tar and Chemical Corp.

- (1) The present data agree very well with that reported by MRI. However, it is significant that a number of important methyl-PNAs, dihydroacenaphthene and dibenzofuran, were not measured in the MRI study. The presence or absence of these compounds may be highly significant in differentiating Well 23 from other possible PNA sources, especially if the methyl-PNAs, dihydroacenaphthene and dibenzofuran can be shown to be absent in St. Louis Park (SLP) well samples.
- (2) Although the compounds identified in Table 1 are not by far a complete list of compounds in the tar from Well 23, the compounds that we detected would be the basis of any detailed analytical studies which we would conduct in an effort to clarify the source of SLP water contamination. One disturbing feature of the water and tar analysis data reported by MRI and referenced above is the difference in the PNA distribution of the Well 23 and NAT LEAD water samples and the PNA distribution in the tar sample from Well 23 (shown in Table 1 of this report). We feel it is important at this time to conduct laboratory experiments to determine what PNA distribution would result from prolonged exposure of the tar sample from Well 23 to a sample of organic-free water. This study could be completed by the middle of August and may demonstrate what concentrations and PNA distributions could be expected from prolonged exposure of the tar to water. If the naphthalene concentration in the exposed water sample is ten times higher than phenanthrene, fluoranthene

408589

and pyrene, as is the case for the water samples from Well 23 and NAT LEAD reported by MRI, then the source of these PNAs can be assumed to be due to the tar injected into Well 23. On the other hand, if the distribution is very different from that reported by the MRI study, then there is a good probability that the PNAs in the water sample of Well 23 and NAT LEAD are due to alternate sources. This same tar/water exposure study can be used to investigate the concentrations of the methyl-PNAs, dihydroacenaphthene and dibenzofuran which were unreported in the MRI study. This single investigation could be important in developing the strategy of a pattern comparison study of water samples from SLP and tar from Well 23 or other PNA sources, if this approach is chosen by Reilly Tar and Chemical Corporation.

If you feel we should pursue the above experimental approach in determining the distribution of PNAs, methyl-PNAs, dihydroacenaphthene and dibenzofuran from the exposure of Well 23 tar to organic-free water, contact me or Joe Brooks immediately so that we may begin these studies as soon as possible.



B. Mason Hughes

BMH/cvd

408590

** SPECTRUM DISPLAY/EDIT **
1 UL 150/150 D10 + REILLY 6-11-1021 7/13/82 BMH
30(4)/8/300 BTL#34 D15477

FRN 15477
1ST SC/PG:1193
X= .25 Y= 4.00




Figure 1. Total ion chromatogram obtained from the capillary GC/MS analysis of a tar sample from Well 23. See Table 1 for the identifications of numbered peaks.

408501

** SPECTRUM DISPLAY/EDIT **
1 UL 150/150 D10 + REILLY 6-11-1021 7/13/82 BMH
30(4)/8/300 BTL#34 D15477

FRN 15477
1ST SC/PG:2057
X= .25 Y= 4.00




Figure 1. (cont'd)

408502

** SPECTRUM DISPLAY/EDIT **
1 UL 150/150 D10 + REILLY 6-11-1021 7/13/82 BMH
30(4)/8/300 BTL#34 D15477

FRN 15477
1ST SC/PG:2985
X= .25 Y= 4.00




Figure 1. (cont'd)

408593

TABLE 1. MAJOR COMPONENTS IDENTIFIED IN WELL 23
TAR SAMPLE NO. 6-11-1021, SHOWN
ANALYZED IN FIGURE 1.

<u>Peak No.</u>	<u>Compound Name</u>	<u>Concentration (mg/g)</u> ^a	<u>MRI Results (mg/g)</u>
1	Naphthalene	7.8	8.8
2	Methylnaphthalene isomers	10.8	NR ^c
3	N,N-diethyl-benzamine	(possible impurity)	
4	Acenaphthalene	2.1	5.8
5	Acenaphthalene	1.4	1.7
6	Dimethylnaphthalene isomers	8.5	NR
7	Dihydroacenaphthalene	4.8	NR
8	Dibenzofuran	5.1	NR
9	Fluorene	6.0	7.9
10	Trimethylnaphthalene isomers	2.9	NR
11	Phenanthrene	23.3	27
12	Anthracene-d ₁₀ (IS)	17.5	-
13	Anthracene	4.0	NR
14	Methylphenanthracene and/or anthracene isomers	8.4	NR
15	Fluoranthene	18.2	21
16	Pyrene	15.3	14
17	Benzo(a)anthracene	3.3	-
18	Chrysene	3.6	6.8
19	Isomer of Benzo(a)pyrene	4.1	17
20	Isomer of Benzo(a)pyrene	1.3	
21	Benzo(a)pyrene	2.0	5.9
22	Indeno (1,2,3,cd)pyrene	1.2	
23	Benzo(g,h,i)perylene	1.1	3.9

^a Estimated by comparing molecular ion responses to that of the internal standard (anthracene-d₁₀).

^b Possibly sum of these two isomers are reported in MRI study.

^c Not reported in MRI study.

MONSANTO RESEARCH CORPORATION

7-09-82
N.
Inter-Office Correspondence

From LOCATION : B. M. Hughes, Dayton Laboratory
(513) 268-3411 (ext. 436, 409, 209)
DATE : 9 July 1982
SUBJECT : Analysis Request Forms Received - 215.45718
REFERENCE : U.S.A. v. Reilly Tar & Chemical Corporation

cc : John C. Craun/ERT
Jerry R. Rick/SEC
J. J. Brooks

TO : Edward J. Schwartzbauer
Dorsey, Windhorst, Hannaford, Whitney, & Halladay
2200 First Bank Place East
Minneapolis, Minnesota 55402

REC'D JUL 13 1982

Enclosed are copies of analytical request forms which have been submitted for the analysis of samples received in conjunction with the project referenced above. MRC has assigned a unique log number for each set of samples and has outlined the requested analyses on the enclosed analytical request forms. If any incorrect information is included on the enclosed forms, please notify me immediately.

B. M. Hughes
B. M. Hughes

BMH/cvd

408595

ANALYSIS REQUEST

DATE

6/29/92

LOG NO.

1-82-06-29-01

MORGANTO RESEARCH CORPORATION

DAYT LABORATORY

REQUESTER**

Reilly

TAR / Soil Expl.

CHARGE NO.**

215,45718

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

Sample # 6/28/9:75

Composite

REPORT RESULTS TO

FILES / KULIK

Brooks

Gridley

M. Johnson

ANALYSIS REQUEST

FILES

Brooks

Gridley

P.M. Hughes

M. Johnson

SAMPLES FOR:

Hughes

SAMPLE LOCATION

1-21

FREEZER

Original Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

ANALYTICAL TECHNIQUE **

☐ GAS CHROMATOGRAPHY☐ NMR☐ ULTRAVIOLET☐ HPLC☐ VISIBLE☒ XRD☐ INFRARED☐ ICP☐ EMISSION☐ ATOMIC ABSORPTION☐ EDAX XRF☐ MASS SPEC☐ MICROSCOPY☐ GC/MS☐ OTHER☐ AUTO ANALYZER

QUAL. SEMIQUANT. QUANT.

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OT

** THIS INFORMATION MUST BE SUPPLIED BY ANALYSIS REQUEST ORIGINATOR

108086

SAMPLE TRANSMITTAL LETTER

Client REFILIN TARP CAMP Project Title REFILIN TARP CAMP
 Date Shipped 6-28-81 Shipped by REFILIN TARP CAMP
 Shipped From REFILIN TARP CAMP
 Shipped To AKA SAKO P. F. H. & C. O. Attention of REFILIN TARP CAMP
 Additional Shipping Information or Comments REFILIN TARP CAMP

Sample Description Code

COMMENTS:

6/22/975
OW 23
SAMPLE FROM
TAKEN FROM
Q.L.C. / SEC. (6-28-81)

REFILIN TARP CAMP

Samples Received by Alan H Ford

Date Samples Received 6/29/82

tape "seal" intact

Return Letter Received by Contract Laboratory

Date

MRC-QA #001T
 0610821h

408597

ANALYSIS REQUEST

DATE

28

LOG NO.

-82-07-02-0

MONSANTO RESEARCH CORPORATION REQUESTER**
DAY LABORATORY

CHARGE NO.**

215.45

8

REPORT RESULTS TO
FILES/KULIKBrooks
Gudde

SAMPLE DESCRIPTION

NUMBER OF

LESS

5

NUMBER OF SAMPLES **

5

ANALYSIS REQUEST
FILES

6/30/8:20 - Depth 653 from Bailer

6/30/10:00 - Depth 655'

6/30/14:00 - Depth 663 1/2'

7/1/10:50 - Depth 666-680

7/1/13:50 - Depth 680'

SAMPLES FOR:

Hughes

SAMPLE LOCATION

1-21 In
August

RECORDED BY:

To il

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ | QUANT. _____ |

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold 0

B.M. Hughes

SAMPLE TRANSMITTAL LETTER

120-8820

Client REILLY TAR & CHEM CO Project Title ST. LOUIS PARK, MINN
Date Shipped 7/1/82 Shipped by Soil Exploration Company
Shipped From Soil Exploration Company 1000 Commercial Ave St Paul MN 55114
Shipped To MONSANTO RESEARCH CORPORATION Attention of JOE BROOKS
Additional Shipping Information or Comments PACKED WITH 5 LBS DRY ICE

Sample Description Code

COMMENTS:

6/30/8:20	
6/30/8:20	SAND & GRAVEL FROM BAILER W/TAR DEPTH 5' 0"
6/30/10:00	TARRED SAND & GRAVEL (COARSE MATERIAL) DEPTH 5' 0"
6/30/14:00	SAND & GRAVEL W/TAR DEPTH 5' 0"
7/1/10:50	TARRED SAND & GRAVEL (COARSE MATERIAL) DEPTH 5' 0" FROM BAILER
7/1/12:50	TARRED SAND & GRAVEL (COARSE MATERIAL) DEPTH 5' 0" FROM BAILER
	FOR 7/1/12:50 SAMPLE WAS NOT TAKEN WITH BAILER
	FOR 7/1/12:50 SAMPLE WAS NOT TAKEN WITH BAILER

Samples Received by

Francine A. Belch

Date Samples Received

7/2/82

Return Letter Received by Contract Laboratory

Date

MRC-QA #001T
0610821h

408599

ANALYSIS REQUEST

DATE

7/7/82

LOG NO.

1-82-07-07-01

MONSANTO RESEARCH CORPORATION

REQUESTER**

CHARGE NO.**

REPORT RESULTS T

FILES/KULIK

DAY LABORATORY

Keilly Tar! Chem.

215.45718

Brooks
Gridley
Johnson

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

7/2/9:15

OW 23 St. Louis Park, MN

Bailer SAMPLE

Depth 685'

ANALYSIS REQUEST
FILESBrooks
Gridley
B.M. Hughes
M. Johnson

Original Chain of Custody to Gridley

SAMPLES FOR:
Hughes

RECORDED BY: A. Ford

SAMPLE LOCATION

1-21
Freezer

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input checked="" type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL _____ SEMIQUANT. _____ | QUANT. _____ |

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold 0

** THIS INFORMATION MUST BE SUPPLIED BY ANALYSIS REQUEST ORIGINATOR

SAMPLE TRANSMITTAL LETTER

REILLY TAR
Client REILLY TAR Project Title 0603 ST LOUIS PARK, MINN
Date Shipped 7-2-82 Shipped by ROSS CHIMON SOIL EXPLORATION COMPANY
Shipped From SOIL EXPLORATION COMPANY 6603 CUMMILL AVE ST PAUL, MINN
Shipped To: MUNSAMO CENTER (RESEARCH) CORPORATION Attention of JOE BOCKIS
Additional Shipping Information or Comments PACKED WITH DRY ICE, SAMPLE
MAY CONTAIN HAZARDOUS WASTE!

Sample Description Code

COMMENTS:

7/2/9:15

PL 33 ST LOUIS PARK, MN

RAILER SAMPLE

DEPT 44 → 685'

BLACK TARRY SUBSTANCE SAND LIT III

SCIENCE STONES

ES.
Boss L. A. Kmax
K.

Samples Received by Alan D. Ford (seal intact)

ce Samples Received 7/6/82

Turn Letter Received by Contract Laboratory _____ Date _____

MONSANTO RESEARCH CORPORATION

6-24-82.
Inter-Office Correspondence

FROM : B. M. Hughes/Dayton Laboratory
(513) 268-3411 (Ext. 436, 409, 209)
DATE : 24 June 1982
SUBJECT : Analysis Request Forms Received - 215.45718
REFERENCE : U.S.A. v. Reilly Tar & Chemical Corporation

cc: William Gregg/ERT
Jerry R. Rick/SEC
J. J. Brooks/MRC

TO

[REDACTED]
Dorsey, Windhorst, Hammarford, Whitney, & Hallada
2200 First Bank Place East
Minneapolis, Minnesota 55402

Chain-of-Custody
Sample Logs
6/14/82 - 6/29/82
(W23 work included)

Enclosed are copies of analytical request forms which have been submitted for the analysis of samples received in conjunction with the project referenced above. MRC has assigned a unique log number for each set of samples and has outlined the requested analyses on the enclosed analytical request forms. If any incorrect information is included on the enclosed forms, please notify me immediately.

B. M. Hughes

B. M. Hughes

409567

ANALYSIS REQUEST | DATE 6/14/82 | LOG NO. 1-82-06-14-06

MONSANTO RESEARCH CORPORATION | REQUESTER** J. Brooks/Reilly T&C | CHARGE NO.** 215. SEE BELOW
DAY N LABORATORY

SAMPLE DESCRIPTION | NUMBER OF BOTTLES: 4 | NUMBER OF SAMPLES: 4

W 023 6-11-82 Casing Shavings
W 023 6-11-1116 Core from well
W 023 6-11-82 Acetone Rinse
W 023 6-11-1021 Core from well

REPORT RESULTS TO
FILES / KULIK

Brooks
Gridley
M. HUGHES

ANALYSIS REQUEST
FILES

Brooks
Gridley
M. Johnson
M. HUGHES

SAMPLES FOR:
M. Hughes

SAMPLE LOCATION
1-21
Freezer

RECORDED BY: A. Ford

REQUIRED ANALYSIS** * NOTE: HOLD ANALYSES FOR COMPARABLE ANALYTICAL INFORMATION FROM CUSTOMER

215. 45718 - GC/MS
215. 45725 - ADMINISTRATIVE

Original Chain of Custody
to: J. Gridley

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input checked="" type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL _____ SEMIQUANT. _____ QUANT. _____ | |

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST	HOURS	INST. TIME

REQUIRED QA/QC

- Full Program
- WORK IS UNDER LITIGATION
- ALL PROCEDURES AND CONTROLS
MUST BE CAPABLE OF STANDING
IN COURT

409568

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE

☐ DISCARD ☐ RETURN HOLD FOR ☐ 30 DAYS ☐ 60 DAYS ☒ OTHER

INDEFINITE

CH. 1-23 INVESTIGATION

Sample Description Code

~~Comments~~

Log #

COMMENTS

W 023 6-11-1024

CORE SAMPLER SCRAPPINGS @ 574'

111 023 6-11-82 ALSTONER RIVER

Rinse From Tools

W 023 6-11-1116

CORE SAMPLER SCRAPINGS @ 575'

W023 6-11-82 Cosmic Surveys

Shavings of USC 9" casing laying
in the area from the shaft

Samples Received by Alan D. Ford - seal tape intact.

Date Samples Received 6/14/82 10:30 A.M.

Return Letter Received by Contract Laboratory _____ Date _____

ANALYSIS REQUEST

DATE

6/24/82

LOG NO.

1-82-06-24-02

MONSANTO SEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**

Reilly TAR

CHARGE NO.**

215.45718

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

6-18-14:42

fine, white sand with tar
substance within.

REPORT RESULTS

FILES /KULIK

Gridley
M. Johnson
J. BrooksANALYSIS REQUEST
FILESGridley
M. Johnson
B.M. Hughes
Brooks

SAMPLES FOR:

M. Hughes

SAMPLE LOCATION

1-21
FREEZEROriginal chain of custody to
J. Gridley

RECORDED BY:

A. Ford

REQUIRED ANALYSIS**

GC/MS - HOLD Analysis.

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

1-82-06-18-01

1-82-06-14-06

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |

QUAL _____ SEMIQUANT. _____ QUANT. _____

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

409570

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS☒ 0

CHAIN OF CUSTODY

PROJECT REILLY TAR & CHEM

LOCATION ST. LOUIS PARK MN.

	SAMPLE NUMBER	DATE COLLECTED
1.	<u>6181442</u> WHITE FINE SAND, WITH TAR 54 STABLE WITH IN	<u>6-18-82</u>
2.	_____	_____
3.	_____	_____
4.	_____	_____
5.	_____	_____
6.	_____	_____
7.	_____	_____

DATE SAMPLED 6-18-82

SHIPPED BY John E. Jorgensen

METHOD OF SHIPMENT FEDERAL EXPRESS

DATE RECEIVED 6/23/82

RECEIVED BY Alan H Ford

COMMENTS Seal tape intact.

ANALYSIS REQUEST

DATE

4/19/82

LOG NO.

1-82-06-18-01

MONSANTO SEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**

Kelly Tar/Brooks

CHARGE NO.**

SEE BELOW

REPORT RESULTS TO

FILES/KULIK

J. Brooks
Gridley
M. Hughes

SAMPLE DESCRIPTION

NUMBER OF BOTTLES

5

NUMBER OF SAMPLES

5

615900
615930
6151000
6151020
6171442ANALYSIS REQUEST
FILESBrooks
M. Hughes
Gridley
M. T. ...

SAMPLES FOR:

Hughes

SAMPLE LOCATION

1-2
FREEZER

Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS**

* NOTE: ALL ANALYTICAL WORK FOR CONFIDENTIAL
ANALYTICAL APPROACH/TASK FROM CUSTOMER.

215.45718 - GCL

215.45725 - ANALYTICAL

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input checked="" type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

- FULL PROCEED -

- WORK IS UNDER REVIEW -

- ALL PROCEDURES FOR CONFIDENTIAL
MUST BE CARRIED OUT

409572

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold

CHAIR OF CUSTODY

Project REMITAR

Location Sidewalk PA

SAMPLE NUMBER

DATE COLLECTED

1.	615900	6/15/82
2.	615930	6/15/82
3.	6151000	6/15/82
4.	6151030	6/15/82
5.	6171442	6/17/82
6.		
7.		

Date Shipped 6/17/82

Shipped By KARL RICK, SEC

Method of Shipment FEDERAL EXPRESS

Date Recieved 6/18/82

Received By Oliver H Ford "seal intact"

Comments _____

7-09-82

MONSANTO RESEARCH CORPORATION

Inter-Office Correspondence


From LOCATION : B. M. Hughes, Dayton Laboratory
(513) 268-3411 (ext. 436, 409, 209)
DATE : 9 July 1982
SUBJECT : Analysis Request Forms Received - 215.45718
REFERENCE : U.S.A. v. Reilly Tar & Chemical Corporation

cc : John C. Craun/ERT
Jerry R. Rick/SEC
J. J. Brooks

TO : Edward J. Schwartzbauer
Dorsey, Windhorst, Hannaford, Whitney, & Halladay
2200 First Bank Place East
Minneapolis, Minnesota 55402

REC'D JUL 13 1982

Enclosed are copies of analytical request forms which have been submitted for the analysis of samples received in conjunction with the project referenced above. MRC has assigned a unique log number for each set of samples and has outlined the requested analyses on the enclosed analytical request forms. If any incorrect information is included on the enclosed forms, please notify me immediately.



B. M. Hughes

BMH/cvd

408595

ANALYSIS REQUEST

DATE 6/29/82

LOG NO.

1-82-06-29-01

REPORT RESULTS TO:

FILES/KULIK

MONSANTO RESEARCH CORPORATION

REQUESTER**

CHARGE NO.**

DAYT LABORATORY

Reilly TAR/Soil Expl. 215,45718

Prooks

Gridley

M. Johnson

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

Sample # 6/28/9:75

Composite

ANALYSIS REQUEST TO

FILES

Brooks

Gridley

B.M. Hughes

M. Johnson

SAMPLES FOR:

Hughes

SAMPLE LOCATION

1-21

FREEZER

Original Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

☐ GAS CHROMATOGRAPHY☐ NMR☐ ULTRAVIOLET☐ HPLC☐ VISIBLE☐ XRD☐ INFRARED☐ ICP☐ EMISSION☐ ATOMIC ABSORPTION☐ EDAX XRF☐ MASS SPEC☐ MICROSCOPY☐ GC/MS☐ OTHER _____☐ AUTO ANALYZER

QUAL. _____ SEMIQUANT. _____ QUANT. _____

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OTHER

** THIS INFORMATION MUST BE SUPPLIED BY ANALYSIS REQUEST ORIGINATOR

408596

SAMPLE TRANSMITTAL LETTER

Client REILLY TARP COMPANY Project Title REILLY TARP COMPANY
Date Shipped 6-28-81 Shipped by REILLY TARP COMPANY
Shipped From REILLY TARP COMPANY
Shipped To ALASKA STATE DEPARTMENT Attention of MR. BROWN
Additional Shipping Information or Comments REILLY TARP COMPANY

Sample Description Code

COMMENTS:

[illegible]

Samples Received by Alan H Ford

Date Samples Received 4/29/82 tape "seal" intact

Return Letter Received by Contract Laboratory _____ Date _____

MRC-QA #001T
0610821h

408597

ANALYSIS REQUEST

DATE

7/2/82

LOG NO.

1-82-07-02-01

REPORT RESULTS TO

FILES /KULIK

MONSANTO RESEARCH CORPORATION

REQUESTER**

CHARGE NO.**

DAYT LABORATORY

Kelly T. Chem

215.45718

Brooks
Hudley
M. Johnson

SAMPLE DESCRIPTION

NUMBER OF BOTTLES

5

NUMBER OF SAMPLES **

5

6/30/8:20 - Depth 653 from Bailer

6/30/10:00 - Depth 655'

6/30/14:00 - Depth 663 1/2

7/1/10:50 - Depth 666-680

7/1/13:50 - Depth 680'

ANALYSIS REQUEST
FILESHudley
Brooks
BM Hughes
M. Johnson

SAMPLES FOR:

Hughes

SAMPLE LOCATION

1-21 In
Fresno

RECORDED BY:

To Kulik

REQUIRED ANALYSIS**

GC/MS Hold analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE

DISCARD



RETURN

HOLD FOR ☐ 30 DAYS

60 DAYS

Hold OTI

B. M. Hughes

SAMPLE TRANSMITTAL LETTER

120-8820

Client REILLY TAR & CHEM CORP Project Title ST. JAMES PARK, MN
 Date Shipped 7/1/82 Shipped by Soil Exploration Company
 Shipped From Soil Exploration Company 600 Commercial Ave. St. Paul, MN 55114
 Shipped To MONSANTO RESEARCH CORPORATION Attention of JOE BROOKS
 Additional Shipping Information or Comments PACKED WITH 5 LBS DRY ICE

Sample Description Code

COMMENTS:

Comments	
<u>6/30/8:20</u>	<u>SAND & GRAVEL FROM BAILER W/TAR</u> <u>DEPTH 5' 0"</u>
<u>6/30/10:00</u>	<u>TARRED SAND & GRAVEL (COARSE MATERIAL)</u> <u>DEPTH 5' 0"</u>
<u>6/30/14:00</u>	<u>SAND & GRAVEL W/TAR</u> <u>DEPTH 5' 0"</u>
<u>7/1/10:50</u>	<u>TARRED SUBSTANCE (COARSE MATERIAL) (DIFF</u> <u>DEPTH 5' 0" FROM BAILER</u>
<u>7/1/12:50</u>	<u>TARRED SUBSTANCE (COARSE MATERIAL) (DIFF</u> <u>DEPTH 5' 0" FROM BAILER</u>
	<u>FROM 7/1/12:50 SAMPLE WAS NOT</u> <u>IMBEDDED WITH DRAIN RECEPTION</u> <u>FROM REILLY AND ASSOCIATES</u>

Samples Received by

Francine D. Zelik

Date Samples Received

7/2/82

Return Letter Received by Contract Laboratory

Date

MRC-QA #001T

0610821h

408599

ANALYSIS REQUEST

DATE

7/7/82

LOG NO.

1-82-07-07-01

REPORT RESULTS TO
FILES /KULIK

MONSANTO RESEARCH CORPORATION

REQUESTER**

CHARGE NO.**

DAYT LABORATORY

Reilly Tar Chem.

215.45718

Brooks
Gridley
Johnson

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

7/2/9:15

OW 23 St. Louis Park, MN

Bailer SAMPLE

Depth 685'

ANALYSIS REQUEST
FILESBrooks
Gridley
B.M. Hughes
M. JohnsonSAMPLES FOR:
Hughes

SAMPLE LOCATION

1-21
Fretzer

Original Chain of Custody to Gridley

RECORDED BY:

A. Ford

REQUIRED ANALYSIS**

GC/MS Hold Analysis

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

☐ GAS CHROMATOGRAPHY☐ NMR☐ ULTRAVIOLET☐ HPLC☐ VISIBLE☒ XRD☐ INFRARED☐ ICP☐ EMISSION☐ ATOMIC ABSORPTION☐ EDAX XRF☐ MASS SPEC☐ MICROSCOPY☐ GC/MS☐ OTHER _____☐ AUTO ANALYZER

QUAL. _____ SEMIQUANT. _____ QUANT. _____

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold OTHER

** THIS INFORMATION MUST BE SUPPLIED BY ANALYSIS REQUEST ORIGINATOR

403000

SAMPLE TRANSMITTAL LETTER

REILLY TAR
Client REILLY TAR Project Title CR23 ST LOUIS PARK, MINN
Date Shipped 7-2-82 Shipped by ROSS Chimon Soil Exploration company
Shipped From SOIL EXPLORATION COMPANY 6602 CUMMILL AVE ST PAUL, MINN
Shipped To: MONSANTO RESEARCH (RESEARCH) CORPORATION Attention of JOE BOCKES
Additional Shipping Information or Comments PACKED WITH DRY ICE, SAMPLE
MAY CONTAIN HAZARDOUS WASTE!

Sample Description Code

COMMENTS:

~~CONFIDENTIAL~~

12/9:15

BL 23 ST LOUIS PARK, MN

BAILER SAMPLE

DEPTH \rightarrow 685'

BLACK TARRY SUB STRATE, SAND (WITHIN)
SOME STONES. //

25.
Boss L. A. Max.
H.

Samples Received by

Alan D. Ford (seed intact)

te Samples Received


7/6/82

Turn Letter Received by Contract Laboratory

Date


MONSANTO RESEARCH CORPORATION

N.
6-24-82.
Inter-Office Correspondence

From  : B. M. Hughes/Dayton Laboratory
(513) 268-3411 (Ext. 436, 409, 209)
DATE : 24 June 1982
SUBJECT : Analysis Request Forms Received - 215.45718
REFERENCE : U.S.A. v. Reilly Tar & Chemical Corporation

cc : William Gregg/ERT
Jerry R. Rick/SEC
J. J. Brooks/MRC

TO


Dorsey, Windhorst, Hammarford, Whitney, & Halladay
2200 First Bank Place East
Minneapolis, Minnesota 55402

Enclosed are copies of analytical request forms which have been submitted for the analysis of samples received in conjunction with the project referenced above. MRC has assigned a unique log number for each set of samples and has outlined the requested analyses on the enclosed analytical request forms. If any incorrect information is included on the enclosed forms, please notify me immediately.



B. M. Hughes

409567

ANALYSIS REQUEST

DATE

6/14/82

LOG NO.

1-82-06-14-06

MONSANTO RESEARCH CORPORATION

REQUESTER**

CHARGE NO.**

SEE BELOW

DAY N LABORATORY

J. Brooks/Reilly T/C

215.

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 4

NUMBER OF SAMPLES -- 4

REPORT RESULTS TO

FILES / KULIK

Brooks
Gridley
M. HUGHES

W 023 6-11-82 Casing Shavings

W 023 6-11-1116 Core from well

W 023 6-11-82 Acetone Rinse

W 023 6-11-1021 Core from well

ANALYSIS REQUEST
FILESBrooks
Gridley
M. Johnson
M. HUGHES

SAMPLES FOR:

M. Hughes

SAMPLE LOCATION

1-21

Freezer

RECORDED BY:

A. Ford

REQUIRED ANALYSIS** * NOTE: HOLD ANALYSES FOR COMPARABLE ANALYTICAL INFORMATION FROM CUSTOMER

215. 45718 - GC/MS
215. 45725 - ADMINISTRATIVEOriginal Chain of Custody
to: J. Gridley

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input checked="" type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL _____ SEMIQUANT. _____ | QUANT. _____ |

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST

HOURS

INST. TIME

REQUIRED QA/QC

- Full Program

- WORK IS UNDER LITIGATION

- ALL PROCEDURES AND CONTROLS
MUST BE CAPABLE OF STANDING
IN COURT

409568

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS☒

01

- INDEFINITE

SAMPLE TRANSMITTAL LETTER

Client Reilly, Tadhg & Citizens Project Title CU-23 INVESTIGATION
Date Shipped 6/10/72 Shipped by Jerry Rick, SEC
Shipped From St. Louis Park, MN
Shipped To Albuquerque Research Attention of Joe Brooks
Additional Shipping Information or Comments SAMPLES WERE SEALED IN COOLERS
AT ST. LOUIS PARK AND GIVEN TO MARK J. HANSEN TO RETURN WITH
IN A HIS PLAS - W/OUT

Sample Description Code

~~CONFIDENTIAL~~

LOG #	COMMENTS
W 023 6-11-1021	CORE SAMPLER SCRAPINGS @ 574'
W 023 6-11-82 ACETONE RINSE	RINSE FROM TOOLS
W 023 6-11-1116	CORE SAMPLER SCRAPINGS @ 575'
W 023 6-11-82 CASING & SCRAPINGS	Scrapings off USC's 4" CASING LAYING IN RE-USE OF 1" IN 1" HUSK

Samples Received by Alan D. Ford - seal tape intact.

Date Samples Received 6/14/82 10:30 A.M.

Return Letter Received by Contract Laboratory _____ Date _____

ANALYSIS REQUEST | DATE 6/24/82 | LOG NO. 1-82-06-24-02

MONSANTO SEARCH CORPORATION
DAYTON LABORATORY

REQUESTER**
Reilly TAR

CHARGE NO.**
215.45718

SAMPLE DESCRIPTION

NUMBER OF BOTTLES: 1

NUMBER OF SAMPLES ** 1

6-18-14:42

fine, white sand with tar substance within.

Original chain of custody to J. Gridley

RECORDED BY: A. Ford

REPORT RESULTS TO
FILES/KULIK
Gridley
M. Johnson
J. Brooks

ANALYSIS REQUEST
FILES
Gridley
M. Johnson
B.M. Hughes
Brooks

SAMPLES FOR:
M. Hughes

SAMPLE LOCATION
1-21
FREEZER

REQUIRED ANALYSIS**

GC/MS - HOLD Analysis.

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

1-82-06-18-01
1-82-06-14-06

COMPLETION DATE

TIME ALLOTTED FOR ANALYSES

ANALYST HOURS INST. TIME

ANALYTICAL TECHNIQUE **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL _____ SEMIQUANT. _____ | QUANT. _____ |

REQUIRED QA/QC

409570

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE

☐ DISCARD ☐ RETURN

HOLD FOR ☐ 30 DAYS

☐ 60 DAYS

☒

CHAIN OF CUSTODY

PROJECT REILLY TAR + CHEM

LOCATION ST. LOUIS PARK MN.

	<u>SAMPLE NUMBER</u>	<u>DATE COLLECTED</u>
1.	<u>6181442</u> <small>WHITE FINE SAND, WITH TAR SYNTHETIC WITH IN</small>	<u>6-18-82</u>
2.	_____	_____
3.	_____	_____
4.	_____	_____
5.	_____	_____
6.	_____	_____
7.	_____	_____

DATE SAMPLED 6-18-82

SHIPPED BY John C. Jorgensen

METHOD OF SHIPMENT FEDERAL EXPRESS

DATE RECEIVED 6/23/82

RECEIVED BY Alan H Ford

COMMENTS Seal tape intact.

409571

ANALYSIS REQUEST | DATE 4/19/82 | LOG NO. 1-82-06-18-01

MONSANTO RESEARCH CORPORATION
DAYTON LABORATORYREQUESTER**
Keilly Tar / BrooksCHARGE NO.**
SEE BELOWREPORT RESULTS
FILES / KULIK
J. Brooks
Gridley
M. Hughes

SAMPLE DESCRIPTION

NUMBER OF BOTTLES 5

NUMBER OF SAMPLES 5

615900
615930
6151000
6151020
6171442ANALYSIS REQUEST
FILES
Brooks
M. Hughes
Gridley
M. T. ...SAMPLES FOR:
HughesSAMPLE LOCATION
1-21
FREEZER

Chain of Custody to Gridley

RECORDED BY: A. Ford

REQUIRED ANALYSIS** * NOTE: THIS ANALYTICAL WORK FOR INFORMATION OF
ANALYTICAL APPROACH/TASK FROM CUSTOMER.215. 45718 - GC/MS
215. 45725 - ANALYTICAL

KNOWN HEALTH HAZARD PRESENTED BY SAMPLE: **

ANALYTICAL TECHNIQUE **

REFERENCE TO PREVIOUS WORK (REQUEST #, JOURNAL, ETC.) **

- | | |
|---|--|
| <input type="checkbox"/> GAS CHROMATOGRAPHY | <input type="checkbox"/> NMR |
| <input type="checkbox"/> ULTRAVIOLET | <input type="checkbox"/> HPLC |
| <input type="checkbox"/> VISIBLE | <input type="checkbox"/> XRD |
| <input type="checkbox"/> INFRARED | <input type="checkbox"/> ICP |
| <input type="checkbox"/> EMISSION | <input type="checkbox"/> ATOMIC ABSORPTION |
| <input type="checkbox"/> EDAX XRF | <input type="checkbox"/> MASS SPEC |
| <input type="checkbox"/> MICROSCOPY | <input checked="" type="checkbox"/> GC/MS |
| <input type="checkbox"/> OTHER _____ | <input type="checkbox"/> AUTO ANALYZER |
| QUAL. _____ SEMIQUANT. _____ QUANT. _____ | |

COMPLETION DATE _____

TIME ALLOTTED FOR ANALYSES

ANALYST HOURS INST. TIME

REQUIRED QA/QC

- FULL PROTOCOL
- WMS IS UNCLE LITIGATION
- ALL PROCEEDINGS FOR LITIGATION
- MUST BE CAREFUL OF SAMPLES

409572

**SAMPLE DISPOSAL:
AFTER REPORT COMPLETE☐ DISCARD☐ RETURNHOLD FOR ☐ 30 DAYS☐ 60 DAYS

Hold

CHAIR OF CUSTODY

Project REM-ITAR

Location Sidewalk PA

SAMPLE NUMBER

DATE COLLECTED

1. 615900

6/15/82

2. 615930

6/15/82

3. 6151000

6/15/82

4. 6151020

6/15/82

5. 6171442

6/17/82

6.

7.

Date Shipped 6/17/82

Shipped By KARY RICK, SEC

Method of Shipment FEDERAL EXPRESS

Date Recieved

6/18/82

Received By


Walter H Ford

"seal intact"

Comments

6/15/82
IN.

Hash Output File
1982



Minnesota Pollution Control Agency

June 15, 1982

Mr. George W. Boyer, P.E.
E. A. Hickok and Associates, Inc.
545 Indian Mound
Wayzata, Minnesota 55391

Dear Mr. Boyer:

Thank you for your submittal of July 9, 1982 regarding progress on the St. Louis Park Well Abandonment Program. I have several comments on your submittal, as follows:

1. Copies. Please delete Mr. Jim Pankanin, USEPA, Chicago, from your list of people to receive copies, and substitute Mr. Paul Bitter, same address. I will send Mr. Bitter a copy of this submittal, and I apologize for not noting this change earlier.
2. Well 23. The Minnesota Pollution Control Agency (Agency) understands that work on Well 23 has progressed much slower than anticipated and that a number of difficulties have been encountered. There were a number of inconsistencies and omissions in your progress report, however, which we would like your comments on:
 - a. Starting depth. You indicate that creosote was encountered at an initial depth of 567.8. My notes from the 11th of June indicated that creosote was encountered at 574. Please explain.
 - b. The progress report did not detail that fibers were found at one point and that, in fact, the borings were almost clean sand just prior to the point where the split spoon sampler was lost. I would hope that your field notes are, and final report would be, much more detailed than your progress report is. I would prefer that such significant details be reported in future progress reports.

Phone: _____

1935 West County Road B2, Roseville, Minnesota 55113-2785

Regional Offices • Duluth/Brainerd/Detroit Lakes/Marshall/Rochester

Equal Opportunity Employer



- c. Depth 601. Your progress report indicates that a depth of 601 was reached on Friday, June 11, 1982. Then, on Monday, June 14, drilling began at a depth of 593. Please explain.
3. Search and Inventory. Your Detailed Work Plan indicated that the door-to-door survey would begin July 23, 1982. Subsequent discussions with the city fixed that date to July 21, 1982, and significant community relations efforts have been started using that date. Please do not start the survey until July 21, 1982 as we discussed, so that the survey will more effectively mesh with other activities. In the future, please do not move any activities ahead in the schedule without notifying the Agency ahead of time. I do not regard a notice which I receive on the day that activity will start as prior notice.

4. Expenditures

- a. Expenses. Expenses will be approved as noted.
- b. Engineering Costs - Well 23. Certain engineering costs are in excess of the amount spelled out in the contract and will not be approved. Specifically, page 15 of the contract provides for the following engineering costs:

1) Field geologist 173 hours at \$36.00 per hour

6) Interaction with state 10 hours at \$78.00 per hour

Therefore, I will approve the following engineering costs:

144.5 hours at \$36.00 per hour = 5,202.00

10 hours at \$78.00 per hour = 780.00

TOTAL = 5,982.00

The remaining costs of \$5,593.80 are not authorized in the contract, were not authorized prior to expenditure as provided on page 13 of the contract, and will not be approved.

It is apparent that additional time will be needed for the field geologist and for interaction. Please estimate the additional time necessary, and inform us as soon as possible, so that the contract can be amended, if necessary.


- c. Engineering Costs - Search and Inventory. Engineering costs will be approved as noted. However, the hourly rates do not match the rates in the contract. Please explain.

Mr. George W. Boyer, P.E
Page Three

5. Delinquency. Every major item of work and report on this project have been late by several days to a week. While some of this delay has been due to circumstances beyond your control (e.g. work on Well 23), submission of the detailed work plan, submission of the first progress report, and response to my letter of June 17 have been delinquent. This is not satisfactory. In the future, please be more timely in your interactions with this office.

I would be happy to discuss this matter with you at your earliest convenience.

Sincerely,

A handwritten signature in cursive script, appearing to read "Michael J. Hansel".

Michael J. Hansel
Regulatory Compliance Section
Solid and Hazardous Waste Division

MJH/dc

cc. Paul Bitter, U.S. Environmental Protection Agency

The University of Iowa

Iowa City, Iowa 52242

University Hygienic Laboratory

(319) 353-5990



RECEIVED JUL 23 1982

20 July 1982

E.A. Hickok and Associates
545 Indian Mound
Wayzata, MN 55391

Attn: Mr. George Boyer

RE: UHL #2-2346

Dear George:

Attached are the results of the "soil" analysis from St. Louis Park. As discussed with Ms. Patt Cain the sample was split into three fractions by dissolving the sample in dichloromethane (85% soluble) and extracting with acid (1% soluble) and then base (1% soluble). All compounds identified are at concentrations greater than 10 ppm.

Sincerely,

Armand F. Lange, Ph.D.

Armand F. Lange, Ph.D.
Chief, Organic Analytical Division

lm

enclosure

cc: Dr. Splinter
Dr. Hahne
Ms. Cain
Mr. Brewer
File

Qualitative Analysis

Sample 2-2346

Acid Extract

<u>Scan #</u>	<u>Compound</u>
826	Naphthalene
962	2-Methyl naphthalene
982	1-Methyl naphthalene
979	2-Methyl quinoline
1055	
1103	Dimethyl quinoline (3 isomers)
1126	
1169	
1192	
1195	C ₃ Quinoline* (6 isomers)
1198	
1204	
1239	
1264	C ₄ Quinoline*
1314	9H-Carbazole
1329	2-Methyl naphthylisocyanide
1380	9-Methyl-9H-carbazole
1399	N-(phenylmethyl)-benzenemethanamine
1439	[1,1'-Biphenyl]-2-carboxamide
1457	Anthracene/phenanthrene
1466	Acridine
1476	Benzo[h]quinoline
1497	9H-Fluoren-9-imine
1519	Methyl acridine

Qualitative Analysis

Sample 2-2346

Acid Extract

<u>Scan #</u>	<u>Compound</u>
1555	
1565	Methyl benzo[f]quinoline (4 isomers)
1578	
1595	
1617	Phenylindole (2 isomers)
1626	
1610	
1618	
1625	
1631	
1639	Methyl-phenyl-1H-indole (12 isomers)
1652	
1658	
1661	
1669	
1675	
1688	
1692	
1703	
1719	Anthracenecarbonitrile (4 isomers)
1765	
1788	
1809	
1821	Methyl anthracenecarbonitrile (4 isomers)
1856	
1881	

Qualitative Analysis
Sample 2-2346
Acid Extract

<u>Scan #</u>	<u>Compound</u>	
1853	Diphenylpyridene	(3 isomers)
1895		
1907		
2040	Methyl benz[c]acridene	(2 isomers)
2047		
2451	Dibenz[a,j]acridene	

*C₃, C₄ etc - the compound has additional Methyl (CH₃), Ethyl (CH₃, CH₂) etc. Groups attached to total the subscripted number of additional carbon atoms.

Qualitative Analysis

Sample 2-2346

Base Extract

<u>Scan #</u>	<u>Compound</u>
850	Naphthalene
992	2-Methyl naphthalene
1012	1-Methyl naphthalene
1121	
1137	
1141	C ₂ Naphthalene * (4 isomers)
1159	
1172	Acenaphthylene
1209	1,2-Dihydroacenaphthylene
1244	Dibenzofuran
1244	Naphthalenol
1311	9H-Fluorene
1341	Methyl naphthalenol
1442	Dimethyl-1-naphthol
1489	Dibenzodioxin (2 isomers)
1556	
1502	Anthracene/Phenanthrene
1528	3-Methoxy-1,1'-biphenyl
1569	
1586	Methyl dibenzothiophene (4 isomers)
1662	
1674	
1639	Methyl 9H-Pyrido[3,4-b]indol-7-ol (2 isomers)
1650	

Qualitative Analysis

Sample 2-2346

Base Extract

<u>Scan #</u>	<u>Compound</u>
1608	Methyl dibenzofuran
1628	(2 isomers)
1742	Fluoranthene
1785	Pyrene
1794	4-Methyl benzo[c]cinnoline
1804	1-Phenanthrenol

* C₃, C₄ etc The compound has additional Methyl(CH₃), Ethyl(CH₃CH₂) etc. Groups attached to total the subscripted number of additional carbon atoms.

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>	
362	Ethylbenzene	
374	Xylene	(3 isomers)
411		
524		
533		
573	C ₃ Benzene *	(4 isomers)
618		
638	1-Propenyl benzene	
652	1H-Indene	
672		
703		
712	C ₄ Benzene *	(5 isomers)
756		
762		
714	1-Ethenyl-3-ethylbenzene	
728	1-Ethenyl-3,5-dimethylbenzene	
741	Methyl benzofuran	
769	1-Methyl-2-(2-propenyl)benzene	
789	2,3-Dihydro-4-methyl-1H-indene	
804		
812	Methyl-1H-indene	(3 isomers)
824		
856	Naphthalene	
863	Benzo[b]thiophene	
866	Methyl decane	

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>
930	1,2-Dihydro-2-methyl naphthalene
935	2,3-Dihydro-4,7-dimethyl-1H-indene
942	1,2-Dihydro-3-methyl naphthalene
945	1,1-Dimethyl-1H-indene
956	1,2-Dihydro-6-methyl naphthalene
997	2-Methyl naphthalene
1005	6-Methyl benzo[b]thiophene
1017	1-Methyl naphthalene
1093	1,1'-Biphenyl
1110	
1123	
1140	C ₂ Naphthalene* (6 isomers)
1144	
1162	
1179	
1131	Dihydroacenaphthylene (2 isomers)
1150	
1175	Acenaphthylene
1208	
1218	
1270	Methyl-1,1'-biphenyl (5 isomers)
1283	
1259	
1213	Acenaphthene

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>
1229	2-(1-Methylethyl)-naphthalene
1246	Dibenzofuran
1252	
1258	
1275	C ₃ Naphthalene * (5 isomers)
1278	
1292	
1295	1H-Phenylene
1316	9H-Fluorene
1340	1-(2-Propenyl)-naphthalene
1351	
1364	Methyl dibenzofuran (3 isomers)
1376	
1386	Dimethyl Biphenyl
1397	1-Methyl-7-(1-methylethyl)-naphthalene
1406	9,10-Dihydrophenanthrene
1427	
1434	Methyl-9H-fluorene (3 isomers)
1444	
1459	2-Methoxy-9H-fluorene
1480	Dibenzothiophene
1510	Anthracene/Phenanthrene
1545	Dimethyl-9H-fluorene
1555	9H-Carbazole

Qualitative Analysis

Sample 2-2346

Neutral Extract

Scan #	Compound
1571	1-Phenyl naphthalene
1605	
1611	
1619	Methyl phenanthrene (5 isomers)
1628	
1632	
1697	
1704	C ₂ Phenanthrene* (3 isomers)
1720	
1747	Fluoranthene
1790	Pyrene
1839	Methyl pyrene (2 isomers)
1860	
1873	11H-Benzo[a]fluorene
1893	11H-Benzo[b]fluorene
1947	1,1':2',1''-Terphenyl
1983	Benzo[b]naphtho[1,2-d]thiophene
1990	Benzo[c]phenanthrene
2031	Chrysene
2039	Benz[a]anthracene
2054	triphenylene
2106	Methyl chrysene benz[a]anthracene triphenylene (4 isomers)
2114	
2121	
2131	

Qualitative Analysis

Sample 2-2346

Neutral Extract

<u>Scan #</u>	<u>Compound</u>
2239	Benzo[k]fluoranthene
2256	Benzo[j]fluoranthene
2289	Benzo[e]pyrene
2300	Benzo[a]pyrene
2317	Perylene
2577	Indeno[1,2,3,-cd]pyrene
2585	Dibenzanthracene
2651	Benzo(ghi)perylene
3088	Dibenzpyrene

* C_3, C_4 etc The compound has additional Methyl(CH_3), Ethyl(CH_3CH_2) etc.
Groups attached to total the subscripted number of additional carbon atoms.

Braun

STATE OF MINNESOTA

Office Memorandum

DEPARTMENT HEALTH

Jim Pankanian

TO : U.S. Environmental Protection Agency
Enforcement Division
230 S. Dearborn

DATE: 5/21/81

FROM : Chicago, Illinois 60604

PHONE: 612-296-5297

SUBJECT: Hickok Report 6-18-3 : Acceptable Contaminant Levels

I am forwarding to you for your information and review a copy of Hickok's report
"Acceptable Contaminant Levels". This is a revision of their earlier report.

002614

MEMORANDUM NO. G18-3


DATE: May 19, 1981

TITLE: ST. LOUIS PARK GROUNDWATER CONTAMINATION STUDY
LITERATURE REVIEW - ACCEPTABLE CONTAMINANT LEVELS

revised edition

ABSTRACT: ACCEPTABLE CONTAMINANT LEVELS, OR CRITERIA, ARE PROPOSED FOR POLYNUCLEAR AROMATIC HYDROCARBONS (PAH) IN WATER AND SOIL, AS RELATED TO SOIL AND GROUNDWATER CONTAMINATION FROM THE FORMER REPUBLIC CREOSOTE SITE IN ST. LOUIS PARK, MINNESOTA. CRITERIA ARE PROPOSED FOR (1) GROUNDWATER, (2) SOIL, (3) DISCHARGE TO SURFACE WATER, AND (4) DISCHARGE TO SANITARY SEWER, AND ARE BASED ON EPA CRITERIA AND LABORATORY DETECTION LIMITS. CRITERIA ARE PROPOSED FOR INDIVIDUAL PAH COMPOUNDS, INCLUDING BOTH KNOWN CARCINOGENS AND OTHER PAH. AN ANNOTATED BIBLIOGRAPHY IS INCLUDED. THIS MEMORANDUM REPRESENTS COMPLETION OF TASK 1040 OF THE REFERENCED PROJECT.

EUGENE A. HICKOK & ASSOCIATES
HYDROLOGISTS - ENGINEERS - 545 INDIAN MOUND, WAYZATA, MINNESOTA 55391



EUGENE A. HICKOK & ASSOCIATES

HYDROLOGISTS - ENGINEERS - 545 INDIAN MOUND, WAYZATA, MINNESOTA 55391

002615

LITERATURE REVIEW - ACCEPTABLE CONTAMINANT LEVELS

I. INTRODUCTION

This memorandum proposes acceptable contaminant levels (criteria) for polynuclear aromatic hydrocarbons (PAH) in water and soil. Criteria for PAH are required for a rational approach to cleaning up soil and groundwater contamination from the former Republic Creosote site in St. Louis Park.

Criteria for the following are proposed:

- Groundwater
- Soil
- Discharge to surface water
- Discharge to sanitary sewer

Also included in this memorandum is an annotated bibliography of the literature reviewed.

By way of background, two agencies in recent years have established PAH criteria for waters. The World Health Organization in 1971 specified a maximum permissible concentration in drinking water of 200 ng/l for the sum of six PAH compounds (fluoranthene, benzo(a) pyrene, benzo(b) fluoranthene, benzo(k) fluoranthene, benzo(g,h,i) perylene and indeno (1,2,3-c,d) pyrene). This criterion does not have a firm toxicological basis and has generally come to be regarded as obsolete. The U. S. Environmental Protection Agency (EPA) published ambient water quality criteria for PAH in 1978, with an updated version in October 1980. This will be discussed in the sequel.

The primary concern over PAH contamination stems from the cancer-causing, or carcinogenic, property of a number of PAH compounds. Some 12 PAH compounds are listed as "having substantial evidence of carcinogenicity" in the July 14, 1980 EPA publication, "The Carcinogen Assessment Group's List of Carcinogens." These compounds are shown in Table 1 - Carcinogenic PAH. It should be noted that this list is almost surely incomplete: relatively few of the many PAH compounds have been thoroughly investigated for carcinogenicity.

II. REVIEW OF CRITERIA PUBLISHED BY EPA

It is widely held that there is no threshold level for carcinogens, that is, a level of exposure below which there is no carcinogenic effect. Instead, it is believed that very low exposure does cause cancer, but at a proportionately low rate of incidence.

This concept is embodied in the October 1980 EPA document, "Ambient Water Quality Criteria for Polynuclear Aromatic Hydrocarbons," which states:

TABLE 1 - CARCINOGENIC PAH

Benz(a)anthracene
Benzo(a)pyrene
Benzo(b)fluoranthene
Benzo(j)fluoroanthene
Chrysene
Dibenz(a,h)anthracene
Dibenzo(a,e)pyrene
Dibenzo(a,h)pyrene
Dibenzo(a,i)pyrene
7,12-dimethylbenz(a)anthracene
Indeno(1,2,3-c,d)pyrene
3-Methylcholanthrene

SOURCE: U. S. Environmental Protection Agency, "The Carcinogen Assessment Group's List of Carcinogens," July 14, 1980.

For the maximum protection of human health from the potential carcinogenic effects due to exposure of polynuclear aromatic hydrocarbons through ingestion of contaminated water and contaminated aquatic organisms, the ambient water concentration should be zero based on the non-threshold assumption for this chemical.

Although this statement may appear logical taken at face value, there are three serious objections to the specification of a zero criterion.

First, no chemical process is capable of absolute, or 100 percent, efficiency. Thus, treatment of any water contaminated with PAH cannot reasonably be expected to yield water meeting a zero criterion. This is a constraint imposed by natural law. (Incidentally, there are certain literature references to activated carbon adsorption efficiencies of 100 percent for some PAH compounds; however, this is a result of numerical round off of some actual efficiency such as 99.95 percent. The truth of the matter is, the only road to 100 percent efficiency is an infinite succession of additional 9's following 99. percent.)

The second objection to a zero criterion is based on the ubiquity of PAH in the earth's environment. The literature reveals that PAH are detected in raw and finished drinking water sources in the U. S. and elsewhere, German groundwater, Belgian aquifers, Norwegian snow, Russian rivers, urban and rural air in Japan, the U. S. and elsewhere, marine and lake sediments, fresh vegetables, meats and fish, grain products, and, as rare minerals, in certain geologic formations. The major source of PAH in the environment is believed to be fossil fuel combustion, so its widespread occurrence is not surprising in light of the possibilities for atmospheric distribution. However, natural fires surely contribute some background of PAH, as does incomplete combustion of most any organic or biogenic material.

In any case, it appears unlikely that a zero level of PAH exists in any environmental sample from any region of the biosphere, excepting perhaps igneous rock and any rock formed prior to the era of terrestrial life. This bold assertion is made with the knowledge that improved analytical techniques have in recent years yielded lower and lower limits of detection for PAH.

Which points to the third objection: despite the great analytical advances, a zero level of PAH cannot be measured. Just as no chemical process can be 100 percent efficient, no analytical technique can achieve a zero detection limit. Therefore there is no way to monitor a zero criterion.

Perhaps in recognition of the above objections, the October 1980 EPA document modifies the previously quoted statement with the following:

However, zero level may not be attainable at the present time. Therefore, the levels which may result in incremental increase of cancer risk over the lifetime are estimated at 10^{-5} , 10^{-6} and 10^{-7} . The corresponding recommended criteria are 28.0 ng/l, 2.8 ng/l and 0.28 ng/l, respectively.

These EPA criteria are based on a study of the specific compound benzo(a)pyrene (BaP). BaP is believed to be the most potent carcinogen of the PAH. Therefore it is conservative, and reasonable, to use BaP as a basis for other PAH criteria. One way to do this is to apply a concentration limit determined for BaP to other individual PAH compounds. Another way is to require the sum of PAH concentrations to meet a limit originally determined for BaP alone. Both procedures are conservative, but the second one is extremely so, and is particularly difficult to work with because the laboratory detection limits for many PAH exceed the stated concentration limits. For this reason, setting limits for individual compounds is preferable.

III. PROPOSED CRITERIA

The criteria proposed here are based on the EPA criteria, as applied to individual PAH compounds. A combination of risk level and detection limits determines the specific limits. Separate criteria are proposed for those PAH known to be carcinogenic, and for all other PAH. Limits for "other PAH" are set due to concern for synergistic effects (for example, certain non-carcinogenic PAH have been shown to enhance the carcinogenicity of certain PAH carcinogens). Criteria for potable water are first proposed.

The Minnesota Department of Health has commonly adopted a risk level of 10^{-5} for single chemical species. However, a risk level of 10^{-6} is more appropriate for individual carcinogenic PAH compounds, since several such compounds can occur together in creosote-contaminated water. The 10^{-6} risk level corresponds to a concentration limit of 2.8 ng/l for carcinogenic PAH. This is the proposed acceptable level for carcinogenic PAH; however, it is proposed to consider the detection limit as the criterion whenever the detection limit exceeds 2.8 ng/l. Detection limits vary from compound to compound, from laboratory to laboratory, from sample to sample, and from time to time.

The Minnesota Department of Health laboratory can at present measure half or more of the 12 known PAH carcinogens. In this laboratory, the likely range of detection limits is 0.5 - 10.0 ng/l for the carcinogenic PAH.

For other PAH, a concentration limit of 28.0 ng/l is proposed. This corresponds to a 10^{-5} risk level for BaP, but it cannot be related to a risk level for these "other PAH" since they are (at least presumably) non-carcinogenic. This is a purely judgmental limit. It is intended to prevent substantial synergism with carcinogenic PAH possibly present at low levels. As with the carcinogenic limit, whenever a detection exceeds 28.0 ng/l it serves to define the acceptable level in that case.

In summary, PAH criteria for potable water are proposed as follows:

Proposed PAH Criteria for Potable Water:

- (1) For each PAH compound designated as carcinogenic, the concentration must be less than 2.8 ng/l or the laboratory detection limit for the compound, whichever is greater;
- (2) for each PAH compound not designated as carcinogenic, the concentration must be less than 28.0 ng/l or the laboratory detection limit for the compound, whichever is greater.

The potable water criteria form the basis for acceptable levels of PAH in groundwater, soil, discharge to surface water, and discharge to sanitary sewer, as discussed in the following paragraphs.

Groundwater. The proposed criteria for groundwater are identical with those for potable water. Groundwater in the region is generally of excellent quality, and is widely and heavily used for drinking water.

Soil. The proposed criteria for soil are determined by multiplying the potable water criteria (2.8 ng/l and 28.0 ng/l, respectively, for carcinogenic and "other" PAH) by a Sorption Factor, which describes the tendency for a compound to be adsorbed by (i.e., adhere to) soil particles. The Sorption Factor is the ratio of adsorbed to dissolved concentrations of a compound at equilibrium; it is also called the "partition constant." Based on recent studies by J. C. Means et al. (1979, 1980), the Sorption Factor can exceed 30,000 for certain PAH compounds in certain soils, and a minimum value of 500 appears to be reasonable for the Sorption Factor for carcinogenic PAH. It is recommended that this value (500) be adopted unless more detailed information comes to light. This would imply soil PAH limits of 1,400 ng/kg for carcinogenic PAH, and 14,000 ng/kg for "other" PAH. As before, the detection limit would over-ride when it exceeds the stated limit.

The column studies by Professor Pfannkuch at the University of Minnesota currently being done for the Minnesota Department of Health and U.S. Geological Survey may provide useful information in refining the Sorption Factor. Alternatively, where the organic carbon content of soil is known or estimated, Means et al. (1980) have discovered a good relationship between a PAH compound's aqueous solubility, S, and a parameter (K_{oc}) closely akin to the Sorption Factor. The relationship with S is:

$$\log K_{oc} = -0.82 \log S + 4.07$$

and from K_{oc} and percent organic carbon content (% Org-C) of the soil, the Sorption Factor is determined by:

$$\text{Sorption Factor} = \frac{(K_{oc}) \times (\% \text{ Org-C})}{100}$$

A paper by Yalkowsky and Valvani (1979) gives additional information useful for determining Sorption Factor values.

Discharge to Surface Water. The proposed criteria for discharge to surface water are very strict, due to the possibility of bioconcentration in fish which may be consumed by humans. This will be illustrated by considering discharge to the Mississippi River.

In this case there is a critical population group in the Twin Cities which consumes large amounts of fish taken from the Mississippi River. The daily intake of river fish may be on the order of one pound (0.4536 kg) for members of this group. The ingestion rate of a particular PAH associated with this fish intake can be estimated for a hypothetical concentration of the PAH in the river water by the following formula:

$$\text{PAH Intake} = (0.4536 \text{ kg/day}) \times \text{BF} \times C_w$$

in which C_w = river water concentration of the PAH, and BF = bioconcentration factor (ratio of PAH concentration in organism - in this case, fish - to concentration in water, following period of equilibration).

Various investigators have found bioconcentration factors of 500 (Southworth, 1977; for anthracene with fathead minnows) and 900 (Lu et al., 1977, cited on page B-1 of the EPA October 1980 Criteria document; for BaP with mosquitofish). The evidence is scant, but a value of 700 appears reasonably typical for BF in the above formula. *bioaccumulation factor*

The river water concentration, C_w , which results in a daily PAH intake equal to that in drinking water, at its limiting concentration, can now be determined. For a particular carcinogenic PAH in drinking water, consumption of two liters per day at the limiting concentration of 2.8 ng/l implies a daily intake of 5.6 ng. Substituting this in the previously given formula (along with BF = 700),

$$5.6 \text{ ng/day} = (0.4536 \text{ kg/day}) \times 700 \times C_w$$

and solving for C_w yields a river concentration of 0.018 ng/l. (Note 1 l. water has mass 1 kg.) This limit is less than one hundredth that for drinking water.

Allowance could be made for dilution in the case of discharge to the river. The daily low flow of record for the Mississippi River in the metropolitan area appears to have occurred at Lock and Dam Number 1 on September 1, 1976. (Special river studies were carried out cooperatively by the U.S. Geological Survey with local agencies during the drought period in 1976.) The measured stream-flow was 219 cubic feet per second.

Gradient control wells in the shallower aquifers in St. Louis Park (i.e., excluding the Prairie du Chien-Jordan and deeper aquifers, from which pumped water is likely to be treated and used as water supply) may produce a total flow on the order of 800 gallons per minute, or 1.8 cubic feet per second.

The resulting dilution factor (219/1.8) is 122, and applying this to the river concentration limit of 0.018 ng/l yields an allowable effluent concentration of 2.2 ng/l. This is roughly equal to the drinking water limit.

To sum up, discharge to the Mississippi River is severely constrained by the possibility of PAH bioconcentration. In fact, under the assumption that a critical population group consumes one pound of Mississippi fish per person daily, the effluent quality would need to be comparable to drinking water.

Note that smaller dilution factors will result for other surface waters in the area. Minnehaha Creek, for example, exhibits zero flow occasionally. This implies a dilution factor of unity. Thus, discharge to the Creek could possibly need to be of much higher quality than drinking water.

The criteria proposed for discharge to surface water therefore depend on characteristics of the receiving water. For discharge to the Mississippi River, it is proposed to adopt the potable water criteria, since these approximate the results of the analysis above. Specific criteria are not proposed at present for other receiving waters.

Discharge to Sanitary Sewer. The criteria for discharge to sanitary sewer are intended to insure that the Metropolitan Wastewater Treatment Plant at Pig's Eye meets the criteria for surface water discharge to the Mississippi River. For this purpose, the potable water criteria are multiplied by a Dilution Factor.

This factor is the ratio of total wastewater flow at Pig's Eye to the total pumpage from gradient control wells discharging to the sewer. The total wastewater flow is on the order of 200 million gallons per day, and total pumpage from the shallower control wells, again, is likely to be about 800 gallons per minute (1.2 million gallons per day).

The resulting Dilution Factor is then approximately 167. This implies concentration limits of 468 ng/l for each carcinogenic PAH, and 4,680 ng/l for other individual PAH compounds. These are representative numbers, based on approximate or preliminary estimates of flow. And again, the detection limit would define the acceptable level for a compound whenever it exceeds the specified limits.

Summary. Table 2 - Proposed Environmental PAH Criteria, summarizes the above discussion. Note once again that the EPA criteria are the primary basis for the proposed criteria. Also, the detection limit in a given case serves as the acceptable level whenever the detection limit exceeds the limit derived from EPA criteria.

002622

TABLE 2 - PROPOSED ENVIRONMENTAL PAH CRITERIA

GROUNDWATER: (1) For each PAH compound designated as carcinogenic, the concentration must be less than 2.8 ng/l or the laboratory detection limit for the compound, whichever is greater; (2) for each PAH compound not designated as carcinogenic, the concentration must be less than 28.0 ng/l or the detection limit for the compound, whichever is greater.

SOIL: (1) For each PAH compound designated as carcinogenic, the concentration must be less than 2.8 ng/kg multiplied by a Sorption Factor, or the detection limit for the compound, whichever is greater; (2) for each PAH compound not designated as carcinogenic, the concentration must be less than 28.0 ng/kg multiplied by a Sorption Factor, or the detection limit for the compound, whichever is greater. (See text for discussion of Sorption Factor.)

DISCHARGE TO SURFACE WATER: For discharge to the Mississippi River, the proposed criteria are identical with those for groundwater. (See text for discussion.)

DISCHARGE TO SANITARY SEWER: (1) For each PAH compound designated as carcinogenic, the concentration must be less than 2.8 ng/l multiplied by a Dilution Factor, or the detection limit for the compound, whichever is greater; (2) for each PAH compound not designated as carcinogenic, the concentration must be less than 28.0 ng/l multiplied by a Dilution Factor, or the detection limit, whichever is greater. (See text for discussion of Dilution Factor.)

	<u>g.w.</u>	<u>soil</u>	<u>river</u>	<u>sanitary</u>
each carcinogenic PAH	2.8 ng/l	2.8 ng/kg	2.8 ng/l	2.8 x dilution factor = 468 ng/l
each non-carc. PAH	28 ng/l	28	28 ng/l	28 x dilution factor = 4680

IV. BRIEF BIBLIOGRAPHY

The following relate directly to the above discussion of criteria. Other background documents appear in the annotated bibliography comprising the final section of this memorandum.

1. World Health Organization (1971), 3rd Ed. International Standard for Drinking Water, Geneva.
2. U. S. Environmental Protection Agency (July 14, 1980), "The Carcinogen Assessment Group's List of Carcinogens," 25 pp.
3. U. S. Environmental Protection Agency (October 1980), "Ambient Water Quality Criteria for Polynuclear Aromatic Hydrocarbons," Wash., D.C., 199 pp.
4. Means, J. C., J. J. Hassett, S. G. Wood and W. L. Banwart (1979), "Sorption Properties of Energy-Related Pollutants and Sediments," in Jones and Leber, ed., Polynuclear Aromatic Hydrocarbons, Third International Symposium on Chemistry and Biology - Carcinogenesis and Mutagenesis, Ann Arbor Science, Ann Arbor, pp. 327-340.
5. Means, J. C., S. G. Wood, J. J. Hassett and W. L. Banwart (December 1980), "Sorption of Polynuclear Aromatic Hydrocarbons by Sediments and Soils," Environmental Science and Technology, vol. 14, no. 12, pp. 1524-1528.

V. ANNOTATED BIBLIOGRAPHY

The references listed here are organized under the following headings:

- A. EPA Documents
- B. Levels in Drinking Water
- C. Environmental Levels and Sources
- D. Sorption
- E. Environmental Fate
- F. Hazard and Risk
- G. Case Studies
- H. Measurement

To avoid confusion, the numbering of references is continuous throughout.

A. EPA DOCUMENTS

1. U.S. Environmental Protection Agency (July 14, 1980), "The Carcinogen Assessment Groups' List of Carcinogens".

Lists "chemical substances for which substantial or strong evidence exists showing that exposure to these chemicals, under certain conditions, causes cancer in humans, or can cause cancer in animal species which in turn, makes them potentially carcinogenic in humans." Information sources were International Agency for Research on Cancer, National Toxicology Program (formerly National Cancer Institute Bioassay Program), Food and Drug Administration, and previous evaluations by EPA's Carcinogen Assessment Group.

2. U.S. EPA (October, 1980), "Ambient Water Quality Criteria for Polynuclear Aromatic Hydrocarbons", Washington D.C.

Proposes PAH water quality criteria (intended for surface waters) and thoroughly reviews pertinent information. The information review covers PAH levels in drinking water, food and the environment, as well as human health effects and toxicity to aquatic organisms. The proposed criteria, however, are ambiguous. On Page C-180 (under "Summary of Pertinent Data" in the appendix) the document clearly implies that a criterion is given only for benzo(a)pyrene (BaP):

"The water quality criterion for BaP is based on the experiment reported by Neal and Rigdon (1967)... ..The result is that the water concentration of baP should be less than 28 ng/l in order to keep the individual lifetime risk below 10^{-5} . It is recognized that numerous carcinogenic PAH other than BaP are found in water. However, there is probably little need to derive criteria for all such PAH, since efforts to reduce BaP levels to within acceptable limits will result in the reduction of all PAH."

But on the preceding page (Page C-179, under "Summary and Conclusion Regarding the Carcinogenicity of Polynuclear Aromatic Hydrocarbons (PAH)" in the appendix), the document presents the same numerical criterion as applicable to the sum of carcinogenic PAH:

"The water quality criterion for carcinogenic PAH compounds is based on the assumption that each compound is as potent as BaP and that the carcinogenic effect of the compounds is proportional to the sum of their concentrations. Based on an oral feeding study of BaP in mice, the concentration of BaP estimated to result in a lifetime risk of 10^{-5} is 28 ng/l. Therefore, with the assumption above, the sum of concentrations of all carcinogenic PAH compounds should be less than 28 ng/l in order to keep the lifetime cancer risk below 10^{-5} ."

And finally, on the report's very first page of text (page vi, which is headed "Criteria Document"), the document gives numerically equivalent criteria for, simply, "polynuclear aromatic hydrocarbons" - which seems to mean the sum of all PAH:

"For the maximum protection of human health from the potential carcinogenic effects due to exposure of polynuclear aromatic hydrocarbons through ingestion of contaminated water and contaminated aquatic organisms, the ambient water concentration should be zero based on the non-threshold assumption for this chemical. However, zero level may not be attainable at the present time. Therefore, the levels which may result in incremental increase of cancer risk over the lifetime are estimated at 10^{-5} , 10^{-6} , and 10^{-7} . The corresponding recommended criteria are 28.0 ng/l, 2.8 ng/l, and 0.28 ng/l, respectively.

The EPA document nowhere compares the merits of these three different interpretations.

3. Sorrell, R. K., H. J. Brass and R. Reding (date unknown), "A Review of Occurrences and Treatment of Polynuclear Aromatic Hydrocarbons", U.S. EPA Cincinnati.

Literature review of PAH contamination of raw, finished and distributed drinking waters. Included are PAH concentrations measured in ground and surface waters in Germany, surface waters in the Soviet Union and England, and in raw and treated drinking water supplies of 24 cities throughout the U.S. "Concentrations of PAH's in drinking water sources range from nanogram to microgram-per-liter quantities", states the report. Effectiveness of treatment processes is also reviewed.

4. U.S. EPA (date unknown), "Listing Background Document - Wood Preserving".

For wood preserving processes that use creosote or pentachlorophenol, this document states: "The Administrator [of EPA] has determined that wastewater from these wood preserving processes and the resulting bottom sediment sludges from wastewater treatment are solid wastes that may pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, disposed of or otherwise managed, and therefore should be subject to appropriate management requirements under Subtitle C of RCRA." The document supports this conclusion with data and responds to comments from the wood preserving industry on an earlier version of the listing.

B. LEVELS IN DRINKING WATER

(Note that references 2 and 3 contain additional information in this category.)

5. Basu, D. K. and J. Saxena (1978), "Polynuclear Aromatic Hydrocarbons in Selected U.S. Drinking Waters and Their Raw Water Sources," Environ. Sci. Technol., Vol. 12, No. 7.

Detected PAH in ng/l range in all raw and treated waters from 10 eastern U.S. water supplies.

6. Benoit, F. M., G. L. Lebel and D. T. Williams (1979), "Polycyclic Aromatic Hydrocarbon Levels in Eastern Ontario Drinking Waters, 1978," B. Env. Contam. & Tox., Vol. 23, No. 6

Concentrations of individual, low-molecular-weight PAH ranged from 0.04 - 6.4 ng/l in treated waters and from 0.1 - 34.4 ng/l in raw waters, for five eastern Ontario municipal water supplies.

7. Quaghebeur, D. and E. DeWulf (1978), "Polynuclear Aromatic Hydrocarbons in the Main Belgian Aquifers," Science of the Total Env., Vol. 10, No. 33.

Low concentrations of PAH were found in the aquifers of the six main geological formations in Belgium, where groundwater accounts for 65 percent of drinking water supply.

C. ENVIRONMENTAL LEVELS AND SOURCES

8. Borneff, J. and H. Kunte (1967), "Carcinogens in Water and Soil. XIX. Effect of Sewage Purification on Polycyclic Aromatic Compounds," translated by H. Tobias from Arch. Hyg. Bakteriol., 151.

Finds that sewage from households and industry, as well as street runoff, contains considerable quantities of PAH. Sewage treatment reduces carcinogenic PAH (primary settling to about half, activated sludge to ambient river water levels).

9. Blumer, M. and W. W. Youngblood (1975), "Polycyclic Aromatic Hydrocarbons in Soils and Recent Sediments," Science, Vol. 188.

Finds that soils and recent marine sediments contain a variety of PAH. In a wide range of depositional environments, the series of alkyl homologs of the PAH are highly similar in molecular weight distribution. The evidence suggests that natural fires produce the PAH, and air movement mixes and disperses them prior to deposition.

10. Blumer, M. (1975), "Curtisite, Idrialite and Pendletonite, Polycyclic Aromatic Hydrocarbon Minerals. Their Composition and Origin," Chemical Geology, 16.

Analysis of these "rare polycyclic aromatic hydrocarbon minerals" reveals the composition of pendletonite as nearly pure coronene, while that of the other minerals includes over 100 PAH and related compounds. The origin of these minerals is medium-temperature pyrolysis of organic matter.

11. Blumer, M., W. Blumer and T. Reich (1977), "Polycyclic Aromatic Hydrocarbons in Soils of a Mountain Valley: Correlation with Highway Traffic and Cancer Incidence," Environ. Sci. & Technol., Vol. 11, No. 12.

Soil PAH near a Swiss mountain tower correlated with proximity to a highway. PAH ranged from 300 mg/kg (dry soil) near the highway, to 4-8 mg/kg in the higher surrounding Alps. (Correlation with cancer is indirect.)

12. Davies, I. W., R. M. Harrison, R. Perry, D. Rathnayaka and R. A. Wellings (1976), "Municipal Incinerator as Source of Polynuclear Aromatic Hydrocarbons in Environment," Environ. Sci. & Technol., Vol. 10, No. 5.

Finds that incomplete combustion of municipal refuse in a continuous feed incinerator produced PAH. Ash waste, stack gases and wastewater from the incinerator plant all contained PAH.

13. Dunn, B. P. and J. Fee (1979), "Polycyclic Aromatic Hydrocarbon Carcinogens in Commercial Seafoods," Canadian J. Fisheries & Aquatic Sciences, Vol. 36, No. 12.

Wet weight concentrations of benzo(a)pyrene ranged from 0.8 - 7.9 ug/kg in commercial lobsters, and from below 10 - 36 ug/kg in other shellfish. Vertebrate fish not packed in vegetable oil contained no detectable BaP. For lobsters, creosote contamination during impoundment was implicated as a cause.

14. Faoro, R. B. and J. A. Manning (1981), "Trends in Benzo(a)pyrene, 1966-77," Journ. Air Poll. Control Assoc., Vol. 31, No. 1.

BaP concentrations in urban air have decreased from approximately 4.0 ng/cu m to less than 1.0 ng/cu m between 1966 and 1977 (averages for 26 U.S. cities). The decrease is primarily attributed to decreased use of coal for residential heating; open-burning bans and coke oven emission controls also contributed to the decrease. In 1975, BaP emissions in the U.S. were mainly accounted for by coke ovens (38%), wood burning for heat (25%), coal refuse fires (17%) and residential coal furnaces (9%).

15. Grimmer, G., H. Boehnke and A. Glaser (1977), "Polycyclische Aromatische Kohlenwasserstoffe Im Abgas Von Kraftfahrzeugen" [Polycyclic Aromatic Hydrocarbons in the Automotive Exhaust Gas], Erdoel Kohle Erdgas Petrochem Ver Brennst Chem, Vol. 30, No. 9.

PAH in car exhaust and fuel was investigated. Comparison reveals that most PAH in fuel is destroyed in combustion, while new and different PAH are produced in the same process.

16. Gubergrits, M. Ya. (1978), "Protection of the Environment from Carcinogenic Pollutants in the Thermal Processing of Solid Fuels," Solid Fuel Chem., Vol. 12, No. 5.

This Soviet study finds that thermal processing of solid fuels (shale and coal) produces substantial benzo(a)pyrene, mostly concentrated in the tar and tar waters. The initial fuels contain limited amount of BP.

17. Heit, M. (1979), "Concentrations of Benzo(a)Pyrene in the Sediments of Six Western United States Lakes," Water, Air, Soil Pollution, Vol. 11, No. 4.

Lake sediment concentrations of BaP ranged up to 305 ug/kg, found in a Los Angeles reservoir.

18. Hites, R. A., R. E. LaFlamme and J. W. Farrington (1977), "Sedimentary Polycyclic Aromatic Hydrocarbons: The Historical Record", Science, Vol. 189, P. 829.

Investigated PAH in dated sediment cores from Buzzards Bay, Mass. Some low-level background is thought to be from natural sources, but most of the sedimentary PAH appears to have come from fossil fuel combustion.

19. Shabad, L. M. and G. A. Smirnov (1972), "Aircraft Engines as a Source of Carcinogenic Pollution of the Environment [Benzo(a)pyrene Studies]," Atmos. Environ., Vol. 6, No. 3.

Soviet study finds that both piston and turbine aircraft engines produce BaP in exhaust and soot. Rate of BaP release is from 2-10 mg per minute for modern aircraft engines.

20. Williams, R. L. (1979), "Benzo(a)pyrene Emissions from Gasoline and Diesel Automobiles," SAE Preprint No. 790419 for Feb. 26 - Mar. 2 Meeting.

BaP emission averaged 2.7 ug per mile for diesel and gasoline cars without catalytic converters. Catalytic converters reduced BaP emission by over 95% for gas cars, but had no effect for diesel.

D. SORPTION

21. Herbes, S. E. (1977), "Partitioning of Polycyclic Aromatic Hydrocarbons Between Dissolved and Particulate Phases in Natural Waters", Water Research, Vol. 11, No. 6.

Investigates anthracene adsorption in suspensions of autoclaved yeast cells (a form of particulate organic matter). Sorption was over 10 times greater than that observed on mineral surfaces.

22. May, W. E. (1980), "The Solubility Behavior of Polycyclic Aromatic Hydrocarbons in Aqueous Systems", in L. Petrakis and F. T. Weiss, eds., Petroleum in the Marine Environment, American Chem. Soc., Wash. D.C.

Presents aqueous solubilities for 11 PAH and sorption data for four PAH on several artificial and natural media. Partition coefficients (ratios of concentrations adsorbed onto sediment medium to aqueous concentration at equilibrium) ranged from 1.6 - 159 for artificial media, and from 4.5 - 36 for two undescribed "Alaskan sediments."

23. Means, J. C., J. J. Hassett, S. G. Wood and W. L. Banwart (1979), "Sorption Properties of Energy-Related Pollutants and Sediments", in P. W. Jones and P. Leber, eds., Polynuclear Aromatic Hydrocarbons, Ann Arbor Science Publishers, Ann Arbor.

Reports sorption properties for two PAH on three different soil and lake sediment samples. Partition coefficients ranged from 70 - 12,000, and were proportional to organic carbon content of the soil/sediments. The octanol/water partition coefficient was in turn proportional to the partition coefficients normalized to organic carbon content.

24. Means, J. C., S. G. Wood, J. J. Hassett and W. L. Banwart (1980), "Sorption of Polynuclear Aromatic Hydrocarbons by Sediments and Soils", Environ. Sci. & Technol., Vol. 14, No. 12.

Partition coefficients (both unnormalized and normalized to soil/sediment organic carbon content) are reported for four PAH on 14 soils and sediments. Partition coefficients ranged from 70-56,000 but when normalized ranged from 44,000-6,400,000. The normalized coefficients were related to solubility as well as octanol/water partition coefficient.

25. Rogers, R. D., J. C. McFarlane and A. J. Cross (1980), "Adsorption and Desorption of Benzene in Two Soils and Montmorillinite Clay", Environ. Sci. & Technol., Vol. 14, No. 4.

Reports sorption properties of benzene [which is the basic unit of PAH compounds, and could be termed a "mononuclear aromatic hydrocarbon"]. Freundlich constants which essentially represented linear partition coefficients ranged from 1.8 - 31 for two soil and two clay samples. For the soils, partition coefficients normalized to organic carbon content were about 100. [These results conform to findings for PAH compounds that increasing molecular size and complexity are associated with increasing sorption.]

26. Yalkowsky, S. H. and S. C. Valvani (1979), "Solubilities and Partitioning - 2. Relationships Between Aqueous Solubilities, Partition Coefficients, and Molecular Surface Areas of Rigid Aromatic Hydrocarbons", J. Chem. Eng. Data, Vol. 24, No. 2.

This article presents a reliable equation for 31 PAH compounds, relating the octanol-water partition coefficient to "molecular surface area". A table of component surface areas also is given; this allows estimation of the above parameters for any PAH of known structure. [In conjunction with results in Ref. 24, this allows prediction for any known PAH of soil partition coefficient, normalized to organic carbon content.]

E. ENVIRONMENTAL FATE

27. Carlson, R. M., A. R. Oyler, E. H. Gerhart, R. Caple and K. J. Welch (1979), "Implications to the Aquatic Environment of Polynuclear Aromatic Hydrocarbons Liberated from Northern Great Plains Coal", EPA/600/3-79/093.

Reports bioaccumulation factors of 1,000 - 5,000 for several PAH.

28. Cerniglia, C. E. and D. T. Gibson (1977), "Aromatic Hydrocarbons: Degradation by Bacteria and Fungi", American Chem. Soc., Div. Fuel Chem., Preprint Vol 22, No. 3., Wash., D.C.

Reports investigations on microbial degradation of naphthalene. The fungus Cunninghamella elegans and two Pseudomonas bacteria species were found to metabolize naphthalene.

29. Dean-Raymond, D. and R. Bartha (1975), "Biodegradation of Some Polynuclear Aromatic Petroleum Components by Marine Bacteria", NTIS Report AD/A-006 346.

Finds six bacterial strains (isolated from an oil-polluted estuary) able to metabolize naphthalene and some alkyl homologs. One strain could also metabolize acenaphthylene, biphenyl, fluorene and tetralin.

30. Gardner, W. S., R. F. Lee, K. Tenore and L. Smith (1978), "Degradation of Selected Polycyclic Aromatic Hydrocarbons in Coastal Sediments: Importance of Microbes and Polychaete Worms," Water, Air and Soil Poll., Vol 11.

Finds significant microbial degradation of several PAH in laboratory experiments with fine sand and medium sand sediments. The benthic polychaete, Capitella capitata, stimulated degradation. Microbial degradation was more rapid near the sediment surface than at greater depths. In marsh sediment, PAH degradation was minimal. [Evidence here points to aerobic degradation.]

31. Katz, M. and D. A. Lane (1975), "Photomodification of Benzo(a)pyrene Under Simulated Atmospheric Conditions", Amer. Chem. Soc., Div. Environ. Chem., Preprint Vol. 15, No. 1.

Photodecomposition of BaP occurred with half-life of 5.3 hr. in clean air, and 0.10 hr. in air with 2.0 ppm ozone. [These correspond to 99% reductions each 35 hr. and 0.7 hr., respectively.]

32. Lee, R. F., W. S. Gardner, J. W. Anderson, J. W. Blaylock and J. Barwell-Clarke (1978), "Fate of Polycyclic Aromatic Hydrocarbons in Controlled Ecosystem Enclosures", Environ. Sci. & Technol. Vol. 12, No. 7.

Studies of ecosystem enclosures suspended in a coastal inlet demonstrated exponential decrease of six PAH, due to several mechanisms. Microbial degradation appeared significant only for naphthalene (with removal rates up to 5% per day). Higher molecular weight PAH are mainly associated with particulates. Sedimentation and photochemical oxidation are the major processes affecting the aqueous concentrations of the higher molecular weight PAH.

33. MacKenzie, M. J. and J. V. Hunter (1979), "Sources and Fates of Aromatic Compounds in Urban Stormwater Runoff", Environ. Sci. & Technol., Vol. 13, No. 2

PAH in urban runoff was found most likely to originate from crankcase oil, based on comparison of hydrocarbon and sulfur fractions.

34. Southworth, G. R. (1977), "Transport and Transformations of Anthracene in Natural Waters: Process Rate Studies", in L. L. Marking and R. A. Kimerle, eds., Aquatic Toxicology (Proceedings of 2nd Annual Symposium), Amer. Soc. for Testing and Materials, Philadelphia.

Investigates removal of anthracene from water by processes of volatilization, adsorption to bed, photolysis, microbial degradation and sedimentation. First-order rate constants were developed for these processes through laboratory studies. For combined processes, estimated half-lives ranged from 1.4 - 21.6 hr. for various flowing water environments. Microbial degradation dominates removal in slow-moving streams, while photolysis and volatilization become more important in shallow, fast clear water. Bioaccumulation factors of roughly 1,000 and 500 were found for the zooplankter Daphnia and fathead minnows, respectively.

F. HAZARD AND RISK

35. Dacre, J. C., D. H. Rosenblatt and D. R. Cogley (1980), "Preliminary Pollutant Limit Values for Human Health Effects", Environ. Sci. & Technol., Vol. 14, No. 7.

Presents a method for determining allowable pollutant levels in soil, based on acceptable daily intake by humans. The article suggests analysis of human exposure pathways and use of partition coefficients and other factors as appropriate.

36. Hervin, R. L. and E. A. Emmett (1976), "Health Hazard Evaluation/Toxicity Determination Report 75-194-324, Western Roofing Co., A. J. Shirk Roofing Co., Quality Roofing Co., Kansas City, Missouri", Nat. Inst. Occup. Safety and Health, Cincinnati.

Results of NIOSH medical-environmental evaluation. Workers were exposed to toxic concentrations of particulate PAH during the tear-off a 7-acre roof. Skin photosensitivity attributed to PAH exposure was found in 71% of the roofers, and conjunctivitis similarly in 65%.

37. Lynn, W. R. (1981), "What Scientists Really Mean by 'Acceptable Risk'", U.S. News & World Report, March 30, 1981.

Interesting discussion of risk, with focus on catastrophes such as occurred at Three Mile Island. Lynn makes the point that, "How safe is safe is a value judgement", and he observes that scientists and technologists have often made such judgements "because nobody else is prepared to do it".

38. Markel, H. L. Jr., R. N. Ligo and J. B. Lucas (1977), "Health Hazard Evaluation/Toxicity Determination Report 75-117-372, Koopers Co., Inc., North Little Rock, Arkansas", NIOSH, Cincinnati

Investigation at wood treating operation revealed potentially toxic PAH concentrations in air. Several cases of skin and eye irritations were attributed to creosote exposure.

39. NIOSH (1980), "Health Hazard Evaluation Determination Report HE-79-43-663, Harbison-Walker Refractories, Clearfield, Pennsylvania", Cincinnati.

Investigation of creosote exposure. PAH were detected in "personal air samples" and were recognized as potentially carcinogenic or co-carcinogenic. NIOSH recommends controlling exposure "to the lowest reliable analytical detection level."

40. van Rensburg, J. F. J., A. Hassett, S. Theron and S. G. Wiechers (1981), "The Fate of Organic Micropollutants Through an Integrated Wastewater Treatment/Water Reclamation System," Municipal Wastewater Reuse News (AWWA Research Foundation), No. 42.

Evaluation of an integrated pilot plant's capability to produce water of potable quality. In this South African study, "lower hazard limits" were set at 100 ng/l per compound for several carcinogenic PAH, at 1,000 ng/l for several non-carcinogenic PAH, and at various levels for other pollutants. The "modified lime flotation biological" plant produced effluent with no PAH exceeding the hazard limits, and the effluent quality is said to be superior to water supplies of Port Elizabeth, Cape Town and Pretoria.

G. CASE STUDIES

41. McCann, D.L. (1978), "Ground Water Quality Conditions During the Year 1977 at the S.C.E.

002635

Visalia Pole Yard, Visalia, California", prepared by LeRoy Crandall and Assoc. for Southern Calif. Edison Co.

Annual report on groundwater conditions in the vicinity of a pole yard where creosote and pentachlorophenol contamination has occurred. Shallow monitoring wells and deeper municipal wells nearby were monitored: concentrations of pentachlorophenol and of "creosote" ranged, respectively, from 1,700 - 44,000,000 ug/l and from 3,000 - 41,000,000 ug/l in shallow, on-site wells; and for municipal wells, penta was detected in 50% of samples, ranging from 0.1 - 0.2 ug/l, and "creosote" was not detected. During the year reported, a subsurface bentonite-cement cutoff wall was completed around the pole yard (approximately 1,700 lineal feet) down into an underlying silt-clay aquitard (approximately 60 feet deep). Pumpout wells were used and in 1977 produced 531,000 gallons from the shallow aquifer (with maximum penta and "creosote" concentrations of 3,100,000 ug/l and 11,000,000 ug/l, respectively) and 5,000,000 gallons from the deeper, confined aquifer (with average penta about 3,500 ug/l and "creosote" concentrations "generally less than" 7,000 ug/l). All contaminated water was discharged to the Visalia Sewerage System.

42. Thompson, G. E. (1978), "Hydrogeological Control and Clean-Up of Soil and Groundwater Contaminants at Northern Wood Preservers, Ltd.," Proceedings of 25th Ontario Indust. Waste Conf., Ontario Ministry of the Environment, Ottawa.

Report on creosote contamination at plant adjacent to Thunder Bay, Lake Superior. Major portion of spilled materials (mainly creosote, also some chromated copper arsenate and pentachlorophenol) has infiltrated into the ground and is moving laterally into the lake. Remedies have included dredging adjacent portions of the lake. Further plans included barrier or pumpout wells, with effluent treatment by ozonation and activated carbon.

H. MEASUREMENT

(The following list, far from complete, is merely suggestive of the literature concerning PAH measurement technique and detection limits.)

43. Acheson, M. A., R. M. Harrison, R. Perry and K. A. Wellings (1976), "Factors Affecting the Extraction and Analysis of Polynuclear Aromatic Hydrocarbons in Water", Water Research, Vol. 10, No. 3

Investigated effects of initial PAH concentration, presence of suspended solids, prolonged sample storage and other factors affecting measurement. Extraction efficiencies ranged from 30-85%.

44. Bishop, D. F. (1980), "Project Summary, GC/MS Methodology for Measuring Priority Organics in Municipal Wastewater Treatment", U.S. EPA, Municipal Environmental Research Laboratory, Cincinnati.

Summarizes EPA methods and limitations for measuring priority organics including certain PAH in municipal wastewaters and sludges. Detection limits are generally stated as ranging from less than 1 - 25 ug/l. Quality control limits for percent recovery were plus-or-minus three standard deviations; it was observed that for many compounds these limits ranged from zero to several hundred percent. [Municipal wastewaters and sludges are especially prone to analytical interferences.]

45. Bolger, J. J., of Environmental Research Group, Inc. (December 2, 1980), letter regarding PAH determination in wastewaters, (accompanying letter from O. C. Braids, Geraghty & Miller, Inc., to J. Erdmann, E. A. Hickok and Associates, dated January 27, 1981.)

Discusses PAH detection limits and reports opinions of Dr. Frank Hammer, head of ERG's Organic Chemistry Department. Dr. Hammer notes that the Minnesota Department of Health's procedure for PAH determination differs slightly from U.S. EPA procedures (published December 3, 1979 in the Federal Register) "and may provide better detection limits". Dr. Hammer could not judge the validity of MDH detection limits as low as 10 ng/l without running a series of analyses using the MDH procedure. [Note that the cited EPA procedures give detection limits by HPLC for 16 PAH ranging from 40 - 5,000 ng/l (considering for each compound only the better of the UV or fluorescence detection limits).]

46. Drew, S. R., of Energy Resources Co., Inc. (November 3, 1980), letter regarding PAH determination, (accompanying letter from A. J. Barber, Geraghty & Miller, Inc., to J. Erdmann, E. A. Hickok and Associates, dated November 6, 1980).

Notes non-EPA approved methods for determining PAH down to the 1 - 10 ng/l level by high performance liquid chromatography. Energy Resources Co.'s lab, using gas chromatography - mass spectrometry, would have PAH detection limits in the 10 - 100 ng/l range, depending on the compound.

47. Hilpert, L. R., W. E. May, S. A. Wise, S. N. Chesler and H. S. Hertz (1978), "Interlaboratory Comparison of Determinations of Trace Level Petroleum Hydrocarbons in Marine Sediments," Anal. Chem., Vol. 50, No. 3

This National Bureau of Standards report compares hydrocarbon determinations in marine sediments by eight laboratories. The scatter of results for PAH compounds (four rings and larger) was typically three orders of magnitude. Determinations were in the ug/kg range.

48. Josephson, J. (1981), "Polynuclear Aromatic Hydrocarbons", Environ. Sci. & Technol., Vol. 15, No. 1.

Article highlights the Fifth International Symposium on Polynuclear Aromatic Hydrocarbons. Advances in PAH detection and analysis, allowing sub-part per billion determinations, are repeatedly noted.

49. Kadar, R., K. Nagy and D. Fremstad (1980), "Determination of Polycyclic Aromatic Hydrocarbons in Industrial Waste Water at the ng/ml Level", Talanta, Vol. 27, pp. 227-230.

Describes combination of column, thin-layer and capillary gas chromatography for PAH determination. From reported data, detection limits were evidently 1 ug/l for several PAH. [Note that 1 ng/ml = 1 ug/l.]

50. Keith, L. H., of Radian Corp. (October 21, 1980), letter regarding PAH detection limits, (accompanying letter from O. C. Braids, Geraghty & Miller, Inc., to J. Erdmann, E. A. Hickok and Associates, dated November 26, 1980).

Notes that detection limits for PAH in 2-liter drinking water samples, concentrated by factor of 2,000, may range from 1 - 40 ug/l using GC-MS. Use of selected ion monitoring can lower the range of detection limits to 100 - 4,000 ng/l (i.e., 0.1 - 4 ug/l). Detection limits can be lowered further yet, to 10 - 500 ng/l range, if capillary GC-MS with selected ion monitoring is used under non-routine conditions, and there are no interferences.

51. Ogan, K., E. Katz and W. Slavin (1978), "Concentration and Determination of Trace Amounts of Several Polycyclic Aromatic Hydrocarbons in Aqueous Samples", J. Chromatogr. Sci., Vol 16, No. 11.

Reports preliminary method of PAH determination in drinking water, using reversed phase liquid chromatography and fluorescence detection. Specific compounds were recovered quantitatively at levels below 10 ng/l.

52. Ogan, K., E. Katz and W. Slavin (1979), "Determination of Polycyclic Aromatic Hydrocarbons in Aqueous Samples by Reversed-Phase Liquid Chromatography," Anal. Chem., Vol. 51, No. 8.

Describes additional work beyond that in Ref. 51. The technique is applied to 16 PAH (of which 15 are on the EPA Priority Pollutant list) in environmental water samples. Several compounds were quantitated at concentrations below 10 ng/l in the original sample.

53. Oyler, A. R., D. L. Bodenner, K. J. Welch, R. J. Liukkonen, R. M. Carlson, H. L. Kopperman and R. Caple (1978), "Determination of Aqueous Chlorination Reaction Products of Polynuclear Aromatic Hydrocarbons by Reversed Phase High Performance Liquid Chromatography - Gas Chromatography", Anal. Chem., Vol. 50, No. 7.

Reports on "a convenient procedure" combining liquid and gas chromatography with a reverse-phase setup. The procedure quantitates PAH in water at the ng/l to ug/l level.

54. Richardson, J. H. and M. E. Ando (1977), "Sub-Part-Per-Trillion Detection of Polycyclic Aromatic Hydrocarbons by Laser Induced Molecular Fluorescence", Anal. Chem., Vol. 49, No. 7.

Reports very low PAH detection limits using laser-induced molecular fluorescence. All PAH fluorescence was found to depend linearly on concentration, in some cases over six orders of magnitude. Reported detection limits for four PAH range from 0.5 - 4.4 ng/l.

55. Robertson, D. J., R. H. Groth, D. G. Gardner and L. G. Glastris (1979), "Interferences from Filters and Solvents in PNA Analysis by High Performance Liquid Chromatography", J. Air Pollut. Control Assoc., Vol. 29, No. 2.

Reports that PAH are present in most readily available filter media and in solvents used to extract the filters in PAH analysis. The interfering PAH can be detected in solvent samples after concentrating by 50 - 100 x or after extracting an unused filter.

56. Snook, M. E., R. F. Severson, H. C. Higman, R. F. Arrendale and O. T. Chortyk (1979), "Methods for Characterization of Complex Mixtures of Polynuclear Aromatic Hydrocarbons," in P. W. Jones and P. Leber, eds., Polynuclear Aromatic Hydrocarbons, Ann Arbor Science Publishers, Ann Arbor.

Reports on a gel filtration chromatographic technique used in combination with HPLC and GC-MS to characterize complex mixtures of PAH in cigarette smoke condensate. The article notes that almost 1,000 different PAH have been identified in cigarette smoke condensate.

Jaun

ADMIN. 1000A

STATE OF MINNESOTA

Office Memorandum

DEPARTMENT Health

TO : *Jim Pankanian*
U.S.E.P.A. - Region 5
Enforcement Division
230 S. Dearborn ~~Highway~~ Street
FROM : *Chicago, Illinois 60604*

DATE: *5/27/81*

SUBJECT: *Mike Conroy*
Fourth Hickok Work Report : Gradient Control Wells.

I am forwarding to you for your information and review a copy of Hickok's report on Gradient Control Wells. Please return your comments to me by June 10, 1981

*received
6-1/81
source of plane info.
how about reingestion?*

002583

MEMORANDUM NO. G18-4

DATE: MAY 21, 1981

TITLE: ST. LOUIS PARK GROUNDWATER CONTAMINATION STUDY
CONCEPTUAL ANALYSIS AND DESIGN OF GRADIENT
CONTROL WELL SYSTEM

ABSTRACT: THIS MEMORANDUM AND THE ACCOMPANYING REPORT PRESENT A CONCEPTUAL ANALYSIS AND DESIGN OF A GRADIENT CONTROL WELL SYSTEM FOR CONTAINING GROUNDWATER CONTAMINATION FROM THE FORMER REPUBLIC CREOSOTE SITE IN ST. LOUIS PARK, MINNESOTA. EXISTING WATER SUPPLY WELLS CAN BE USED TO CONTROL CONTAMINANTS IN THE PRAIRIE DU CHIEN-JORDAN AQUIFER. DEEPER AQUIFERS ARE NOT BELIEVED TO REQUIRE GRADIENT CONTROL WELLS, HOWEVER MULTI-AQUIFER WELLS PENETRATING THESE AQUIFERS MUST BE SEALED. FOR THE SHALLOWER AQUIFERS, FIVE WELLS PUMPING APPROXIMATELY 800 GALLONS PER MINUTE CAN CONTROL CONTAMINANT MOVEMENT. CONSTRUCTION COSTS FOR THESE WELLS IS ESTIMATED TO BE APPROXIMATELY \$75,000 NOT INCLUDING TREATMENT OR OPERATING COSTS. THIS MEMORANDUM AND THE ACCOMPANYING REPORT REPRESENT COMPLETION OF TASKS 2010 AND 2030 OF THE REFERENCED PROJECT.

EUGENE A. HICKOX & ASSOCIATES
HYDROLOGISTS-ENGINEERS-545 HUNAN AVENUE, WAXZATA, MINNESOTA 55391

EUGENE A. HICKOX & ASSOCIATES
HYDROLOGISTS-ENGINEERS-545 HUNAN AVENUE, WAXZATA, MINNESOTA 55391



CONCEPTUAL ANALYSIS AND DESIGN OF GRADIENT CONTROL WELL SYSTEM

This memorandum and the accompanying report present an analysis of gradient control wells to contain groundwater contamination from the former Republic Creosote site in St. Louis Park. The analysis may be refined as further hydrogeologic data, and perhaps a computer model, become available over the next few months.

The accompanying report describes the analytical approach and identifies and evaluates control alternatives for each aquifer. Included is each aquifer from the drift to the Mt. Simon-Hinckley, approximately 1,000 feet deep. This memorandum summarizes the alternatives and gives estimated well construction costs.

Table A - Summary of Gradient Control Alternatives, shows the key results of the analysis. Contaminant movement in the shallower aquifers (Middle Drift, Platteville and St. Peter) can be contained using five wells pumping a total of approximately 800 gallons per minute, or 1.15 million gallons daily. (Last alternative for each aquifer.) The estimated well construction costs for this total approximately \$75,000. This total does not include treatment facilities or any operating costs.

For the Prairie du Chien-Jordan aquifer, the analysis considered only existing water supply wells as possible controls. Alternatives for this aquifer therefore do not have associated well construction costs. Contaminant movement in the Prairie du Chien-Jordan aquifer can be contained by increasing the pumpage of several existing wells (alternative 5). These include municipal wells SLP-15 (St. Louis Park) and H-3 (Hopkins), which have been shut down due to high PAH levels.

The total pumpage to control contaminant movement in the Prairie du Chien-Jordan aquifer is shown in Table A as 9.3 million gallons per day. This includes a substantial amount of pumpage (primarily from the pumping "centers" CP-A through CP-D) currently used for municipal water supply, without special treatment, in St. Louis Park, Hopkins and Edina. Out of the pumpage total (9.3 mgd), at least 2 mgd (for SLP-15 and H-3), and perhaps some greater amount, will require special treatment to reduce PAH levels. The amount which will require special treatment depends on the PAH criteria adopted.

Contamination of the deeper aquifers (Ironton-Galesville and Mt. Simon-Hinckley) is believed to be minor. Multi-aquifer wells reaching these aquifers must be sealed to prevent any further contamination there. Gradient control wells are probably not necessary in the deeper aquifers and have not been designed.

TABLE A - SUMMARY OF GRADIENT CONTROL ALTERNATIVES

Aquifer	Alternative	Gradient Control Wells			Total Pumpage	Resulting Contaminant Movement	Well Construction Cost
		Designation	Number	@ Rate			
Middle Drift	1	RW5 & RW6	2	100 gpm	200 gpm	East @ 107 ft/yr	\$17,800
	2	RW3 & RW4	2	100 gpm	200 gpm	East @ 104 ft/yr	\$17,800
	3	RW1 & RW2	2	100 gpm	200 gpm	Contained	\$17,800
Platteville	1	RW1 & RW2*	2	100 gpm	200 gpm	East @ 355 ft/yr	Not estimated
	2	Control via Middle Drift & St. Peter Wells				Contained	0
St. Peter	1	SLP-1,2,3	1	400 gpm	400 gpm	East @ 89 ft/yr	\$21,700
	2	RW1 & SLP-1,2,3	2	200 gpm	400 gpm	East @ 83 ft/yr	\$38,200
	3	R-1, R-2 & R-3	3	200 gpm	600 gpm	Contained	\$57,300
Prairie du Chien-Jordan	1	CP-A,CP-B CP-C & CP-D	4	6 mgd	6 mgd	East @ 45 ft/yr	0**
	2	CP-A,CP-B CP-C & CP-D	4	6 mgd	7 mgd	Similar to Alt. 1	0
		SLP-15	1	1 mgd			
	3	CP-A,CP-B CP-C & CP-D	4	6 mgd	9 mgd	Southeast @ 7 ft/yr	0
		CP-C & CP-D		"Centers"(total)			
		SLP-15,SLP-6 & E-7	3	1 mgd			
	4	CP-A,CP-B CP-C & CP-D	4	6 mgd	8.5 mgd	Northeast @ 14 ft/yr	0
		CP-C & CP-D		"Centers"(total)			
		SLP-15,SLP-6 H-3	2 1	1 mgd 0.5 mgd			

002586

<u>Aquifer</u>	<u>Alterna- tive</u>	<u>Gradient Control Wells</u>			<u>Total Pumpage</u>	<u>Resulting Contam- inant Movement</u>	<u>Well Construction Cost</u>
		<u>Designation</u>	<u>Number</u>	<u>@ Rate</u>			
	5	CP-A, CP-B CP-C & CP-D	4	6 mgd "Centers"(total)			
		SLP-15 & H-3 SLP-6	2 1	1 mgd 1.3 mgd	9.3 mgd	Contained	0
Iron-ton- Galesville	-	Seal multi-aquifer wells				Unknown, but believed minor	-
Mt. Simon- Hinckley	-	Seal multi-aquifer wells				Believed minor	-

* Note that well designations refer to different wells in different aquifers

** All Prairie du Chien-Jordan alternatives use existing wells only

See accompanying report for locations of designated wells.

002587

To sum up, creosote-waste contaminants in the groundwater near the former Republic Creosote site can be contained by gradient control wells. Total pumpage on the order of 10.5 million gallons per day (including substantial current pumpage for water supply) is required. Existing water supply wells can be used to control the Prairie du Chien-Jordan aquifer. Well construction costs in the shallower aquifers are estimated to be approximately \$75,000. Discharge from the shallower control wells (approximately 1.2 million gallons daily) and from some portion of the 9.3 million gallons daily from the Prairie du Chien-Jordan will require special treatment to reduce PAH levels.

$$I = \frac{229.31 Q}{Tr}$$

$$r = \frac{229.31 Q}{T I}$$

$r = \text{radius (ft)}$

$T = \text{transmissivity}$

$Q = \text{gpm}$

$I = \text{ft/ft}$

for: equation

$$T = 38,600$$

$$r = 1,000$$

find Q

$$I = \frac{10 \text{ ft}}{\text{mi}} = .00189$$

$$Q = \frac{I Tr}{229.31} = \frac{(.00189)(38,600)(1,000)}{229.31}$$

$$= 318 \text{ gpm}$$

big 2
graph

$$T/Q = 130$$

$$Q = \frac{T}{130} = \frac{38,600}{130}$$

$$= 297 \text{ gpm}$$

$$T = K(\text{depth}) = 38,600 \text{ gpd/ft}$$

$$K = \frac{T}{\text{depth}} = 158 \text{ gpd}$$

$$7.48 \text{ gal/ft} \times (1.54 \text{ ft}) = 11.52 \text{ ft}$$

$$q = Km \text{ d/h}$$

$$= 158 \text{ gpd} (297 \text{ gpm}) (.00189)$$

$$V_s = \frac{K d h}{n_e} = \frac{158 (38,600) (.00189)}{(.2) (7.48)}$$

$$= 48.76 \text{ ft/yr}$$

065700

$$1.5 \text{ g/g} =$$

$$V = \frac{e}{K_1}$$

$$= 21.17 \text{ g/g}$$

$$= 158 \text{ g/g}$$

$$K = \frac{b}{I} = \frac{244 \text{ g/g}}{38600 \text{ g/g}}$$

$$K = 244 \text{ g/g}$$

$$T = 38600 \text{ g/g}$$

$$T = K$$

$$1 \text{ g/g} = 0.134 \text{ g/g}$$

$$10 \text{ g/g} = 1.02189$$

$$2 = 2$$

For future use

Geraghty & Miller, Inc.

TASKS 2010 AND 2030
CONCEPTUAL ANALYSIS AND DESIGN OF
GRADIENT-CONTROL WELL SYSTEM

Submitted to:

E. A. HICKOK & ASSOCIATES
Wayzata, Minnesota

By:

GERAGHTY & MILLER, INC.
Annapolis, Maryland

April 1981

002591

CONTENTS

	<u>Page</u>
INTRODUCTION	1
IDENTIFICATION AND EVALUATION OF ALTERNATIVES	5
Middle Drift Aquifer	8
Platteville Aquifer	11
St. Peter Aquifer	13
Prairie du Chien-Jordan Aquifer	15
Ironton-Galesville Aquifer	19
Mt. Simon-Hinckley Aquifer	20

TABLES

1. VALUES OF AQUIFER PARAMETERS	3
2. AVERAGE ANNUAL PUMPING RATE IN PRAIRIE DU CHIEN-JORDAN	17

FIGURES

1. RELATIONSHIPS BETWEEN GRADIENTS, TRANSMISSIVITIES, PUMPING RATE AND RADIAL DISTANCE	4
2. CONTROL OF GRADIENT AT A POINT	6
3. PLUME OF CONTAMINATION IN THE MIDDLE DRIFT AQUIFER SHOWING SELECTED CRITICAL POINTS AND LOCATIONS OF WELLS	9
4. PLUME OF CONTAMINATION IN THE PLATTEVILLE AQUIFER SHOWING SELECTED CRITICAL POINTS AND LOCATIONS OF WELLS	12
5. PLUME OF CONTAMINATION IN THE ST. PETER AQUIFER SHOWING SELECTED CRITICAL POINTS AND LOCATIONS OF WELLS	14
6. PLUME OF CONTAMINATION IN THE PRAIRIE DU CHIEN-JORDAN AQUIFER SHOWING SELECTED CRITICAL POINTS AND LOCATIONS OF WELLS	16

TASKS 2010 AND 2030
CONCEPTUAL ANALYSIS AND DESIGN OF
GRADIENT-CONTROL WELL SYSTEM

INTRODUCTION

The contaminated ground water in the aquifers underlying St. Louis Park is moving through the earth in directions and at rates determined by natural hydraulic gradients and gradients created by pumping from wells. Hydraulic gradient is the rate of change of pressure head per unit of distance of flow at a given point and in a given direction. According to studies made by the U. S. Geological Survey (USGS), the regional hydraulic gradient within the hydrogeologic system of the St. Louis Park area is generally to the east at about 10 ft/mi. Locally, however, the contaminated ground water in the aquifers may be moving in other directions, due to the influence of pumping from nearby public water-supply wells.

The most practical way of controlling the movement of contaminated ground water is to pump from wells located up-gradient, so that the original gradient in the contaminated body is flattened or reversed. The gradient-control wells must be pumped at the proper rate to achieve the desired level of flattening or reversal at any point within the contaminated ground-water body. The factors that determine

the gradient created at any particular point by a pumping well are the (1) rate of pumping, (2) rate at which water is transmitted through a unit width of the aquifer under a unit hydraulic gradient (which is referred to as the transmissivity of the aquifer), and (3) distance from the pumping well to the point. The following formula, based on Darcy's Law, shows the relationship of these factors:

$$I = \frac{229.31 Q}{Tr} \quad (1)$$

where,

I = hydraulic gradient in ft/ft,
 Q = pumping rate in gpm,
 T = transmissivity in gpd/ft, and
 r = distance from any point to the pumped well in ft.

Values of transmissivity for the various aquifers in the St. Louis Park area are given in Table 1, which also contains other data on aquifer parameters. These values represent the best information available, but may not be entirely correct for all parts of the study area. Test drilling and test pumping would be needed to improve knowledge in this regard.

Figure 1 is a graphical representation, based on the foregoing formula, of the gradients created by pumping at different radial distances from a gradient-control well. One way of using the graph is to first select a radial distance to the point at which some desired level of gradient

TABLE 1
VALUES OF AQUIFER PARAMETERS

Formations	Depth (ft)	Thickness (ft)	Transmissivity (gpd/ft)	Horizontal Hydraulic Conductivity (gpd/ft ²)	Vertical Hydraulic Conductivity (gpd/ft ²)	Storage Coefficient	Porosity	Sources of Information (see biblio- graphy)
Upper Drift	65	15-20			0.02 - 2.2			1
Middle Drift	to	20	10,500	20 - 1050			0.3	1
Lower Drift	85	20-30						
Platte- ville	68-85	20-30	26,000				0.2	*
Glenwood	90-95	2-5			7.5×10^{-5}			1 and 2
St. Peter	93	110	37,500	341	297	1×10^{-4}	0.3	3
Basal St. Peter	203	55			0.015			1 and 2
Prairie du Chien-Jordan	258	244	38,600	158		5×10^{-5}	0.20	2 and 3
St. Lawrence Franconia	502	191	675	3.5	0.035			2
Ironton- Galesville	693	50	112	2.2	1.5		0.25	3
Eau Claire	743	87			5.5×10^{-5}			3
Mt. Simon- Hinckley	830	263	19,500	74	53	8×10^{-3}	0.22	3

* Geraghty & Miller, Inc. estimate

002595





Figure 1. Relationships between gradients, transmissivities, pumping rates and radial distances.

control is needed and then move vertically upward on the the left and read off the value of transmissivity divided by the pumping rate. Using the proper value of transmissivity from Table 1, the pumping rate for the gradient-control well can then be determined.

An example of how a gradient can be controlled by pumping is given in Figure 2, which shows a hypothetical plume of contamination in any aquifer. If the pre-existing hydraulic gradient at point P-1 is 10 ft/mi to the east, as depicted by the dashed arrow on the illustration, and if the objective is to attain a net hydraulic gradient of zero ft/mi at that point, the solution would be to locate a recovery well at a proper distance to the west. If the aquifer has a transmissivity of 38,600 gpd/ft (which is the reported transmissivity of the Prairie du Chien-Jordan aquifer), calculations using equation 1 or Figure 2 show that a recovery well (RW-1) located 1,000 ft west of point P-1 would have to be pumped at a rate of 319 gpm in order to achieve the net hydraulic gradient of zero ft/mi at point P-1.

IDENTIFICATION AND EVALUATION OF ALTERNATIVES

The present situation at and in the vicinity of the Reilly Company site is that the natural hydraulic gradients



EXPLANATION

- ⊙ RW-1 RECOVERY WELL
- GRADIENT DUE TO PUMPING
- - - - -> NATURAL GRADIENT

Figure 2. Control of gradient at a point.

are believed to differ from place to place within the contaminated bodies of ground water in all of the aquifers, although no detailed maps of the potentiometric surfaces are available to show these variations. This of course makes it difficult to know how to select sites and pumping rates for an effective gradient-control system. However, several examples of alternative locations and pumping rates were evaluated using the best estimates for aquifer parameters, existing pumping rates for various wells in the area, and an assumed existing hydraulic gradient of 10 ft/mi to the east for all aquifers. The analysis indicated that the most critical points for gradient control lie along the boundary of the plume, with the leading edge of the plume being of greatest concern.

The alternatives included using different numbers and locations of wells to be pumped at different rates within and/or outside the contaminated plumes. Other combinations of recovery wells pumped at different rates and located in other places could be, designed to accomplish the same result. In the following analysis of alternatives, the overlapping effects of pumping from multiple recovery wells were calculated using the basic logic discussed above. Figures 3 through 6 show the boundaries of the plume in the Middle Drift, Platteville, St. Peter, and the Prairie du

Chien-Jordan aquifers, along with desired control points and locations of hypothetical recovery wells. Each of the examples is discussed below.

A. Middle Drift Aquifer

Contaminated ground-water in the Middle Drift aquifer appears to extend approximately 6,000 ft east and approximately 4,000 ft south of the site (see Figure 3) and is estimated to be moving at a rate of 167 ft/yr to the east. The estimated rate of movement was derived in this and all ensuing examples from the equation:

$$V = \frac{K_h I}{\theta}$$

where,

V = rate of movement in ft/yr,
K_h = horizontal hydraulic conductivity
in ft/day,
I = hydraulic gradient in ft/ft, and
θ = porosity of the aquifer

Three alternatives were considered in which the recovery wells were pumped at 100 gpm each, using an aquifer transmissivity of 10,500 gpd/ft, to calculate the resultant magnitude and direction of the hydraulic gradients at points P-1 and P-2. The first alternative uses two recovery wells, RW-5 and RW-6, located west of the plume. The calculated




Figure 3. Plume of contamination in the Middle Drift Aquifer showing selected critical points and locations of wells.

002601

resultant hydraulic gradients are 6.6 ft/mi to the east at P-1 and 5.7 ft/mi to the west at P-2. Thus, with this pumping arrangement, the plume would continue to expand to the east and the west. Wells RW-5 and RW-6 would be contaminated in 15 years, and the eastern plume boundary would move to the east at a rate of 107 ft/yr.

The second alternative uses two recovery wells, RW-3 and RW-4, located north and south of the plume. The resultant hydraulic gradients are 6.4 ft/mi to the east at P-1 and 14 ft/mi to the east at P-2. As with the first alternative, contaminated water at P-1 would continue to move to the east at a rate of 104 ft/yr and well RW-3 would be contaminated in about 2 years.


The third alternative uses two recovery wells, RW-1 and RW-2, located within the plume. The resultant hydraulic gradients are 3.1 ft/mi to the west at P-1 and 14.8 ft/mi to the east at P-2. Using this pumping scheme, contaminated water would be pumped from RW-1 and RW-2, but the movement of the contaminated water at P-1 along the eastern edge of the plume would be reversed toward the recovery wells. Movement at all points on the plume boundary would be toward wells RW-1 and RW-2, resulting in a gradual decrease in the size of the contaminated area.

This third alternative would be more effective than the first two in controlling the movement of contaminated ground water.

B. Platteville Aquifer

Contaminated ground water appears to extend about 8,000 ft east and about 4,500 ft south of the site (see Figure 4) and is estimated to be moving at a rate of 483 ft/yr to the east. Two alternatives were considered, the first involving pumping at a rate of 100 gpm from each of the two recovery wells, RW-1 and RW-2, located within the plume. The value of transmissivity used was 26,000 gpd/ft. The resultant net hydraulic gradients are 11.6 ft/mi to the east at P-1 and 7.3 ft/mi to the east at P-2. Thus, contaminated water at P-2 would continue to move to the east at 355 ft/yr. *based on...*

A second alternative would be to allow the Platteville aquifer to continue discharging contaminants into the Middle Drift and St. Peter aquifers, simply because the Platteville cannot be pumped at a high enough rate to stop the movement of contaminants. Under this alternative, the contaminants entering the Middle Drift and St. Peter aquifers, which have a greater thickness and available drawdown than the Platteville aquifer, would be controlled by recovery well systems in those two aquifers. This alternative appears to be a more effective way of dealing with the contamination in the Platteville aquifer.



C. St. Peter Aquifer

Contaminated ground water appears to extend about 7,000 ft east, 2,000 ft west, 2,400 ft north, and 3,000 ft south of the site (see Figure 5) and is estimated to be moving at a rate of 105 ft/yr to the east. Three alternatives were considered, the first involving installation of a new recovery well at the site of existing water-supply wells SLP-1, SLP-2, and SLP-3 (unless one of these wells could be used for this purpose). Using a pumping rate of 400 gpm and an aquifer transmissivity of 37,500 gpd/ft, a net gradient at P-4 of about 8.5 ft/mi toward the east was calculated. Thus, contaminants at P-3 would continue to move to the east at about 89 ft/year.

The second alternative requires the use of two recovery wells at RW-1 and at the site of water-supply wells SLP-1, SLP-2, and SLP-3. Both wells would be pumped at 200 gpm. The resulting net hydraulic gradients would still all be to the east. Specifically, they are 7.9 ft/mi at P-3, 7.6 ft/mi at P-4, 11.5 ft/mi at P-5, and 11.8 ft/mi at P-6. Using this pumping scheme, contaminants at P-3 would continue to move to the east at about 83 ft/yr.




Figure 5. Plume of contamination in the St. Peter Aquifer showing selected critical points and location of wells.


002606

The third alternative requires the use of three recovery wells, R-1, R-2, and R-3, each being pumped at 200 gpm. The resultant net hydraulic gradients, which are all toward the recovery wells, are 12.6 ft/mi at P-1, 12.3 ft/mi at P-2, and 8.4 ft/mi at P-3. This alternative appears to be the most effective means of controlling the contamination in the aquifer.

D. Prairie du Chien-Jordan Aquifer

Contaminated ground water appears to extend about 11,000 ft to the east, 18,800 ft to the south, 4,000 ft to the west, and 2,600 ft to the north of the site (see Figure 6) and is estimated to be moving at a rate of 73 ft/yr to the east. Five alternatives were considered using only existing water-supply wells as recovery wells. For closely spaced water-supply wells pumping at appreciable rates (see Table 2), centers of pumping (CP) were selected so as to reduce the number of calculations in the analysis. For example, CP-A is the center of pumping for water-supply wells SLP-8 and SLP-16. An aquifer transmissivity of 38,700 gpd/ft was used.

The first alternative is to continue pumping the existing wells outside the plume at a combined rate of 6 mgd. Four principal centers of pumping, CP-A through CP-D



002608

TABLE 2

AVERAGE ANNUAL PUMPING RATE
IN PRAIRIE DU CHIEN-JORDAN
(1979)

St. Louis Park (1979)

<u>Well Number</u>	<u>Pumping Rate, gpm</u>
SLP- 4	221
SLP- 5	39
SLP- 6	859
SLP- 7	0
SLP- 8	721*
SLP- 9	0
SLP-10	0
SLP-14	35
SLP-15	20
SLP-16	739*

* Center of pumping CP-A due to
pumping wells SLP-8 and SLP-16

Edina (January through June 1979)

<u>Well Number</u>	<u>Pumping Rate, gpm</u>
E- 2	825
E- 3	4
E- 4	44
E- 5	9*
E- 6	634
E- 7	4
E- 8	2+
E-11	835*
E-13	0
E-14	0+
E-15	42
E-16	253+
E-17	7
E-18	1*

+ Center of pumping CP-C due to
pumping wells E-8, E-14 and E-16

* Center of pumping CP-D due to
pumping wells E-5, E-11 and E-18

Hopkins (1976)

<u>Well Number</u>	<u>Pumping Rate, gpm</u>
H-1*	512
H-3	136
H-4*	0
H-5*	1092
H-6*	0

* Center of pumping CP-B due to
pumping wells H-1, H-4, H-5, and
H-6

(see Figure 6), were used in the analysis. The resulting net hydraulic gradients, which are all to the east, are 2.9 ft/mi at P-1, 6.1 ft/mi at P-2, 7.2 ft/mi at P-3, 7.0 ft/mi at P-4, 3.7 ft/mi at P-5, and 5.4 ft/mi at P-6. This pumping scheme would only slow the movement of contaminants to the east, which would still generally be at a rate of about 45 ft/yr at P-2.

The second alternative is to pump the existing centers, CP-A through CP-D, at a total of approximately 6 mgd and to pump existing well SLP-15, located inside the plume, at 1 mgd. The resulting net hydraulic gradients, which are all to the east, range from 5.1 ft/mi to 8.1 ft/mi. This alternative would be hardly better than the first, except that the contaminated ground water within a radius of approximately 2,000 ft from water-supply well SLP-15 would probably move toward that well.

The third alternative is to pump wells SLP-6, SLP-15, and E-7, located inside the plume, at 1 mgd each, in addition to pumping a total of 6 mgd at centers CP-A through CP-D. The resulting net hydraulic gradients are all toward the inside of the contaminated plume, except at P-2 along the eastern boundary, where movement of contaminants would be to the southeast at 7 ft/yr.

The fourth alternative is to pump water-supply wells SLP-6 and SLP-15 at 1 mgd each and water-supply well H-3 at 0.5 mgd, in addition to pumping a total of 6 mgd at centers CP-A through CP-D. The resulting net hydraulic gradients at all points except P-2 are toward the inside of the plume. At P-2, along the eastern edge of the plume, the net gradient would be about 2 ft/mi to the northwest. Thus, the contaminants along the eastern boundary of the plume would continue to move, but the rate of movement would be only about 14 ft/yr.

The fifth alternative is to pump water-supply wells SLP-15 and H-3 at 1 mgd each and water-supply well SLP-6 at 1.3 mgd, in addition to pumping at a total of 6 mgd at centers CP-A through CP-D. The resulting net hydraulic gradients at all points are toward those recovery wells inside the plume. Thus, the spread of the contamination would be stopped and the volume of contaminants would gradually be reduced.

E. Iron-ton-Galesville Aquifer

Contaminated ground water in this aquifer extends approximately 1,000 ft north, 1,500 ft south, and 5,500 ft east of well W-23, which is located at the site. Because the Iron-ton-Galesville is not widely used for water supply,

perhaps the most sensible way of dealing with the contamination would be to seal or reconstruct all uncased multi-aquifer wells connecting this aquifer with other contaminated aquifers. If the contaminants nevertheless continue to spread, Well W-23 could be used as a recovery well or other recovery wells could be installed.

F. Mt. Simon-Hinckley Aquifer

Contaminated ground water in this aquifer appears to extend about 6,000 ft east and about 3,000 ft north and south of the site. The east-west extent of contamination is due primarily to seepage through the two multi-aquifer wells in the area. The north-south extent of contamination appears to be caused by pumping from the City of St. Louis Park wells 11, 12, and 13.

In order to prevent further contamination, multi-aquifer wells completed in the Mt. Simon-Hinckley aquifer should be sealed. Although a reduction in the spread of contaminants might be accomplished by discontinuing the use of the City of St. Louis Park wells 11, 12, and 13, contaminants would continue to move in the direction of and at the rate of the natural ground-water flow. At this time, the data are insufficient to predict the rate and direction of this natural flow.

The time required for contaminated water to seep into the Mt. Simon-Hinckley through the St. Lawrence-Franconia, the Iron-ton-Galesville, and the Eau Claire from the Prairie du Chien-Jordan was estimated to be about 4,250 years. The vertical hydraulic conductivities and porosities of the formations between the Mt. Simon-Hinckley and the Prairie du Chien-Jordan are shown in Table 1. The vertical hydraulic gradient used in the calculation of time of travel between the Prairie du Chien-Jordan and the Mt. Simon-Hinckley was 2.3 ft/ft.

6/15/82
N.



GCA CORPORATION
Technology Division

213 Burlington Road
Bedford, Massachusetts 01730
Telephone: 617-275-5444
Telex: 92-3339

June 15, 1982

Mike Kosakowski
U. S. Environmental Protection Agency
Office of Hazardous Waste Enforcement
Fairchild Building, 2nd Floor
499 S. Capital, S. W.
Washington, D. C. 20460

Subject: EPA Contract No. 68-01-6316
Task C
(GCA 1-452-124)

Dear Mike:

The enclosed data package contains the analysis results you requested. Specifically, the following data are included.

- PAH Analysis By HPLC - Fluorescence Of Eleven Water Samples From The Mississippi River.
- PAH Analysis By HPLC - Fluorescence Of Fifteen Water Samples From The MWCC (Seven Influent and Eight Effluent)
- PAH Analysis by HPLC - Fluorescence of Four Empty Sample Containers (Field Blanks).

The data tables are identified by the sample location as submitted on the chain of custody records.

If you have any questions, please feel free to call.

Sincerely,

MIKE

Mike Rennekamp
Senior Scientist
Laboratory Analysis Department
GCA/Technology Division

cc: K. T. McGregor
G. T. Hunt
S. M. Sandberg

MER/mdp

Analytical Conditions

Column: Altex Ultrasphere ODS, 4.6 x 250 mm.

Mobile Phase: 70% to 75% Acetonitrile over 20 minutes, then
75% to 100% Acetonitrile over 20 minutes
Second component of mobile phase is water.

Flow rate: 1.0 ml/min.

Chart Speed: 0.1 in/min.

Fluorescence Detector: Excitation 280 nm.
Emission 389 nm.

Temperature: Ambient

Injection Volume: 30 µl

Note: Benzo(k) Fluoranthene is not quantitated in some samples as this component was later determined to be adequately resolved for detection under the above conditions and was subsequently added to the list of parameters.



GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18825

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-827Analysis Date 6/3/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	< 11	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 9	
Phenanthrene	< 1	
Fluoranthene	< 17	
Anthracene	< 2	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	3.0	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18826

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-840 Analysis Date 6/3/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	< 11	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	40,320	
Phenanthrene	< 1	
Fluoranthene	< 17	
Anthracene	< 2	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 2	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18827

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-847 Analysis Date 6/7/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	35	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	126	
Phenanthrene	< 1	
Fluoranthene	< 17	
Anthracene	< 2	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 2	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18828

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-859 Analysis Date 6/7/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-108 Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	< 11	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	670	
Phenanthrene	< 1	
Fluoranthene	< 17	
Anthracene	< 2	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 2	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18829

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Ford Dam Analysis Date 6/7/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	< 11	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 9	
Phenanthrene	< 1	
Fluoranthene	< 17	
Anthracene	< 2	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 2	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18931

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Field Bank Analysis Date Sample Matrix Analytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration Total Nanograms	Remarks
Naphthalene	< 14	
Acenaphthene	< 23	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 18	
Phenanthrene	< 2	
Fluoranthene	3,040	
Anthracene	50	
Triphenylene	< 2	
Pyrene	< 2	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 4	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 4	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 13	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18932

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff-E; Effluent, MWCC Analysis Date 6/7/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 7	
Acenaphthene	< 11	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 9	
Phenanthrene	< 1	/
Fluoranthene	< 17	
Anthracene	5	
Triphenylene	< 1	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 2	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18933

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff-W; Effluent, MWCC Analysis Date 6/7/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 137	
Acenaphthene	< 229	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 182	
Phenanthrene	< 13	
Fluoranthene	8,400	
Anthracene	< 38	
Triphenylene	< 20	
Pyrene	< 13	
Chrysene	< 2	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene		
Benzo(b)fluoranthene	< 34	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 38	
Benzo(g,h,i)perylene	< 6	
Dibenzo(a,h)anthracene	< 4	
Indeno(1,2,3-cd)pyrene	< 122	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18934

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Ford Dam; Mississippi River, Mpls. Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	44	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	2,270	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	2	
Triphenylene	< 4	
Pyrene	13	
Chrysene	1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 13	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	5	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18935

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Gray Cloud; Mississippi River, St. Paul Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-108 Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	< 1	
Chrysene	9	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 13	
Benzo(b)fluoranthene	26	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	2	
Indeno(1,2,3-cd)pyrene	< 14	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18936

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf; Influent, MWCC Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	1,580	
Acenaphthene	< 142	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	198,000	
Phenanthrene	49,200	
Fluoranthene	< 416	
Anthracene	241	
Triphenylene	210	
Pyrene	< 8	
Chrysene	< 6	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	2,310	
Benzo(b)fluoranthene	< 44	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 6	
Benzo(g,h,i)perylene	< 6	
Dibenzo(a,h)anthracene	381	
Indeno(1,2,3-cd)pyrene	< 56	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18937

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-827; Mississippi River, St. Paul Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	5	
Triphenylene	69	
Pyrene	6	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	87	
Benzo(b)fluoranthene	16	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	12	
Indeno(1,2,3-cd)pyrene	22	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18938

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-840; Mississippi River, St. Paul Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	298	
Fluoranthene	< 21	
Anthracene	2	
Triphenylene	< 4	
Pyrene	4	
Chrysene	3	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 13	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18939

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-847; Mississippi River, Mpls. Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	50	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	114	
Fluoranthene	< 21	
Anthracene	2	
Triphenylene	< 4	
Pyrene	2	
Chrysene	2	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 13	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18940

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. UM-859; Mississippi River, Mpls. Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	< 7	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	364	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	2	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 13	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18977

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Field Blank Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration Total Nanograms	Remarks
Naphthalene	< 81	
Acenaphthene	< 14	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 111	
Phenanthrene	< 46	
Fluoranthene	< 42	
Anthracene	< 3	
Triphenylene	< 8	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 26	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 2	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18978

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff E; MWCC, Effluent - East Bank Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	34	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	36	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	4	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18979

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff W; MWCC, Effluent-West Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	13	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	21	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	2	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18980

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf E; MWCC, Influent - East Bank Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 5,060	
Acenaphthene	542	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 6,940	
Phenanthrene	< 2,840	
Fluoranthene	102,000	
Anthracene	< 186	
Triphenylene	3,300	
Pyrene	< 53	
Chrysene	< 38	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 1,650	
Benzo(b)fluoranthene	< 25	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 38	
Benzo(g,h,i)perylene	220	
Dibenzo(a,h)anthracene	267	
Indeno(1,2,3-cd)pyrene	< 350	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 18981

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf Isco; MWCC, Influent-Isco Sampler Analysis Date 6/9/82Sample Matrix Analytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 8,100	
Acenaphthene	< 1,420	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	285,000	
Phenanthrene	< 4,540	
Fluoranthene	< 4,160	
Anthracene	< 300	
Triphenylene	< 800	
Pyrene	< 80	
Chrysene	< 60	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 2,640	
Benzo(b)fluoranthene	< 40	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 60	
Benzo(g,h,i)perylene	300	
Dibenzo(a,h)anthracene	301	
Indeno(1,2,3-cd)pyrene	< 560	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19099

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Field Blank Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration Total Nanograms	Remarks
Naphthalene	159	
Acenaphthene	< 14	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	4,500	
Phenanthrene	< 45	
Fluoranthene	< 42	
Anthracene	18	
Triphenylene	4	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 26	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	3	
Dibenzo(a,h)anthracene	2	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19100

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf E; MWCC, East Bank, Influent Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	6,760	
Acenaphthene	< 142	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	1,190	
Phenanthrene	< 454	
Fluoranthene	19,100	
Anthracene	112	
Triphenylene	2,340	
Pyrene	< 8	
Chrysene	< 6	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	3,330	
Benzo(b)fluoranthene	< 4	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 64	
Benzo(g,h,i)perylene	< 6	
Dibenzo(a,h)anthracene	< 16	
Indeno(1,2,3-cd)pyrene	< 56	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19101

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf E Isco; MWCC, East Influent, Isco Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 810	
Acenaphthene	606	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	6,530	
Phenanthrene	< 454	
Fluoranthene	< 416	
Anthracene	< 300	
Triphenylene	162	
Pyrene	103	
Chrysene	101	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 264	
Benzo(b)fluoranthene	< 40	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 6	
Benzo(g,h,i)perylene	1,220	
Dibenzo(a,h)anthracene	< 160	
Indeno(1,2,3-cd)pyrene	< 560	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19102

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff E; MWCC, East Bank, Effluent Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-108 Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	298	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	90	
Phenanthrene	252	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	< 1	
Chrysene	2	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	28	
Benzo(b)fluoranthene	5	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	2	
Dibenzo(a,h)anthracene	1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19103

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff W; MWCC, West Bank, Effluent Analysis Date 6/9/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 41	
Acenaphthene	146	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 56	
Phenanthrene	< 23	
Fluoranthene	< 21	
Anthracene	< 2	
Triphenylene	< 4	
Pyrene	< 1	
Chrysene	< 1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	35	
Benzo(b)fluoranthene	6	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	3	
Dibenzo(a,h)anthracene	< 1	
Indeno(1,2,3-cd)pyrene	< 3	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19157

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Field Blank Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration Total Nanograms	Remarks
Naphthalene	< 81	
Acenaphthene	186	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 111	
Phenanthrene	< 45	
Fluoranthene	< 42	
Anthracene	< 3	
Triphenylene	< 8	
Pyrene	< 1	
Chrysene	1	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 26	
Benzo(b)fluoranthene	< 1	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 1	
Benzo(g,h,i)perylene	< 1	
Dibenzo(a,h)anthracene	< 2	
Indeno(1,2,3-cd)pyrene	< 6	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19158

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff E II⁰; MWCC, Effluent East, Auto Analysis Date 6/10/82
SamplesSample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 405	
Acenaphthene	106	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	< 555	
Phenanthrene	< 227	
Fluoranthene	< 208	
Anthracene	< 15	
Triphenylene	< 40	
Pyrene	< 4	
Chrysene	< 3	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 132	
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 3	
Benzo(g,h,i)perylene	< 3	
Dibenzo(a,h)anthracene	< 8	
Indeno(1,2,3-cd)pyrene	< 28	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19159

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Eff W II⁰: MWCC, Effluent West, Auto Sampler Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 405	
Acenaphthene	< 71	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	2,940	
Phenanthrene	< 227	
Fluoranthene	< 208	
Anthracene	29	
Triphenylene	< 40	
Pyrene	9	
Chrysene	4	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	20	
Benzo(b)fluoranthene	< 2	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 3	
Benzo(g,h,i)perylene	< 3	
Dibenzo(a,h)anthracene	< 8	
Indeno(1,2,3-cd)pyrene	< 28	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19160

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf E I⁰; MWCC, Influent East, Auto-Sampler Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	1,670	
Acenaphthene	< 142	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	197,000	
Phenanthrene	52,200	
Fluoranthene	< 416	
Anthracene	218	
Triphenylene	< 80	
Pyrene	< 8	
Chrysene	554	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	< 264	
Benzo(b)fluoranthene	92	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 60	
Benzo(g,h,i)perylene	125	
Dibenzo(a,h)anthracene	< 160	
Indeno(1,2,3-cd)pyrene	< 560	

GCA CORPORATION
Technology Division

Project 1-452-124cGCA Control No. 19161

DATA REPORT SHEET

Polynuclear Aromatic Hydrocarbons

Sample I.D. Inf IOE Isco; MWCC, East Influent, Isco Analysis Date 6/10/82Sample Matrix WaterAnalytical Method EPA 610 (Federal Register, 40 CFR Part 136, December 3, 1979)Instrument Dupont 850 HPLC, PE 650-10S Fluorescence/PE LC-75 UV Detectors

Parameter	Concentration (ng/l)	Remarks
Naphthalene	2,390	
Acenaphthene	< 142	Coelutes with acenaphthylene; value calculated on basis of acenaphthene
Fluorene	5,700	
Phenanthrene	52,200	
Fluoranthene	< 416	
Anthracene	917	
Triphenylene	< 80	
Pyrene	< 8	
Chrysene	125	Coelutes with Benzo(a)Anthracene; Value calculated on basis of Chrysene
Benzo(k)fluoranthene	2,100	
Benzo(b)fluoranthene	364	Coelutes with Benzo(e)Pyrene; Value calculated on basis of Benzo(b)Fluoranthene
Benzo(a)pyrene	< 60	
Benzo(g,h,i)perylene	334	
Dibenzo(a,h)anthracene	< 160	
Indeno(1,2,3-cd)pyrene	< 560	

GCA CORPORATION
Technology Division

STATE OF MINNESOTA

DEPARTMENT

POLLUTION CONTROL AGENCY

Office Memorandum

TO : Steve Shakman, Special Assistant Attorney General
Paul Bitter, U.S. Environmental Protection Agency, Chicago
Mike Convery, Minnesota Department of Health
Marc Hult, United States Geological Survey
Mike Kosakowski, U.S. Environmental Protection Agency, Washington
Bob Leininger, U.S. Environmental Protection Agency, Chicago

FROM : Michael J. Hansel, Regulatory Compliance Section
Solid and Hazardous Waste Division

SUBJECT: LOCATION OF MISSISSIPPI RIVER AND MINNESOTA WASTE CONTROL COMMISSION
PIG'S EYE PLANT SAMPLES


DATE: June 24, 1982

PHONE:

You recently received a copy of the analyses of river and influent/effluent by GCA. Attached is a copy of a memo which locates where those samples were taken. The sample identification number on the tabulation's from GCA correspond to locations on the river or at the plant. You should note that samples were taken at each location on two different dates, but the tabulations from GCA do not show which is which. I have asked GCA to clarify this, and I will forward the clarification to you as soon as received.

MJH/sf

Attachment



DEPARTMENT POLLUTION CONTROL AGENCY

Office Memorandum

TO : Gordon Meyer, Chief
Regulatory Compliance Section
Division of Solid and Hazardous Waste

DATE: February 24, 1982

FROM : John F. McGuire, P.E., Chief
Monitoring and Analysis Section
Division of Water Quality

PHONE: 6-7242

SUBJECT: PAH SAMPLING FROM THE MISSISSIPPI RIVER AND THE METRO WASTE CONTROL -
ST. PAUL PLANT

The Monitoring and Analysis Section has completed the PAH sampling of the Mississippi River and the Metro Waste Control - St. Paul Plant. The attached sampling program will detail the investigation. The PAH analyses will be forwarded to Rick Ferguson as they become available. Please contact Dan Helwig (296-7288) of my staff if you have any questions.

JFM:DDH/drn

Attachment

cc: Rick Ferguson - Regulatory Compliance Section ✓
Loren Voight - Enforcement
David Maschwitz - Monitoring and Analysis Section
Lovell Richie - Senior Executive Officer
Steve Shakman - Special Assistant, Attorney General

RECEIVED

MAR 11 1982

MINN. POLLUTION
CONTROL AGENCY

Office Memorandum

TO : John F. McGuire, P.E., Chief
Monitoring and Analysis Section

THRU: Marvin E. Hora, Head
Ambient and Intensive Monitoring Unit

FROM : Daniel D. Helwig, Biologist DDH
Monitoring and Analysis Section

DATE: February 22, 1982

PHONE: 6-7288

SUBJECT: PAH SAMPLING FROM THE MISSISSIPPI RIVER AND THE METRO WASTE CONTROL -
ST. PAUL PLANT

Introduction:

The Solid and Hazardous Waste Division requested assistance to sample Polynuclear Aromatic Hydrocarbons (PAH) at the Metro Waste Control Commission (MWCC) - St. Paul Plant, the Mississippi River, and the Minnehaha Creek in a memo from Dale Wikre to Barry Schade, dated October 29, 1981. Richard Ferguson called a meeting on December 18, 1981. Marv Hora, Dave Maschwitz, and I attended. Sampling locations, sampling procedures, and sample replication were discussed. Rick summarized the results of the meeting and our later conversations in a memo dated January 11, 1982, to Marv Hora. Sampling was initiated on January 13 and finished on January 28. The details of the sampling program are discussed in this memo. The results are not available at this time.

Methods:

Mississippi River Samples

PAH and non-filtrable residue samples were taken from four sites on the Mississippi River on January 13, and again on January 19, 1982. The samples were taken from 1) the Minneapolis Water Works Plant (UM-859), 2) Ford Dam Generating Plant (UM-847), 3) Lambert's Landing (UM-840), and 4) near Grey Cloud Island (UM-827). (See Table 1). UM-859 was taken from a constantly flowing tap, directly off the intake line from the river, within the Softening Building of the Minneapolis Water Works Plant. UM-847 was taken with a sampling arm, from open water, immediately upstream of the bar screens to the Ford Generating Plant. UM-840 was taken with a sampling arm, through approximately 2" of ice, from Lambert's Landing. UM-827 was taken by hand through approximately 8" of ice, next to a barge mooring pier at the Larson Plant of Shieley, Inc., near Grey Cloud Island.

Grab samples were taken at all Mississippi River stations. Pre-washed glass gallon bottles (PAH) and glass liter bottles were filled directly from the river, to the top, with no sample pre-rinsing. A field blank accompanied the sample containers on the January 19 sampling but not on the January 13 sampling. An internal sample split with GCA Lab. was taken at the Ford Dam site on January 13. Internal splits with GCA Lab. and outside splits with the MDH (see Table 1) were taken at the Ford Dam and at the Grey Cloud Island site on January 19.

MWCC - St. Paul Plant

Twenty-four hour composite samples of the influent, effluent, and press cake were taken from the St. Paul Plant on January 18-19, January 20-21, January 25-26, and January 27-28 (See Table 1). The water samples were taken from MWCC automatic, flow-proportioning samplers, and from an Isco auto sampler designed for sampling priority pollutants. The press cake was taken from a conveyor belt leading away from the press cake frames.

Influent entering the St. Paul Plant is divided into East and West banks and further divided into 6 and 2 channels, respectively. The PAH samples were taken from the East Bank, Channels 2 and 5. A 50/50 mixture of the influent from MWCC flow-proportioning auto samplers Mag 2 and Mag 5 (see Figure 1) was used to represent the influent to the whole plant. PVC plastic pipe feed the auto samplers on a flow through basis. Although some contribution and/or uptake of PAH compounds from the pipe is recognized; they are assumed to have reached a steady state condition. To verify this assumption, an Isco sampler, designed for priority pollutants, was set up in the channel to sample from nearly the same point as the auto samplers. The Isco samples are not flow proportioned.

The effluent sample was taken from auto samplers "East Effluent" and "West Effluent". These samplers are similar to the influent samplers, providing flow proportioned composite samples. One sample each sampling day and from each bank was taken because of the differing treatment processes on the waste water.

The press cake sample was taken from a conveyor belt leading away from the press cake frames. An equal amount of press cake (by weight) was spooned into the sample jars each hour for 24 hours.

The influent and effluent from the auto samplers were taken from 6:00 A.M. to 6:00 A.M. as were the press cake samples. The influent Isco sample was taken from 11:00 A.M. to 11:00 A.M. No internal splits for GCA Lab were taken due to the analytical needs of MWCC. External splits for MDH were taken from the influent auto samplers, from the effluent auto west bank sampler, and from the press cake on January 20-21 and January 27-28. (See Table 1.) The press cake samples won't be analyzed by MDH until GCA Lab documents a methodology. All samples were picked up at noon, iced, and shipped overnight to GCA Lab. The shipping coolers were sealed with a MPCA tag with the GCA chain of custody lab sheets and sent with the "SSS Chain of Custody" service of Federal Express. All shipping documentation are enclosed.

DDH/drn


Attachment

TABLE 1. "PAH" SAMPLING DATES, LOCATIONS, AND LABS

Date	Sample Location	Lab		
		GCA	NFR*	MDH
		PAH		PAH
January 13, 1982	Mississippi River (UM-859), Minneapolis Waterworks	1	1	
	Mississippi River (UM-847), Ford Dam	2	1	
	Mississippi River (UM-840), Lambert's Landing	1	1	
	Mississippi River (UM-827), Grey Cloud Island	1	1	
January 19, 1982	Mississippi River (UM-859), Minneapolis Waterworks	1	1	
	Mississippi River (UM-847), Ford Dam	2	1	1
	Mississippi River (UM-840), Lambert's Landing	1	1	
	Mississippi River (UM-827), Grey Cloud Island	2	1	1
	Field Blank	1		1
	Primary Influent East (I°INF E), MWCC	1		
	Secondary Effluent East (II°EFF E), MWCC	1		
	Secondary Effluent West (II°EFF W), MWCC	1		
	Plate and Frame Press Cake, MWCC	1		
January 21, 1982	Primary Influent East (I°INF E), MWCC	1		1
	Primary Influent East (Isco), MWCC	1		
	Secondary Effluent East (II°EFF E), MWCC	1		
	Secondary Effluent West (II°EFF W), MWCC	1		1
	Plate and Frame Press Cake, MWCC	1		1
	Field Blank	1		1
January 26, 1982	Primary Influent East (I°INF E), MWCC	1		
	Primary Influent East (Isco), MWCC	1		
	Secondary Effluent East (II°EFF E), MWCC	1		
	Secondary Effluent West (II°EFF W), MWCC	1		
	Plate and Frame Press Cake, MWCC	1		
	Field Blank	1		
January 28, 1982	Primary Influent East (I°INF E), MWCC	1		1
	Primary Influent East (Isco), MWCC	1		
	Secondary Effluent East (II°EFF E), MWCC	1		
	Secondary Effluent West (II°EFF W), MWCC	1		1
	Plate and Frame Press Cake, MWCC	1		1
	Field Blank	1		1
		<u>34</u>	<u>8</u>	<u>11</u>

* NFR = Nonfilterable Residue

FIGURE 1. MWCC - ST. PAUL PLANT, PAH SAMPLING LOCATIONS



4/20/82
N.

GCA CORPORATION
Technology Division

213 Burlington Road
Bedford, Massachusetts 01730
Telephone 617-275-5444
Telex: 92-3339

April 20, 1982

Mike Kosakowski
U. S. Environmental Protection Agency
Office of Hazardous Waste Enforcement
Fairchild Building, 2nd Floor
499 S. Capitol Street, S. W.
Washington, D.C. 20460

Subject: EPA Contract No. 68-01-6316
TSA 1, WA 24, Task B
(GCA 1-452-124b)

Dear Mike:

Enclosed please find analytical results pertinent to the above task. Results are included for the following water samples:

SLP - 14 (duplicate)
SLP - 15
SLP - 16
SLP - 17

All measurements were collected using HPLC/fluorescence procedures and are reported in ng/l (ppt). Sample preparation procedures were in accordance with EPA Method 610. I've also included a summary listing of instrument operating conditions and laboratory quality control data pertinent to these analyses.

Should you have any questions concerning the enclosed information, please do not hesitate to call me.

Sincerely,



Kenneth T. McGregor
Manager
Laboratory Analysis Department

KTM/mdp

Analysis of Polynuclear Aromatic Hydrocarbons
EPA Method 610

Instrument Conditions

- 1) Dupont Model 850 High Pressure Liquid Chromatograph.
- 2) Perkin-Elmer Analytical PAK 0250-0082 column.
- 3) Perkin-Elmer 550-10S Fluorescence Spectrophotometer; 15 nm slit setting; 280 nm Excitation, 389 nm Emission.
- 4) Perkin-Elmer LC-75-UV Spectrophotometric detector; 254 nm.
- 5) Gradient Elution - Linear gradient of 30% Acetonitrile/70% water, increasing to 100% Acetonitrile over 60 minutes; flow rate of 1.0 ml./min.
- 6) Injection volume - 30 microliters.



GCA CORPORATION
Technology Division

Polynuclear Aromatic Hydrocarbon Analysis

Procedural Recovery Control Limits

	<u>Percent Recovery</u>		
	Acenaphthylene	Phenanthrene	Benzo (a) Pyrene
\bar{x} (n=3)	100%	72%	97%
Std. Dev. (S)	23	2	7
2S	56	4	14
Control Limit ($\pm 2S$)	44-156%	68-76%	80-108%



Project 1-45-176GCA Control No. 18131-1DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 612Sample I.D. SLP 14Additional Comments Sample SLP 14 (GCA No. 18131-1) and Sample SLP 14
(GCA No. 18131-2) represent replicate analysesAnalyst(s) M. Cardelli Checked By R. RobillardAnalysis Date 3/26/82 Report Date 4/13/82

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 37	
Acenaphthylene ¹	< 20	
Fluorene	< 200	
Phenanthrene	26	
Fluoranthene	< 250	
Anthracene	< 2	
Triphenylene	< 20	
Pyrene	< 8	
Benzo(a)Anthracene	3	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene

Project 1-452-124bGCA Control No. 18131-2DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 610Sample I.D. SLP 14Additional Comments Sample SLP 14 (GCA No. 18131-2) and Sample SLP 14
(GCA No. 18131-1) represent replicate analyses.Analyst(s) M. Gardell Checked By R. RobillardAnalysis Date 3/26/82 Report Date 4/13/82

Parameter	Concentration (rg/l)	Remarks
Naphthalene	< 57	
Acenaphthene ¹	< 20	
Fluorene	< 200	
Phenanthrene	30	
Fluoranthene	< 250	
Anthracene	< 2	
Triphenylene	< 20	
Pyrene	< 8	
Benzo(a)Anthracene	< 3	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene

Project 1-452-124bGCA Control No. 18133DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 610Sample I.D. SLP 16

Additional Comments _____

Analyst(s) M. G. GelfiChecked By R. RobillardAnalysis Date 3/26/82Report Date 4/13/82

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 57	
Acenaphthene ¹	< 20	
Fluorene	< 200	
Phenanthrene	37	
Fluoranthene	< 250	
Anthracene	< 2	
Triphenylene	< 20	
Pyrene	< 8	
Benzo(a)Anthracene	8	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene

Project 1-452-124bGCA Control No. 18132DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 810Sample I.D. SIP 15

Additional Comments _____

Analyst(s) M. GardellChecked By R. RobillardAnalysis Date 3/31/82Report Date 4/13/82

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 57	
Acenaphthene ¹	2,200	
Fluorene	25,000	
Phenanthrene	< 10	
Fluoranthene	20,000	
Anthracene	270	
Triphenylene	86	
Pyrene	< 8	
Benzo(a)Anthracene	17	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene

Project 1-750-124bOCA Control No. 13134DATA REPORT SHEET
Polynuclear Aromatic Hydrocarbons
EPA Method 810Sample I.D. SIP 17

Additional Comments _____

Analyst(s) M. GardellChecked By R. RobillardAnalysis Date 3/30/82Report Date 4/14/82

Parameter	Concentration (ng/l)	Remarks
Naphthalene	< 57	
Acenaphthene ¹	2,100	
Fluorene	4,500	
Phenanthrene	< 10	
Fluoranthene	< 250	
Anthracene	230	
Triphenylene	50	
Pyrene	220	
Benzo(a)Anthracene	10	
Chrysene	< 2	
Benzo(e)Pyrene	< 5	
Benzo(b)Fluoranthene	< 40	
Benzo(a)Pyrene ²	< 1	
Benzo(g,h,i)Perylene	< 10	
Dibenzo(a,h)Anthracene	< 5	
Indeno(1,2,3-cd)Pyrene	< 50	

¹Coelutes with Acenaphthylene--Value calculated on basis of Acenaphthene.²Coelutes with Benzo(k)Fluoranthene--Value calculated on basis of Benzo(a)Pyrene



CAPSULE LABORATORIES

ADVANCED TECHNOLOGY DIVISION

A Division of Economics Laboratory, Inc.
605 West County Road E, St. Paul, MN 55112, (612) 482-8855

Final Report

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC
HYDROCARBONS IN MUNICIPAL WATER
WELLS FOR THE
CITY OF ST. LOUIS PARK

Prepared by:

CAPSULE LABORATORIES
605 West County Road E
Shoreview, Minnesota 55112

Date Submitted:

April 16, 1982

4/16/82
N.



CAPSULE LABORATORIES

ADVANCED TECHNOLOGY DIVISION

A Division of Economics Laboratory, Inc.

605 West County Road E, St. Paul, MN. 55112, (612) 482-8855

April 16, 1982

Enclosed is the final report on the analysis of PNA's in municipal well waters of the City of St. Louis Park. Please note that the concentration of Phenanthrene in Well #4B, Capsule #11647, which was previously reported as N.D. has been corrected to read 110 parts-per-trillion. In addition, a table summarizing the present recoveries of deuterated spikes has been included as well as the statement of detection limits for this analysis.



TECHNICAL DATA

Analysis of Polynuclear aromatics*

Samples Received: 1/15/82
1/27/82

Compound	Well #3 Capsule # 11645	Well #4A Capsule # 11646	Well #4B Capsule # 11647	Well #6 Capsule # 11458	Well #8 Capsule # 11648
Naphthalene	N.D. **	N.D.	5	N.D.	N.D.
1-methyl naphthylene	N.D.	N.D.	N.D.	N.D.	N.D.
Acenaphthene	N.D.	60	92	N.D.	N.D.
Fluorene	N.D.	26	46	N.D.	N.D.
Phenanthrene	N.D.	N.D.	110	N.D.	N.D.
Anthracene	N.D.	7	N.D.	N.D.	N.D.
Fluoranthene	N.D.	N.D.	6	N.D.	N.D.
Pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (b) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (k) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Indeno (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Dibenzo (a,h) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (g,h,i) perylene	N.D.	N.D.	N.D.	N.D.	N.D.

*Results expressed as parts-per-trillion (ng/l)

** N.D. = Signal not observed or does not meet criteria for quantitation.

The detection limit for each PNA is 4 ng/l.



TECHNICAL DATA

Analysis of Polynuclear aromatics*

Samples Received: 1/15/82
1/27/82

Compound	Well #11 Capsule # 11459	Well #12 Capsule # 11460	Well #13 Capsule # 11461	Well #14A Capsule # 11462	Well #14B Capsule # 11463
				(spiked)	
aphthalene	N.D. **	N.D.	N.D.	8	5
ce. ethylene	N.D.	N.D.	N.D.	N.D.	N.D.
phenanthrene	N.D.	N.D.	N.D.	N.D.	N.D.
fluorene	N.D.	N.D.	N.D.	43	6
phenanthrene	N.D.	N.D.	N.D.	N.D.	N.D.
anthracene	N.D.	N.D.	N.D.	28	N.D.
fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (a) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (b) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (k) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (a) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
indeno (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (a,h) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
benzo (g,h,i) perylene	N.D.	N.D.	N.D.	N.D.	N.D.

Results expressed as parts-per-trillion (ng/l)

N.D. = Signal not observed or does not meet criteria for quantitation.

The detection limit for each PNA is 4 ng/l.



TECHNICAL DATA

Analysis of Polynuclear aromatics*

Samples Received: 1/15/82
1/27/82

Compound	Well #15A Capsule # 11464	Well #15B Capsule # 11465	Well #16 Capsule # 11649		
Phthalene	4	N.D.**	N.D.		
Benaphthylene	70	N.D.	N.D.		
Benanthrene	41	N.D.	N.D.		
Fluorene	700	430	N.D.		
Benanthrene	83	N.D.	N.D.		
Anthracene	160	N.D.	N.D.		
Fluoranthene	380	360	N.D.		
Pyrene	260	N.D.	N.D.		
Benzo (a) anthracene	14	N.D.	N.D.		
Benzene	14	N.D.	N.D.		
Ben (b) fluoranthene	N.D.	N.D.	N.D.		
Benzo (k) fluoranthene	N.D.	N.D.	N.D.		
Benzo (a) pyrene	N.D.	N.D.	N.D.		
Benzo (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.		
Benzo (a,h) anthracene	N.D.	N.D.	N.D.		
Benzo (g,h,i) perylene	N.D.	N.D.	N.D.		

Results expressed as parts-per-trillion (ng/l)

N.D. = Signal not observed or does not meet criteria for quantitation.

Detection limit for each PNA is 4 ng/l.

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC HYDROCARBONS

Sampling Equipment

Sampling resin beds used for organic enrichment are connected to a water source by an all-teflon manifold. The teflon manifold is designed to collect samples in duplicate by splitting sample flow with a tee to two resin beds. The inlet of the manifold is compatible with a 1/8" NPT female fitting on the water source. Two teflon needle valves (one on each side of the tee) are used to control water flow through the resin beds. A differential pressure of at least 20 psig is necessary for adequate flow control. When particulate levels are high, a teflon prefilter is placed upstream of the resin beds to remove particulates.

Sampling Procedure

Before sampling, all manifold parts are cleaned with HPLC-grade acetone and water. Preparation of the resin beds consists of flushing each with 4.0 ml HPLC-grade methanol, then 10.0 ml HPLC-grade water. One of the beds is spiked with isotope compounds in the laboratory. The spike level should be similar in concentration to the non-isotopic compounds being analyzed.

At the sampling site, the assembled teflon manifold and resin bed connections are leak-tested. The flow rate through each resin bed is adjusted using the flow valve and the sample flow volume maintained throughout sampling by periodic checks. The water after passing through each resin bed is collected in tared carboys. At the end of the sampling period, the water volume sampled is determined by weighing the carboy and water. At the completion of the sampling, the resin beds are wrapped in foil and kept refrigerated until analysis.

Resin Bed Elution

Each resin bed used to collect and concentrate polynuclear aromatic compounds is eluted using acidified tetrahydrofuran (THF). The acidified THF is then passed through a micro-drying column to remove water. The dried THF extract is collected in a 0.1 ml graduated vial. The micro-drying column is rinsed several times with acidified THF. The volume of acidified THF is reduced under a gentle stream of nitrogen at room temperature. Finally, the concentrated extract is spiked with an isotope internal standard (D_{10} anthracene).

GC/MS Analysis

The extracts are stored in suitable vials until ready for analysis. A 1 μ l aliquot is injected on the column in a splitless injection mode. Single ion monitoring data is continuously acquired and the data stored for later workup. Instrumental parameters are described in Table I.

Data Reduction - Quantitation

The single ion chromatograms are plotted for the characteristic ion of each polynuclear aromatic being analyzed. Areas are then obtained for any peak with a retention time falling within a one minute window relative to the

standard run. Confirmation of identity is based on presence of the EPA selected ions (see Table II) for the individual compound, and all ions must maximize within one scan of each other. Furthermore, the ions must meet spectral integrity criteria for relative ratios ($\pm 20\%$). The areas under each characteristic ion are used to determine the extract concentration. The areas are compared to the internal standard intensity based on the following formula.

$$\text{Concentration}_{\text{unk}} = \frac{(\text{Area}_{\text{unk}}) (\text{Conc}_{\text{IS}})}{(\text{Area}_{\text{IS}}) (\text{R.F.}_{\text{unk}}) (\text{Dilution})}$$

where: unk = priority pollutant being quantitated
IS = internal standard D₁₀ anthracene
R.F. = response factor for the particular compound

Recovery Determinations

A sample to be extracted is spiked with a surrogate standard (a deuterated analog). These materials are carried through the work-up procedure and quantitated along with the normal pollutants. The intensity of these spikes when compared to the area for D₁₀ anthracene added to the final extract allows a percent recovery to be determined for each extraction.

$$\text{Percent Recovery} = \frac{\text{Concentration of Spike Observed}}{\text{Concentration of Spike Added to Sample}} \times 100$$

Matrix Spikes

In addition, a matrix spike is analyzed with each set of samples. The material being extracted is spiked with a mixture of polyaromatic hydrocarbons appropriate for the fractions being analyzed. The recoveries of compounds in the spiking mix will provide information about the matrix effect of the sample on the analytical methodology. Individual component recoveries of the matrix are calculated as follows:

$$\text{Percent Recovery} = \frac{\text{SSR} - \text{SR}}{\text{SA}} \times 100$$

Where: SSR = Spike sample results ($\mu\text{g/g}$)
SR = Sample results ($\mu\text{g/g}$)
SA = Spike added ($\mu\text{g/g}$) from spiking mix

Duplicate Samples

Duplicate analyses are performed every 20 samples or one for each project, whichever is more frequent.

$$\text{Percent Difference} = \frac{D_1 - D_2}{(D_1 + D_2)} \times 100$$

Where: D_1 = First sample value
 D_2 = Second sample value (duplicate)

Detection Limits¹

The method detection limit is defined as the minimum concentration of a substance that can be identified, measured and reported with 99% confidence that the analyte concentration is greater than zero and is determined from replicate analysis of a sample of a given matrix containing analyte².

$$\text{MDL} = t (N-1, 1-\alpha = .99) \times S_c$$

Where: $t (N-1, 1-\alpha = .99)$ is students t value for one-tailed test at the 99% confidence level with $N-1$ degree of freedom.
 S_c is the standard deviation of replicate analyses.

The method detection limit refers to samples processed through all steps comprising an established analytical procedure.

¹Glaser, J.A., et al, "Trace Analyses for Wastewater," Environ. Sci. Tech., 15, 1426(1981).

²"Definition and Procedure for the Determination of the Method Detection Limit," Rev.1.12 45 EPA, Environmental Monitoring and Support Lab., Cincinnati, Jan. 1981.

The detection limit for each PNA is four parts-per-trillion in the well-water.

TABLE I

INSTRUMENT PARAMETERS

Polynuclear Aromatics Analysis

Gas Chromatograph

Hewlett Packard 5840 with HP7671A Autosampler
Column 30m x 0.24mm SE-54 Fused Silicon Capillary (J & W)
Column directly coupled to MS

Injection

Mode: Splitless
Sweep Initiation @ 0.5 minutes
Sweep Flow: 40ml/min. Helium
Carrier Flow: 1cm/sec. linear velocity

Temperatures

Injector: 275°
Temp. 1: 40°C for 3 minutes
Ramp: 10°C/minute
Temp. 2: 280°C for 20 minutes
Interface Temp: 275°C.
Injection Volume: 1 µl

Mass Spectrometer

Hewlett Packard 5985B GCMS
Electron Impact Mode: 70 eV
Delay: 10 minutes
SIM MODE
Dwell time: 100ms per ion
Multiplier Voltage: 2600V.
Source Temp. 225°C

Computer

Hewlett Packard 21MX-E
Disk Drives: HP7906 (20M byte) HP7920 (50M byte)
Tape Drive: Kennedy 9300 9-track dual density



TECHNICAL DATA

TABLE II

Ion (abundances)

<u>Compound</u>	<u>Primary</u>	<u>Confirming</u>	<u>R.T.</u>
Phthalene	128 (100)	127 (13)	12.8
Benzyne	152 (100)	151 (21)	16.8
Naphthene	154 (100)	153 (120)	17.2
Indorene	166 (100)	165 (94)	18.5
Anthracene	178 (100)	176 (20)	20.9
Thracene	178 (100)	176 (21)	21.0
Fluoranthene	202 (100)	101 (11)	23.9
ene	202 (100)	101 (14)	24.5
azo (a) anthracene	228 (100)	*	27.5
ysene	228 (100)	229 (19)	27.7
azo (j) fluoranthene	252 (100)	253 (23)	31.2
azo (k) fluoranthene	252 (100)	253 (22)	31.2
azo (a) pyrene	252 (100)	253 (24)	32.5
eno (1,2,3-c,d) pyrene	276 (100)	*	38.9
enzo (a,h) anthracene	278 (100)	*	39.0
o (g,h,i) perylene	276 (100)	*	40.6

o Secondary ion designated

TABLE III.

% RECOVERIES OF DEUTERATED SPIKES

<u>Compound</u>	Well #4A CAP #11646			Well #6 CAP #11458		
	<u>Total ng Spiked</u>	<u>Total ng Recovered</u>	<u>% Recovery</u>	<u>Total ng Spiked</u>	<u>Total ng Recovered</u>	<u>% Recovery</u>
D ₈ -Naphthalene	1077	54	5.0	108	10	9.0
D ₁₀ -Phenathrene	1286	3600	280	129	180	140
D ₁₀ -Pyrene	1085	2170	200	109	229	210
D ₁₂ -Chrysene	1110	3100	290	111	144	130

<u>Compound</u>	Well #11 CAP #11459			Well #14A CAP #11462		
	<u>Total ng Spiked</u>	<u>Total ng Recovered</u>	<u>% Recovery</u>	<u>Total ng Spiked</u>	<u>Total ng Recovered</u>	<u>% Recovery</u>
D ₈ -Naphthalene	269	43	16	1077	690	64
D ₁₀ -Phenanthrene	322	322	100	1286	2440	190
D ₁₀ -Pyrene	271	488	180	1085	2600	240
D ₁₂ -Chrysene	278	360	130	1110	2000	180

3/8/82
N.



NORTHBROOK OFFICE COURT
SUITE 1502
666 WEST DUNDEE ROAD
NORTHBROOK, IL 60062
PHONE: 312-498-9090

8 March 1982

Mr. Paul Bitter, OSC
Superfund Sites Section
USEPA Region V
230 S Dearborn
Chicago, Illinois 60604

Re: Carbon Isotherm Data for
Selected PAH Compounds

Dear Paul:

Enclosed are the tables and the associated figure which summarize the analysis of the carbon isotherm data of Hickok and the USEPA. The data analyzed appeared in Table 6 of the E.A. Hickok and Assoc. Report "Drinking Water Treatment and Evaluation for St. Louis Park, MN. April 1981". This data was compared to USEPA carbon isotherm data for one PAH compound, Fluoranthene. The comparison was performed for this compound since a X/M relationship existed for all carbon dosages used by Hickok in their analysis.

I trust that this information will be of help to you. Should you have further questions, feel free to call me.

Very truly yours,

ROY F. WESTON, INC.

Robert J. Millman, P.E.

RJM:cls

Enclosure

cc: R. Schoenberger
P. Lederman

FIGURE 1

EXAMPLE ADSORPTION OF PAH USING FLUORANTHENE CONTACTED WITH PAC




TABLE 1

CARBON ISOTHERM DATA FOR COMPOUNDS AS LISTED IN TABLE 6
HICKOK REPORT, APRIL 1981

<u>PAC Dosage Applied</u>	<u>PAC 15 mg/l</u>			<u>PAC 11 mg/l</u>		
<u>Compound</u>	<u>Raw</u> <u>ng/l</u>	<u>Tr.</u> <u>ng/l</u>	<u>X/M</u> <u>ng/mg</u>	<u>Raw</u> <u>ng/l</u>	<u>Tr.</u> <u>ng/l</u>	<u>X/M</u> <u>ng/mg</u>
Acenaphthene	1087	30	70.47	-	35	-
Acenaphtylene	250	11.5	15.90	4.3	4	0.03
Anthracene	613	4	40.60	492	4	44.36
Benzo(a) Anthracene	13	0.5	0.83	0.5	0.5	-
Benzo(a) Pyrene	0.5	0.5	-	0.5	0.5	-
Benzo(ghi) Perylene	2	2	-	2.5	2.5	-
Chrysene	6.5	6.5	-	3	3	-
Dibenzo(ah) Anthracene	0.5	0.2	0.02	1	1	-
Fluorene	121	1	8.00	217	4.5	19.32
Fluoranthene	1220	4	81.07	391	2	35.36
Napthalene	130	5.5	8.30	2	2	-
Phenanthrene	360	4.5	23.70	101	3	8.91
Pyrene	9	8	0.07	535	0.5	48.59
Benzo(k) Fluoranthene	0.15	0.15	-	0.5	0.5	-

NOTE: X/M - Unit of material adsorbed per unit of Carbon (ng/Mg)
Tr. - Treated water

TABLE 1(continued)

CARBON ISOTHERM DATA FOR COMPOUNDS AS LISTED IN TABLE 6
HICKOK REPORT, APRIL 1981

<u>PAC Dosage Applied</u>	<u>PAC 8 mg/l</u>			<u>PAC 5.5 mg/l</u>		
<u>Compound</u>	<u>Raw</u> <u>ng/l</u>	<u>Tr.</u> <u>ng/l</u>	<u>X/M</u> <u>ng/mg</u>	<u>Raw</u> <u>ng/l</u>	<u>Tr.</u> <u>ng/l</u>	<u>X/M</u> <u>ng/mg</u>
Acenaphthene	35	35	-	34	34	-
Acenaphtylene	4	4	-	95	95	-
Anthracene	4	4	-	23	23	-
Benzo(a) Anthracene	3.5	9.9	-	26	0.2	4.69
Benzo(a) Pyrene	2	0.5	0.19	32	1	5.64
Benzo(ghi) Perylene	0.5	0.5	-	25	0.8	4.40
Chrysene	9.2	2.1	0.89	2.2	2.2	-
Dibenzo(ah) Anthracene	1.5	1.4	0.01	6.6	1.5	0.93
Fluorene	4.5	4.5	-	0.65	0.65	-
Fluoranthene	403	6.3	49.59	270	14	46.55
Napthalene	2	2	-	38.5	38.5	-
Phenanthrene	3	3	-	7.5	7.5	-
Pyrene	22	2.5	2.44	2.5	2.5	-
Benzo(k) Fluoranthene	-	-	-	0.9	0.9	-

NOTE: X/M - Unit of material adsorbed per unit of Carbon (ng/Mg)
Tr. - Treated water

TABLE 2

CARBON ISOTHERM
COMPOUND: FLUORANTHANE

<u>Carbon Dose mg/l</u>	<u>Treated mg/l</u>	<u>Removed mg/l</u>	<u>X/M mg/gm</u>
0	0.0581	-	-
1.0	0.0140	0.0567	44.1
2.5	0.0014	0.0567	22.7
5	0.0008	0.0573	11.5
7.5	0.0012	0.0569	7.6
12.5	0.005	0.0576	4.6

Initial pH = 5.3

Source: EPA Publication 600/8-80-0203 pg. 207
"Carbon Adsorption Isotherms for
Toxic Organics", April 1981

3/2/82
N.

A Complete Concept in Consultation



CAPSULE LABORATORIES

A Division of Economics Laboratory, Inc.
Research & Development Center
840 Sibley Memorial Hwy. St. Paul, MN 55118 ■ (612) 457-4926

Cherh memories

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC
HYDROCARBONS IN MUNICIPAL WATER
WELLS FOR THE
CITY OF ST. LOUIS PARK

Prepared by:

CAPSULE LABORATORIES
605 West County Road E
Shoreview, Minnesota 55112

Date Submitted:

March 2, 1982

Analysis of Polynuclear aromatics*

Compound	Well #3 Capsule # 11645	Well #4A Capsule # 11646 (spiked)	Well #4B Capsule # 11647	Well #6 Capsule # 11458	Well #8 Capsule # 11648
Naphthalene	N.D. **	N.D.	5	N.D.	N.D.
Acenaphthylene	N.D.	N.D.	N.D.	N.D.	N.D.
Acenaphthene	N.D.	60	92	N.D.	N.D.
Fluorene	N.D.	26	46	N.D.	N.D.
Phenanthrene	N.D.	N.D.	N.D.	N.D.	N.D.
Acenaphthene	N.D.	7	N.D.	N.D.	N.D.
Fluoranthene	N.D.	N.D.	6	N.D.	N.D.
Pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Chrysene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (b) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (k) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a,h) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (g,h,i) perylene	N.D.	N.D.	N.D.	N.D.	N.D.

Results expressed as parts-per-trillion (ng/l)

N.D. = Signal not observed or does not meet criteria for quantitation.

Analysis of Polynuclear aromatics*

Compound	Well #11 Capsule # 11459	Well #12 Capsule # 11460	Well #13 Capsule # 11461	Well #14A Capsule # 11462 (spiked)	Well #14B Capsule # 11463
Naphthalene	N.D. **	N.D.	N.D.	8	5
Acenaphthylene	N.D.	N.D.	N.D.	N.D.	N.D.
Acenaphthene	N.D.	N.D.	N.D.	N.D.	N.D.
Fluorene	N.D.	N.D.	N.D.	43	6
Phenanthrene	N.D.	N.D.	N.D.	N.D.	N.D.
Acracene	N.D.	N.D.	N.D.	28	N.D.
Fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Chrysene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (b) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (k) fluoranthene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Indeno (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (a,h) anthracene	N.D.	N.D.	N.D.	N.D.	N.D.
Benzo (g,h,i) perylene	N.D.	N.D.	N.D.	N.D.	N.D.

Results expressed as parts-per-trillion (ng/l)

N.D. = Signal not observed or does not meet criteria for quantitation.

Analysis of Polynuclear aromatics*

Compound	Well #15A Capsule # 11464 (Spiked)	Well #15B Capsule # 11465	Well #16 Capsule # 11649		
Naphthalene	4	N.D.**	N.D.		
Acenaphthylene	70	N.D.	N.D.		
Acenaphthene	41	N.D.	N.D.		
Fluorene	700	430	N.D.		
Phenanthrene	83	N.D.	N.D.		
Anthracene	160	N.D.	N.D.		
Fluoranthene	380	360	N.D.		
Pyrene	260	N.D.	N.D.		
Benzo (a) anthracene	14	N.D.	N.D.		
Chrysene	14	N.D.	N.D.		
Benzo (b) fluoranthene	N.D.	N.D.	N.D.		
Benzo (k) fluoranthene	N.D.	N.D.	N.D.		
Benzo (a) pyrene	N.D.	N.D.	N.D.		
Indeno (1,2,3-c,d) pyrene	N.D.	N.D.	N.D.		
Benzo (a,h) anthracene	N.D.	N.D.	N.D.		
Benzo (g,h,i) perylene	N.D.	N.D.	N.D.		

*Results expressed as parts-per-trillion (ng/l)

* N.D. = Signal not observed or does not meet criteria for quantitation.

GC/MS ANALYSIS OF POLYNUCLEAR AROMATIC HYDROCARBONS

Sampling Equipment

Sampling resin beds used for organic enrichment are connected to a water source by an all-teflon manifold. The teflon manifold is designed to collect samples in duplicate by splitting sample flow with a tee to two resin beds. The inlet of the manifold is compatible with a 1/8" NPT female fitting on the water source. Two teflon needle valves (one on each side of the tee) are used to control water flow through the resin beds. A differential pressure of at least 20 psig is necessary for adequate flow control. When particulate levels are high, a teflon prefilter is placed upstream of the resin beds to remove particulates.

Sampling Procedure

Before sampling, all manifold parts are cleaned with HPLC-grade acetone and hexane. Preparation of the resin beds consists of flushing each with 4.0 ml HPLC-grade methanol, then 10.0 ml HPLC-grade water. One of the beds is spiked with isotope compounds in the laboratory. The spike level should be similar in concentration to the non-isotopic compounds being analyzed.

At the sampling site, the assembled teflon manifold and resin bed connections are leak-tested. The flow rate through each resin bed is adjusted using the flow valve and the sample flow volume maintained throughout sampling by periodic checks. The water after passing through each resin bed is collected in tared carboys. At the end of the sampling period, the water volume sampled is determined by weighing the carboy and water. At the completion of the sampling, the resin beds are wrapped in foil and kept refrigerated until analysis.

Resin Bed Elution

Each resin bed used to collect and concentrate polynuclear aromatic compounds is eluted using acidified tetrahydrofuran (THF). The acidified THF is then passes through a micro-drying column to remove water. The dried THF extract is collected in a 0.1 ml graduated vial. The micro-drying column is rinsed several times with acidified THF. The volume of acidified THF is reduced under a gentle stream of nitrogen at room temperature. Finally, the concentrated extract is spiked with an isotope internal standard (D₁₀ anthracene).

GC/MS Analysis

The extracts are stored in suitable vials until ready for analysis. A 1 µl aliquot is injected on the column in a splitless injection mode. Single ion monitoring data is continuously acquired and the data stored for later workup. Instrumental parameters are described in Table I.

Data Reduction - Quantitation

The single ion chromatograms are plotted for the characteristic ion of each polynuclear aromatic being analyzed. Areas are then obtained for any peak with a retention time falling within a one minute window relative to the

standard run. Confirmation of identity is based on presence of the EPA selected ions (see Table II) for the individual compound, and all ions must maximize within one scan of each other. Furthermore, the ions must meet spectral integrity criteria for relative ratios ($\pm 20\%$). The areas under each characteristic ion are used to determine the extract concentration. The areas are compared to the internal standard intensity based on the following formula.

$$\text{Concentration}_{\text{unk}} = \frac{(\text{Area}_{\text{unk}}) (\text{Conc}_{\text{IS}})}{(\text{Area}_{\text{IS}}) (\text{R.F.}_{\text{unk}}) (\text{Dilution})}$$

where: unk = priority pollutant being quantitated
 IS = internal standard D₁₀ anthracene
 R.F. = response factor for the particular compound

Recovery Determinations

Each sample to be extracted is spiked with a surrogate standard (a deuterated analog). These materials are carried through the work-up procedure and quantitated along with the normal pollutants. The intensity of these spikes when compared to the area for D₁₀ anthracene added to the final extract allows a percent recovery to be determined for each extraction.

$$\text{Percent Recovery} = \frac{\text{Concentration of Spike Observed}}{\text{Concentration of Spike Added to Sample}} \times 100$$

Matrix Spikes

In addition, a matrix spike is analyzed with each set of samples. The material being extracted is spiked with a mixture of polyaromatic hydrocarbons appropriate for the fractions being analyzed. The recoveries of compounds in the spiking mix will provide information about the matrix effect of the sample on the analytical methodology. Individual component recoveries of the matrix spike are calculated as follows:

$$\text{Percent Recovery} = \frac{\text{SSR} - \text{SR}}{\text{SA}} \times 100$$

Where: SSR = Spike sample results ($\mu\text{g/g}$)
 SR = Sample results ($\mu\text{g/g}$)
 SA = Spike added ($\mu\text{g/g}$) from spiking mix

Duplicate Samples

Duplicate analyses are performed every 20 samples or one for each project, whichever is more frequent.

$$\text{Percent Difference} = \frac{D_1 - D_2}{(D_1 + D_2)} \times 100$$

Where: D_1 = First sample value
 D_2 = Second sample value (duplicate)

Detection Limits¹

The method detection limit is defined as the minimum concentration of a substance that can be identified, measured and reported with 99% confidence that the analyte concentration is greater than zero and is determined from replicate analysis of a sample of a given matrix containing analyte².

$$\text{MDL} = t (N-1, 1-\alpha = .99) \times S_c$$

Where: $t (N-1, 1-\alpha = .99)$ is students t value for one-tailed test at the 99% confidence level with $N-1$ degree of freedom.
 S_c is the standard deviation of replicate analyses.

The method detection limit refers to samples processed through all steps comprising an established analytical procedure.

¹Glaser, J.A., et al, "Trace Analyses for Wastewater," Environ. Sci. Tech., 15, 1426(1981).

²"Definition and Procedure for the Determination of the Method Detection Limit," Rev.1.12 45 EPA, Environmental Monitoring and Support Lab., Cincinnati, Jan. 1981.

TABLE I

INSTRUMENT PARAMETERS

Polynuclear Aromatics Analysis

Gas Chromatograph

Hewlett Packard 5840 with HP7671A Autosampler
Column 30m x 0.24mm SE-54 Fused Silicon Capillary (J & W)
Column directly coupled to MS

Injection

Mode: Splitless
Sweep Initiation @ 0.5 minutes
Sweep Flow: 40ml/min. Helium
Carrier Flow: 1cm/sec. linear velocity

Temperatures

Injector: 275°
Temp. 1: 40°C for 3 minutes
Ramp: 10°C/minute
Temp. 2: 280°C for 20 minutes
Interface Temp: 275°C.
Injection Volume: 1 µl

Mass Spectrometer

Hewlett Packard 5985B GCMS
Electron Impact Mode: 70 eV
Delay: 10 minutes
SIM MODE
Dwell time: 100ms per ion
Multiplier Voltage: 2600V.
Source Temp. 225°C

Computer

Hewlett Packard 21MX-E
Disk Drives: HP7906 (20M byte) HP7920 (50M byte)
Tape Drive: Kennedy 9300 9-track dual density

TABLE IIIon (abundances)

<u>Compound</u>	<u>Primary</u>	<u>Confirming</u>	<u>R.T.</u>
Naphthalene	128 (100)	127 (13)	12.8
Acenaphthylene	152 (100)	151 (21)	16.8
Acenaphthene	154 (100)	153 (120)	17.2
Fluorene	166 (100)	165 (94)	18.5
Phenanthrene	178 (100)	176 (20)	20.9
Anthracene	178 (100)	176 (21)	21.0
Fluoranthene	202 (100)	101 (11)	23.9
Pyrene	202 (100)	101 (14)	24.5
Benzo (a) anthracene	228 (100)	*	27.5
Chrysene	228 (100)	229 (19)	27.7
Benzo (b) fluoranthene	252 (100)	253 (23)	31.2
Benzo (k) fluoranthene	252 (100)	253 (22)	31.2
Benzo (a) pyrene	252 (100)	253 (24)	32.5
Indeno (1,2,3-c,d) pyrene	276 (100)	*	38.9
Benzo (a,h) anthracene	278 (100)	*	39.0
Benzo (g,h,i) perylene	276 (100)	*	40.6

* No Secondary ion designated

PAH Samples
St. Louis Park, Minnesota
Municipal Raw Water Samples

Date Collected: December 9, 1981

Field #

Municipal Well #

1 g

13

(code as #17)

2 g

13

3 g

14

4 l

14

5 l

14

6 l

14

7 g

14

8 g

16

SLP 13

= Municipal Well #

1

= Field #

PAH Samples
St. Louis Park, Minnesota
Municipal Raw Water Samples

Date Collected December 9, 1981

Field number	Municipal Well number
1	17
2	15
3	14
4	14
5	14
6	14
7	14
8	16

recorded on both
follows

SLP 15 = municipal
well no.
2 = field no.

Eight municipal raw water samples were collected on December 9, 1981 from the St. Louis Park, Mn. municipal water system. The samples were collected between 1 p.m. and 3 p.m. according to standard methods Department of Health. The samples were placed in 2 liter ice chests and packed with ice. The samples were turned over to Rick Ferguson at 4:30 p.m. December 9, 1981.

Richard J. Ferguson took possession at 4:30 pm on December 9, 1981.

Samples were left with him at 5:00 pm for pick up at 5:15 by Federal Express.



RECEIVED

JUL 01 1982

CROSS REFERENCE LIST OF WATER SAMPLES RECEIVED FOR PAH ANALYSIS

(EPA Contract No. 68-01-6316)

(GCA 1-452-124)

Sampling date	Sample code	GCA Control No.
1/13/82	UM-827	18825
	UM-840	18826
	UM-847	18827
	UM-859	18828
	Ford Dam	18829
1/19/82	Field Blank (1/19/82)	18931
	EFF E	18932
	EFF W	18933
	Ford Dam	18934
	Gray Cloud	18935
	INF	18936
	UM-827	18937
	UM-840	18938
	UM-847	18939
	UM-859	18940
1/21/82	Field Blank (1/21/82)	18977
	EFF E	18978
	EFF W	18979
	INF E	18980
	INF ISCO	18981
1/26/82	Field Blank (1/26/82)	19099
	INF E	19100
	INF E ISCO	19101
	EFF E	19102
	EFF W	19103
1/28/82	Field Blank (1/28/82)	19157
	EFF E II ^o	19158
	EFF W II ^o	19159
	INF E I ^o	19160
	INF I ^o E ISCO	19161